


MACHINERY

BROADBENT VERTICAL BORING and TURNING MILLS



These are the double column type and manufactured in sizes 5ft., 6ft., 8ft. and 10ft. table diameter. They can be supplied with right and left hand rams, or, if required, with pentagon turret on right and side. The table is supported on large diameter white metal vee bearing, and is driven through a 2 speed gearbox.




HENRY BROADBENT LIMITED
Sowerby Bridge Yorkshire Telephone Halifax 81331

A COMPANY IN THE KERRY GROUP

H.A.P.

TRADE SERVICE
BROACHING SPLINING & GEAR CUTTING
now includes the Generation of
PRECISION RACKS



INDLE UTO RODUCTS LTD


HAPCO WORKS · CALEDONIA STREET · BRADFORD 5
Phone: BRADFORD 27234-5-6 Grams: HAPCO, BRADFORD

Brayshaw Engineers' Tools
include standard and special
Milling Cutters for all
purposes. . . .

Hacksaw Blades, Gears,
Threads and Splines, Inserted
Blade and Interlocking
Cutters, Woodworking
Cutters, Tools, Hobs,
Reamers, Slitting Saws,
Form Tools, etc.

All tools are precision made
and scientifically hardened,
ensuring accuracy and
maximum productive effort.


Send for your copy of
Catalogue ST. 56 which
includes useful reference to
the design and use of
Milling Cutters.



*Tool Finished and
Profile Ground Hobs*

BRAYSHAW ENGINEERS' TOOLS

BRAYSHAW TOOLS LIMITED
BELLE VUE WORKS, MANCHESTER, 12
Telephone: East 1046 Telegrams: "Hardening." M c.



Wimet


**DRILLS AND
REAMERS**

WICKMAN LIMITED
WIMET DIVISION, TORRINGTON AVENUE, COVENTRY
Telephone: Tfr 310 6621

ANNOUNC

**THE NEW
HAYES
TRACEMASTER**

**FOR 360°
PROFILE
MILLING**



**HAYES
ENGINEERS
(LEEDS) LTD**



GELDERD ROAD, LEEDS 12

Tel: 39741 Grams: Toolmaker, Leeds 12

Sole Selling Agents for Home and Overseas:

**ASSOCIATED BRITISH MACHINE
TOOL MAKERS LTD.**

17 Grosvenor Gardens, London S.W.

When answering advertisements kindly mention MACHINERY.



**The New
COMBINED High Speed SHEARS & NIBBLER**

Type ASQ-8

FOR 5/16" PLATE (NIBBLING TO 1/4")



Starting from anywhere in the sheet, this machine will nibble or shear any shape to line or template. Edges are left clean and true.

HENRY PELS & CO. LIMITED

Offices & Showroom 32-38 OSNABURGH STREET · LONDON · N.W.1


Telephone: EUSTON 4113

When answering advertisements kindly mention MACHINERY.

NRP 1741

A2

ROTAX RECIRCULATING BALL THREADS




OVER 90% EFFICIENT

Now you can benefit from the advanced engineering that has produced assemblies for Britain's finest aircraft. For Rotax recirculating ball threads and nuts are now available for general use.

Wide range...
completely reversible
You'll find the ball thread assembly to meet your exact need in the wide range Rotax offer. All ball threads and nuts are completely reversible. They are stabilised and made of special materials which ensure that they remain accurate indefinitely. Ball tracks are 60 Rockwell C scale hard. Nuts and screws are ground to a finish of 8 micro inches and free from back lash.
Mechanical efficiency.....
.....over 90%
Load carrying capacity.....
.....up to 40 tons

Thread length on shaft.....
.....to your requirement
Shaft diameter.....up to 4"
Pitch.....to your requirement
Working temperature ranges
.....between -70 °C and 800 °C
Minimum P.C.D.....
.....to your requirement
Overall length.....
.....to your requirement
Length/dia. ratio
25 : 1 max. ratio recommended
Pitch error per ft.....
.....+0.0002" according to
.....total length
Life 40 million reversals before
re-lubrication and accord-
ing to load.


ROTAX DRY PARTICLE
MAGNETIC CLUTCH



For further information on Rotax recirculating ball threads, linear ball mechanisms and dry particle magnetic clutches please write or phone.



WILLESDEN JUNCTION, LONDON, N.W.10. (Elgar 7777)





FORGING MACHINES
FORGING PRESSES
BULLDOZER BENDING MACHINES
FORGING ROLLS
SPECIAL MACHINES

TH. KIESERLING & ALBRECHT SOLINGEN
GERMANY

OUR MANUFACTURING PROGRAMME SECTION B

Special Machines for Forging Shops





made to measure

... in all workshops

Universal Measuring Support Type U-10

Precision-built, versatile and robust, the U-10 Measuring Support with its wide range of accessories brings to even the smallest workshop the assurance of speedier, more accurate inspection of machined parts.

Reversed scope. The U-10 Support is used for measuring flat and cylindrical parts, balls and diameters of threads by comparison with a standard or reference gauge. Accessories permit inspection of angles and tapered surfaces, vertical measurement in absolute values and measurement in rectangular and polar coordinates in a horizontal plane.

Portable. Lightweight and of compact design, the U-10 Support presents no transport problems. It is easily on the inspection

bench and can be quickly moved from workshop to workshop.

The U-10 Measuring Support is one of the measuring instruments in the manufacturing programme of Société Générale d'Instrumentation & Physique.

Others are:

MUL-1000, MUL-5000 and MUL-4000 Universal Measuring Machines of 1, 3 and 6 inches linear capacity.

MUL-250 Slip Gauge Measuring Machine, MU-214B Three Co-ordinate Universal Measuring Machine.

Detailed information about SGP Measuring Machines is available from Société Générale d'Instrumentation & Physique, S.A., 1, rue de la République, Paris, 11.
Telephone: 4-001-1.



Measuring Machines by



the Masters of Measured

When answering advertisements kindly mention MACHINERY.

Casting NO DOUBTS



Non-ferrous Foundrywork

HEAVY, MEDIUM and LIGHT SAND CASTINGS

IN ALUMINIUM BRONZES—MANGANESE BRONZES
NICKEL BRONZES—PHOSPHOR BRONZES
GUN METALS—ALUMINIUM, ETC.


PATTERN MAKING & MACHINING

CHILL CAST SOLID and CORED BARS



J. T. Price & Co.
(BRASS & ALUMINIUM FOUNDERS) LTD.

NEWCASTLE STAFFS • phone 52311 (3 lines)



made to measure

... in all workshops

Universal Measuring Support Type U-10

Precise, light, versatile and mobile, the U-10 Measuring Support with its wide range of accessories brings to even the smallest workshop the assurance of a smaller, more accurate inspection of machined parts.

Universal Scope The U-10 Support is used for measuring flat and cylindrical parts, balls and diameters of threads by comparison with standard or reference parts. Accessories permit inspection of angles and thread position, vertical measurement in absolute value and measurement in rectangular and polar co-ordinates in a horizontal plane.

Portable Lightweight and of compact design, the U-10 Support presents no transport problem. It sits easily on the inspection

bench and can be quickly moved from workshop to workshop.

The U-10 Measuring Support is one of several measuring instruments in the manufacturing programme of Société Générale d'Instruments de Précision.

Others are:

MUL-1000, MUL-3000 and MUL-4000 Universal Measuring Machines of 1, 3 and 4 metre linear capacity.

MUL-350 Shop Gauge Measuring Machine.

MU-2-4B Three Co-ordinate Universal Measuring Machine.

Details information from: *SIP Measuring Machines is available from Société Générale d'I.I., Newport Road, Bude, Telephone: 2503/2.*

Measuring Machines by




the Masters of Measurement

When answering advertisements kindly mention MACHINERY.

FIRST IN THE FIELD—AND STILL IN THE LEAD

The Pre-fabricated
Drilling Platform under
construction, showing
the bow end.



Once again...


LINCOLNWELD SUBMERGED ARC WELDING UNITS ARE CHOSEN IN PREFERENCE TO ALL OTHERS

The first of its kind to be built in Great Britain, the 4,800 ton marine oil drilling platform being constructed at Southampton by STEEL STRUCTURES LTD., in association with John Howard & Co. Ltd., of London, and the De Long Corporation of New York is extensively LINCOLNWELDED.

LINCOLNWELD Fully Automatic Submerged Arc Welding Units using Lincolnweld Wire and Flux have been extensively employed for the fabrication of the platform, the all-welded hull (200 ft. long, 106 ft. wide and 16 ft. deep), the Caisson Shells and the Jacking Bars.

Lincoln Improved Fleetweld 5 electrodes were used for the handwelding of the root runs on the Caisson Shells and Lincoln Jetweld Iron powder electrodes for the manual welds on the Jacking Bars.

Hundreds of LINCOLN Automatic Welding Units are in use throughout the world. May we advise on *your* problem? Write or telephone The Automatic Division.



LINCOLN ELECTRIC CO LTD

WELWYN GARDEN CITY HERTS

Welwyn Garden 920 (5 lines) 4581 (5 lines)



Gear Hardening is one of the several production line operations for which Induction Heating is admirably suited. The right way to tackle the problem is to ask Delapena to put their Applications Department at your disposal.

Getting your teeth into the problem




They will show, with particular reference to *your* manufacturing needs, how costs can be reduced by the elimination of grinding operations; how tooth profile can be finally hardened with the minimum of 'shape change'; and how a quieter and longer-lasting gear results.



To problems of repeat Hardening, Soldering and Brazing, Delapena Induction Heating Equipment can provide an economical answer.

Consult us now. Let us get *our* teeth into *your* problem.



This equipment, for example, is fully automatic and handles gears within a range of 1½" to 26" diameter, 2 to 10 diametral pitch, face widths up to 8" and helical gears up to 30°.




INDUCTION HEATING

DELAPENA & SON LIMITED

Manufacturers of Induction Heating and Precision Honing Equipment


ZONA WORKS • CHELTENHAM • ENGLAND

Telephone: CHELTENHAM 56341



When answering advertisements kindly mention MACHINERY.

same size—same weight



...but **this motor** gives **far more power**

The new 'ENGLISH ELECTRIC' standardised ventilated motors using class 'E' insulation and built to the latest B.S. specification 2960/1958 give far more power for the same frame size. For a given horsepower the motor required is smaller and lighter and costs less.

These new motors—from $\frac{1}{2}$ h.p. to 50 h.p. in six frame sizes—have endshields and terminal boxes which turn to any of four 90° positions for floor, wall, or ceiling mounting. Publication DM/239 giving details of the range will be sent on request.

Most sizes AVAILABLE FROM STOCK

STANDARDISED AND INTERCHANGEABLE

'ENGLISH ELECTRIC'

B.S.D. ventilated motors

THE ENGLISH ELECTRIC COMPANY LIMITED, MARCONI HOUSE, STRAND, W.C.2
Industrial Motor Works, Bradford

WORKS: STAFFORD · PRESTON · RUGBY · BRADFORD · LIVERPOOL · ACCRINGTON
DM.67AL5

When answering advertisements kindly mention MACHINERY.



Incanite

FOR HIGH QUALITY MACHINE TOOLS

- (1) Sykes 5E gear generating machine cutting a gear 46 in. diameter and 12 in. face width.
- (2) Casting for Sykes gear generator; weight 2 tons 7 cwts.
- (3) Bed for Sykes 5E machine; weight 5 tons.

The 5E horizontal gear generating machine the largest built by W. E. Sykes Ltd., is known and used all over the world. It is designed to produce gears up to 66 inches diameter and with a face width up to 18 inches. Although specifically designed for cutting double helical gears, it is admirable for cutting double helical gears with straight or helical teeth. The machine tool builder appreciates the close structure and excellent machinability of Incanite which give fast and economical finishing, with consistent reliability in service.

Incanite

the special process cast iron
THE INCANDESCENT HEAT CO. LTD.
 Smethwick · England

The Publicity Department,
 The Incandescent Heat Co. Ltd.,
 Cornwall Road, Smethwick, 40, Staffs.

Dear Sirs, We are interested in Incanite and we should be pleased if you would

- (a) send your new Incanite leaflet
 (b) ask your representative to call

Name
 Position
 Company
 Address

Here is your copy of the
RICHARD LLOYD
Cutting Tools
Catalogue

CUTTING TOOLS

Richard Lloyd Limited

This 60 page Catalogue contains full specifications of a wide range of engineers' cutting tools, including the following—
Twist Drills, Centre Drills,
Core Drills, Reamers,
End Mills, Milling Cutters,
Slitting Saws and useful
technical data.


Richard Lloyd Limited

GALTON HOUSE, ELMFIELD AVENUE, TYBURN, BIRMINGHAM, 24

Telephone: Ashfield 1801, Telegrams "Cogs, Birmingham"

Northern Area Office: Britannia House, Wellington Street, Leeds 1. Telephone: Leeds 2122
London Area Office: 240 Romford Road, Forest Gate, London, E.7 Telephone: Maryland 7304-5

When answering advertisements kindly mention MACHINERY.



**WITH MOTORIZED
CHIP-BREAKER
GROOVE GRINDING
UNIT**

EQUIPPED WITH UNIVERSAL TOOLHOLDER

The Chip-breaker Groove Grinding Unit on the Abwood CG2/CB accommodates almost every shape and size of turning tool. Its robust design allows accurate grinding of grooves of desired radius and size with extreme accuracy and perfect finish.

**UTILIZES DIAMOND WHEELS TO THEIR
MAXIMUM EFFICIENCY**

The ABWOOD range of Carbide Tool Grinders includes:

MODEL No.	WHEEL SIZES	AVAILABLE WITH:
CG0	6in.	Bench or Pedestal.
CG1	8in.	
CG2	8in.	{ Chipbreaker Grooving Attachment.
CG3	12in.	
CG2 CB	8in.	{ Motorised Chip-breaker Unit
CG3 CB	12in.	

ABWOOD MACHINE TOOLS LTD., 100 MILLERS RD., DARTFORD, KENT


Telephone : Dartford 5271 (5 lines)



Telegrams : ABWOOD, DARTFORU

C9/1

When answering advertisements kindly mention MACHINERY.



All standard types in stock

... for precision lathes, watchmakers lathes, milling machines, drilling machines, etc. Crawfords, specialists in collets for more than sixty years, can supply collets of every size and shape, all standard types being held in stock—and specials can always be made to your specifications. Write now for further details.


CRAWFORD COLLETS LIMITED

WITNEY · OXON · TELEPHONE WITNEY 334


London Stockists: Acbars Limited, 16-18, Macleod Street, Walworth Road, London, S.E.17. RODney 7191.
 Midland Stockists: Retseip Engineering Ltd., Vulcan Road, Industrial Site, Lode Lane, Solihull, Birmingham. Solihull 2239.
 Agents or South-West England & Wales: W. O. Bullock & Sons Ltd., 126, Rodbourne Road, Swindon, Wilts. Telephone: Swindon 6331.
 Agents for Scotland: R. McSkimming & Co., 65, West Regent Street, Glasgow, C.2. Telephone: DOUglas 7391-2.

When answering advertisements kindly mention MACHINERY.

Set-ups for any number and type of Unit Heads from the small U.H.O. to the larger U.H.4. Milling type heads are available in standard equipment.



Single and Double ended BILLET DRILLING MACHINES



Enquiries are invited and if you have a production problem our Design Engineers will gladly collaborate with you.

DESIGNED AND BUILT FROM STANDARD UNIT PARTS


A.M.T. (B'HAM) LTD., Bournbrook, Birmingham. Tel.: Selly Oak 1128/9/20. Grams: 'Amtold' B'ham.

When answering advertisements kindly mention MACHINERY.

THIS IS NEW!

100% ACCURACY AND FINISH

- ★ Adaptability
- ★ Low Capital Outlay
- ★ Space Saving
- ★ Integral Cam Feed
- ★ Super Precision Bearings



The FB4F Fine Boring Unit Head illustrated above incorporates an independent feed motion, transmitted to its spindle quill through a simple plate cam, which can be designed to give a fast approach and varying rates of feed. The robust spindle and quill, together with super precision spindle bearings, ensure a high degree of finish and roundness.

These self contained units are readily adaptable for a wide variety of applications without need for costly set ups.

Particularly suitable for mounting on simple base plates together with the necessary work holding fixture enabling single purpose units to be constructed for the minimum of time and cost. Wide range of speeds and feeds obtainable by changing feed cam and motor pulley.

"Descriptive brochure on request."


Manufactured by:—

High Precision Equipment Ltd

DESIGNERS AND MANUFACTURERS OF SPECIAL
MACHINE TOOLS

BLETCHLEY BUCKS

Phone: BLETCHLEY 3403/4/5



For Maximum Production on Capstan and Turret Lathes

INSTALL




Illustration shows
the No. 3C
Capstan Lathe
1½ in. bar capacity

Many new features include
12 spindle speeds — both forward and reverse
Higher centres giving increased swing
Bed protected by stainless steel covers
Inbuilt electrical equipment
Large capacity swarf pan

Full details of our
complete range of
Capstan and Turret
Lathes on request.

H. W. WARD & CO
LTD

SELLY OAK
BIRMINGHAM 29
TELEPHONE SELLY OAK 1131






Table	46 in. x 18 in.
Longitudinal Feed	25 in.
Cross Feed	7 in.
Spindle Centre to Table Top, max.	18 in.
Table Swivel each side of centre	45 deg.
Spindle Speeds (12)	29-775 r.p.m.


SEND FOR BROCHURE
M 9

J PARKINSON & SON (SHIPLEY) LTD

SHIPLEY
TELEPHONE



YORKSHIRE
53231

SWEET-**or dry?**

The choice of bearings — whether they will operate sweetly or run dry in locations where constant and frequent attention is impossible — has a ready answer: COMPO. These oil-retaining sintered metal bearings have been exhaustively and thoroughly proved reliable through years of arduous use, and are available in a comprehensive range of stock sizes. Enquiries for special COMPO bearings are also welcomed, and we offer consultative technical advice on matters of design.

COMPO

OIL-RETAINING BRONZE BUSHES AND BEARINGS

Bound Brook Bearings Ltd

Trent Valley Road, Lichfield, Staffs.
 Telephone: Lichfield 2027/8




MEMBER OF THE



BIRFIELD GROUP

When answering advertisements kindly mention MACHINERY.


5-PORT PLATE VALVES



The S.808 Plate Valve is available as a lever operated valve in $\frac{1}{2}$ " BSP size only. The valve is "fully balanced" and supply air may be connected to any port. All ports are isolated in the mid-position. The exhaust ports are tapped.

The valve is extremely robust and is suitable for heavy industrial applications.

Suitable for the control of double-acting cylinders and similar devices, the construction is such that a degree of flow regulation may be attained by variation of the angular movement of the lever, ranging from a creep to full bore. This feature may be extremely valuable under certain circumstances.



The circuit illustrates two cylinders in opposition, controlled by a single lever-operated valve.

When the lever of the valve is reversed, the internal connections become those shown by broken lines and the upper cylinder will retract at the same time as the lower cylinder out-strokes.

By reversing the connections to either cylinder, the cylinders could be arranged to move in unison instead of opposition.

MARTONAIR LTD., PARKSHOT · RICHMOND · SURREY · ENGLAND

Telephone: RICHMOND 2201 (6 lines)

STOCKS OF PNEUMATIC HOISTS, CYLINDERS, CONTROL VALVES AND ACCESSORIES HELD AT RICHMOND, BIRMINGHAM, GLASGOW, SHEFFIELD, GATESHEAD.

AD.46

When answering advertisements kindly mention MACHINERY.



The fastest way to cut Keyways

WGW

INTERNAL KEYSEATERS

INFINITELY VARIABLE CUTTING
SPEEDS ENSURE MAXIMUM
PERFORMANCE—REGARDLESS OF SIZE

For the rapid and economical cutting of keyways and splines, these machines are unsurpassed. No marking out of parts is required, and several components may be machined at one pass. Tooling is very simple, and provision is made for the cutting of taper keyways and splines. Only a small space is required for the machine, which can carry up to 10 tons in weight, of almost any size.

MODEL NZH 70 as illustrated

CAPACITY

$\frac{1}{2}$ " to 2 $\frac{1}{2}$ " wide

KEYWAYS

CUTTING SPEED

(Infinitely variable) ... 13 to 39 $\frac{1}{2}$ ft. per min.


WORK SIZE

WORKPIECE WEIGHT

up to 10 tons

Available immediately from
London Stock.

Photograph by
courtesy of:
W. A. BAKER & Sons Ltd., Newport



Full particulars from the U.K. sole agents:—

SOAG MACHINE TOOLS LTD. **LONDON**

JUXON STREET • LAMBETH • S.E.11

PHONE: RELIANCE 7201 • GRAMS: SOTOOLSAG, LONDON, S.E.11

MARBAIX

FOR UNUSUAL MACHINES

minutes slashed to seconds
 on the new **MARBAIX**
M58 DISINTEGRATOR

REMOVES BROKEN TOOLS WITHOUT DAMAGE TO THE COMPONENT

CUTS HOLES OF ANY SHAPE IN HARDENED MATERIAL, CARBIDES ETC.

... in fact any material through which electric current can pass.

The new MARBAIX M58 disintegrator removes broken taps, drills, reamers, studs, etc., in a fraction of normal time without damage to the component.



Holes, too, of any shape can be cut in hardened material for subsequent finishing by grinding or other methods.

Note the times for the various examples shown, and write today for full details to Dept. M.I.



HERE'S HOW TO CUT COSTS

Times obtained on Model M58-C (as illustrated)



DEMONSTRATIONS GLADLY GIVEN ON YOUR OWN COMPONENTS

MARBAIX INDUSTRIES LTD

VALIANT HOUSE, VICARAGE CRESCENT
 BATTERSEA, LONDON, S.W.11
 PHONE: BATTERSEA 8888 (8 lines)

Your Opportunity

TO INSTALL A

GIDDINGS & LEWIS

Model 300 RT

Horizontal Boring, Drilling
and Milling Machine

**-DIRECT from LONDON
STOCK!**

with Built-in
ROTARY TABLE
(30" x 36")

and improved
measuring device for
all 3 directions



Note length
at bed and
vertical
travel of
headstock

BRIEF SPECIFICATION

Dia. of Spindle	3"
Length of Bed	72"
Vertical travel of headstock	45"
Built-in Rotary Table—30" x 36" with 36" cross feed									

IN A CLASS



OF ITS OWN



Equipped with Scales and Verniers
as well as improved measuring device
using end measuring rods for headstock, table,
and saddle movement.

This machine has all the well-known Giddings
and Lewis features including—Hardened Bed and
Saddle ways, 22" facing head with telescopic
tools, and above all, heavy stock removal coupled
with an exceptional degree of lasting accuracy.

ROCKWELL

MACHINE TOOL CO. LTD.

For further particulars write or telephone **TODAY**


WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033

ALSO AT BIRMINGHAM—TEL: SPRINGFIELD 1134/5 • STOCKPORT—TEL: STOCKPORT 5241 • GLASGOW—TEL: MERRYLEE 2822

THE *FIRST* SPARK ERODER BUILT AS A PRECISION MACHINE TOOL

ELERODA D1

*Today's answer to the making of
Drawing and Piercing Dies and the
making and reconditioning of Forging
and Stamping Dies—Machines
the "Unworkable" metals.*



A precision Swiss built machine which is today's answer to the machining by electro erosion of metals of any hardness such as hardened steel, tungsten carbide and nimonic without causing distortion of work or alteration of mechanical or physical properties of machined surfaces. The patented electrical circuit combined with the sensitive electro hydraulic servo-mechanism ensures speed of operation and high precision. Six different surface finishes from coarse for roughing to the finest finish are obtainable. 20 power settings. Automatic depth cutout.

ROCKWELL
MACHINE TOOL CO. LTD.


WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033

ALSO AT BIRMINGHAM—TEL: SPRINGFIELD 1134/5 • STOCKPORT—TEL: STOCKPORT 5241 • GLASGOW—TEL: MERRYLEE 2822

EL

When answering advertisements kindly mention MACHINERY.

Industry
demands
Steel
—and
Allen West
Control
Gear



Furnace tapping in the Electric Arc Melting Shop of Messrs. Thos. Firth & John Brown Ltd. Sheffield, by whose courtesy this photograph is reproduced

Whatever the application, for every motor there is an Allen West starter




ALLEN WEST

- * Designed to B.S. Specification throughout
- * Complete range—A.C. or D.C. automatic or hand-operated, from fractional to thousands of horsepower
- * Single units or composite switchboards
- * Crane Control Gear
- * All classes of enclosure, from open-type to fully weatherproof

ALLEN WEST & CO LTD BRIGHTON ENGLAND • Telephone: Brighton 23291 • Telegrams: Control, Brighton
Engineers and Manufacturers of Electric Motor Control Gear and Switchgear
SUBSIDIARY COMPANIES IN CANADA, SOUTH AFRICA AND RHODESIA • AGENCIES THROUGHOUT THE WORLD

When answering advertisements kindly mention MACHINERY.



EASTMAN TEXTILES

For the fastest blindstitch machine made today, the Lewis 162; Eastman & Textile Machines Co. Ltd. specify eleven Harper Grey Iron Castings—all supplied fully machined, enamelled and ready for assembly.

HARPER CASTINGS

Harper Quality covers Grey Iron, Spheroidal Graphite Iron (Mond Nickel Licence) and Meehanite castings.

Also metal pressings, machining, enamelling and other finishes and sub-assembly work.

Also makers of the famous Beatrice Oil Heaters and Harper Housewares.



JOHN HARPER & CO. LTD. JOHN HARPER (MEEHANITE) LTD.
ALBION WORKS Phone: WILLENHALL 124 (5 lines) Grams: HARPERS, WILLENHALL **WILLENHALL**

LONDON OFFICE: SEAFORTH PLACE, 57, BUCKINGHAM GATE, LONDON S.W.1 Tel.: TATE GALLERY 0286


MANCHESTER OFFICE: c/o B. J. Brown & Partners Ltd. 248/9 Royal Exchange, Manchester 3

H636

When answering advertisements kindly mention MACHINERY.

DANGER!

Dirty Coolant



MEANS

- ➡ SPOILT WORK
- ➡ WORN PLANT
- ➡ LOST TIME

Does your coolant do its job—without harm or loss? The Barnesdril separator gives you clean liquid for re-circulation freed at one pass from all ferrous particles, abrasive and general residue.

—for CLEAN COOLANT install . . .

BARNESDRIL

Magnetic Coolant Separators

- ✓ Powerful magnetic drum screens ALL the liquid.
- ✓ Ferrous swarf build-up collects other residue.
- ✓ Clean coolant gives longer tool life, better finish, less wear.
- ✓ Clean coolant means healthier working conditions.
- ✓ Wide application in the metal working field.

FOR UNIT OR BATTERY OPERATION

And for removal of ferrous and non-ferrous materials . . .

the

BARNESDRIL
KLEENALL
COMBINATION

MAGNETIC
AND FABRIC
FILTERS



Models from
5 to 103 gallons
per minute capacity

Patent nos. 603083 and
731655, others pending.
Any infringement will be
prosecuted.


Write to Department M2324

GASTON E. MARBAIX LTD


DEVONSHIRE HOUSE, VICARAGE CRESCENT,
BATTERSEA LONDON, S.W. 11
PHONE BATTERSEA 8188 (4 lines)

For the smaller PRECISION Gears

CAPACITY
UP TO 4" DIA.
by 4" FACE by 20 D.P.



Send for detailed catalogue



V4 UNIVERSAL GEAR HOBGING MACHINE

Easy to set up—simple to operate, the versatile V.4 offers high rates of production, with accuracy and economy, over a wide range of gears such as spurs, helicals, worm wheels, worms, and splines.



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET. LONDON, W.14

Telephone: WESTERN 8077 (8 lines)

Telegrams: ACCURATool HAMMER LONDON

103

When answering advertisements kindly mention MACHINERY.



with the Swiss

KELLENBERGER



JIG FINE BORER—MODEL 60K

A hand wheel with finely graduated ring gives precise control of the boring bar diameter adjustment while the machine is actually in operation. Patented spindle bearings ensure perfect rigidity at maximum boring depth and tolerances of .00012" can easily be held.

Brief Specification

Spindle stroke	39½"
Height under boring head	60"
Spindle to column	17½"
Boring range	$\frac{7}{16}$ " to 20 $\frac{1}{16}$ "
Table size	18" x 47½"

SOLE U.K. DISTRIBUTORS



**DELIVERY
EX-STOCK**



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W. 14

Telephone WESTERN 8077 (8 lines)

Telegrams ACCURATOOL HAMMER LONDON



Write for
this Brochure

149


When answering advertisements kindly mention **MACHINERY**.

5,000 THREADED ENDS

produced by

BRITISH RAILWAYS

on a Maiden 'MB' Threading Machine



British Railways have installed the 'Maiden' MB Threading Machine for the production of Pipe Threads on the 'Bo-Bo' 1160 h.p. Diesel Electric Locomotive currently in production at their Derby Locomotive Works.


Manufactured by

LANDIS MACHINE — MAIDEN LIMITED

Maiden Division

HYDE • CHESHIRE

Telephone: Hyde 2029. Telegrams: "Threading" Hyde.




MAIDEN

When answering advertisements kindly mention MACHINERY.

for power and precision . . .

the **CARDIFF** *Prefect*

9" (18½" SWING) SS & SC LATHE



3 1/16" SPINDLE BORE

18	Spindle Speeds	20-1,000 r.p.m.
80	Sliding Feeds	0.0023"-0.232"
80	Surfacing Feeds	0.0009"-0.096"
56	English Threads	½-30 T.P.I.
24	Metric Threads	0.5-30mm

**ALL FEEDS AND THREADS OBTAINED
BY SINGLE LEVER SETTINGS**

- Gap bed 30", 48", 80" and 100" — alternatively chip flow bed 48" and 80".
- Patented totally enclosed feed box.
- Hardened and ground gears in gearbox and headstock —all meshing faces tooth rounded for easy engagement.
- Patented snap action controls on apron—feeds can be varied whilst cutting.
- 11" (22" swing) Crusader model also available.

*Write NOW for
44 page
Machine Tool Catalogue*

B. ELLIOTT (MACHINERY) LTD

(MEMBER OF THE B. ELLIOTT GROUP OF COMPANIES)

Victoria Works, Willesden, London, N.W.10


Tel. ELG 4050

Overseas Subsidiaries: Canada, U.S.A., Australia, S. Africa




NRP 1826

When answering advertisements kindly mention **MACHINERY**.



type U3
Portable Universal
RADIAL DRILLING MACHINES



Our range of machines has recently been re-designed. Models are available with 4 ft., 5 ft., 6 ft., and 7 ft. spindle radius.

Illustration shows our 7 ft. model.

- FULLY ENCLOSED DRIVE
- INCREASED NUMBER OF SPEEDS & FEEDS
- BUILT-IN ELECTRICS

Full Particulars from—


KITCHEN & WADE LTD. HALIFAX • ENGLAND

Telegrams: KAW, HALIFAX

Telephone: HALIFAX 61173

When answering advertisements kindly mention MACHINERY.

High-pressure pumps




Infinitely variable control with

HYDRO TITAN

Hydraulic
transmission gears
and high-pressure pumps
from 2 HP
to several hundred HP



Standard
transmission gears



Remote-
transmission gears

Variable over a wide range

Regulation with
constant torque power characteristics
or with constant horsepower output

High efficiency over a wide range

Continuous power transmission

Rapid, joltless reversing

Controlled braking


Large overload capacity

Simple maintenance

Flexibility of application

Parallel or series arrangement
of several fluid motors

HYDRO TITAN Units



HYDRO TITAN


the economical, proved and reliable
transmission gear
for all branches of industry and transport




DE ROLL

Louis de Roll Iron Works Ltd.
Works at Klus, Klus (Switzerland)

Sole agents for United Kingdom:
Hydraulic Installations Ltd.
Stone House, 277 Greenwich High Road
London S. E. 10
Telephone: Greenwich 5375



see us for dust



DALLOW LAMBERT

Whatever you make, you make dust—and dust is dangerous, expensive stuff. See us for dust—and get rid of it. There'll be less waste, less wear—and healthier, happier work-people.

dust control equipment for industry

DALLOW LAMBERT & COMPANY LIMITED, THURMASTON, LEICESTER.

There's a resident Dallow Lambert man in your area. Would you like to see him? (Without obligation, of course.)


CRC 76

When answering advertisements kindly mention MACHINERY.


**Agents for
Zeuna-Starker
Unit Millers,
Smart & Brown
Lathes and
Toggle Presses.**

Write for further
details and literature.


3 OPERATION AUTOMATICS



7/8" CAPACITY



1 1/4" CAPACITY



**ZEUNA-STARKER M. V. A.
UNIT MILLING MACHINE**

MODERN


MACHINE TOOLS LIMITED

GOSFORD STREET · COVENTRY


Telephone 2132-6 Cables : Modern Coventry



**No. 2EE HOBROUGH
SURFACE GRINDER**




**3 WAY TAPPING
MACHINE**




THREAD MILLER



SIPHON PUMP




OIL GROOVER



2C CAPSTAN LATHE

Rainbow 1399

When answering advertisements kindly mention MACHINERY.



YOURS PRECISELY...

W. E. Sykes Ltd.—specialists for more than 30 years in the design and manufacture of machines and tools for gear production—invite a closer look at the model V10A gear shaper. External and internal spur gears, helicals, sprockets, serrations, racks, ratchets and many intricate profiles can be produced by this versatile machine.

The precision model V10A will generate with extreme accuracy gears up to 8 inches in diameter and from 12 to 64 D.P. Tooth to tooth and total composite errors are guaranteed to be within the Admiralty Class 1 specification 'Precision Gearing for Control Systems'. Full details and descriptive literature are freely available, together with the experience of the Sykes Technical Advisory Service.



PRECISION GEAR SHAPERS


W. E. SYKES LTD · STAINES · MIDDLESEX · ENGLAND

and associated companies

Sykes Tool Corpn. Ltd., Georgetown, Ontario, Canada.


Sykes Machine & Gear Corpn., Newark, N.J., U.S.A.

W. E. Sykes Ltd., Mascot, Sydney, N.S.W., Australia.



When answering advertisements kindly mention MACHINERY.

"BUYSER"
HIGH PRECISION
MILLER-DRILLER
FOR TOOLROOM, JIG BORING, ETC.
* BUILT TO SALMON LIMITS



**EXPENSIVE
JIG BORING
COSTS HALVED
WITH THIS
FINE MACHINE**
Table 24 x 9

W. URQUHART 1023-7, Garratt Lane,
LONDON, S.W.17
SOLE CONCESSIONAIRES. Phone: Balham 8551 (5 lines)


TAPPING MACHINE



**THE NEW
IMPROVED ACE
TAPPING MACHINE**
Capacity 3 BA
— 1/2 in. in STEEL
Cast Iron 1/2 in.
Left and right
hand threads.
Bench or pedestal
Delivery ex-stock

★ SENSITIVE OPERATION AVOIDING TAP BREAKAGE

W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BALham 8551 (5 lines)



★ BRITISH
MADE
REGISTRATION
No 893106


MICROTEST
★ **MAGNETIC** ★

**MICROTEST
PRECISION MAGNETIC VEE BLOCKS**

★ **WORLD RENOWNED** ★
FOR TOOLROOM • OR PRODUCTION
MADE OF TOUGHENED STEEL, HARDENED AND
GROUND ENSURING CONTINUED ACCURACY
**NOT TO BE COMPARED WITH CHEAPER
NON-HARDENED TYPES ON THE MARKET**
Microtest Vee Blocks are in a class apart
PRICE £18.10.0 or £37.0.0 matched pair

W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BALham 8551 (5 lines)


★ **ASTRA**
VERTICAL MILLER DRILLER
FOR
TOOL ROOM, PRODUCTION, ETC.



★ With left and
right hand tracing
pin. Table 23" x
8". Spindle No. 3
MT.RPM 296-1964.

ORDER NOW!
★ BRITISH MADE

W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BALham 8551 (5 lines)

What is
the cheapest
and simplest way
of fixing
this ...  ...
to this?


When both are metal—the answer is almost invariably stud welding. The cost may be as little as one fifth of, for instance, the cost of drilling and tapping. The time an even smaller fraction. And stud welding is far stronger than any alternative method and absolutely permanent.

Stud welding is speeding up production and lowering costs in an immense range of industries from shipbuilding to domestic equipment. Attachments may be of almost any shape. A talk with our Engineers perhaps, followed by a demonstration, will be worth your while.

Crompton Parkinson STUD WELDING



CROMPTON PARKINSON (STUD WELDING) LIMITED
1-3 Brixton Road, London, S.W.9. Telephone: Reliance 7676




When answering advertisements kindly mention MACHINERY.

NEW

HEAVY DUTY Capstan Lathe

MODEL R5



- 2" bar capacity
- Pre-selection of 18 spindle speeds
- Pre-selection of 12 longitudinal and cross slide feeds
- Feed control by single lever
- Automatic feed knock-out

- Hardened and ground gears
- Screw-cutting attachment by leadscrew and nut

IMMEDIATE DELIVERY

**EXCLUSIVE DISTRIBUTORS
IN THE UNITED KINGDOM**

ELGAR

MACHINE TOOL COMPANY LIMITED

SPECIFICATION

Max. bar sizes 2" dia.

Max. turning dia. over bed 20"

over cross slide 10"

Max. distance, spindle nose to turret 29½"

Spindle speeds (18) 28 - 1400 r.p.m.

RIGHT OPPOSITE NORTH ACTON STN.

172-178 VICTORIA ROAD · ACTON · LONDON W3 · Telephone ACORN 5555

Midlands Office and Showrooms: 1075 KINGSBURY ROAD, BIRMINGHAM 24

Scottish Agents and Showrooms: ANGUS & CRICHTON (SALES) LTD., 37 DALMARNOCK ROAD, RUTHERGLEN, LANARKSHIRE
NRP

**35" of 1" square mild
steel bar reduced to
nothing in 35 hours**

**with one standard-cut
SURFORM blade!**



THAT'S THE RESULT OF ONE OF OUR RECENT TESTS

using a normal standard-cut surform blade. Under controlled conditions of stroke length and load, the same blade was used throughout the test—which proves that surform is tough as well as fast!

This is not the only test surform has passed with flying colours. The Sheffield Testing Works Limited put it through its paces not so long ago and their test proved that there's no hand tool faster than a surform for reducing wood, copper and aluminium—as well as mild steel. And that means big savings in production and labour costs. We'd be glad to give you details.

500 TEETH—NO CLOGGING

The surform blade is unique. It consists of a 10" strip of hardened and tempered Sheffield tool steel with 500 teeth set at a scientifically gauged angle. The depth of cut is controlled and clogging is impossible. The blade was invented by Firth Brown Tools Limited.

NOW IT COMES IN 6 DIFFERENT SURFORMS

Standard File 12/6; Standard Plane 17/8; Block Plane 10/-; Fine-Cut File 12/6; Convex Plane 17/6; Half-Round File 13/-. Interchangeable replacement blades for all models.

HOW ABOUT A DEMONSTRATION?

We can easily arrange for a surform demonstration on your premises. Drop us a line and we'll put our area representative in touch with you.

SURFORM



Made by: SIMMONDS AEROCESSORIES LTD.
TREForest • PONTYPRIDD • GLAMORGAN

A MEMBER OF THE FIRTH CLEVELAND GROUP



CRC 345U

When answering advertisements kindly mention MACHINERY.

ASEA JIG BORING MACHINE

for toolroom accuracy

This high-class machine is rigidly built with a large table, ample throat space, large spindle and spindle head vertical movement.

The micrometer screws controlling the long and cross travel of the table allow a setting accuracy of ± 0.0002 in. over a length of 12 in., while an accuracy of ± 0.0001 in. is attainable in any one inch of the screws.

SPECIFICATION

High speed
spindle ranges 215-460-940-2050 r/m

Feed per spindle
revolution ... 0.0012"-0.0035"-0.0059"
(0.03-0.09-0.15 mm)

Spindle head vertical
movement 7½" (190 mm)


Spindle vertical
movement 6½" (175 mm)

Table
dimensions ... 15" x 22" (380 x 560 mm)

Distance spindle
to table 19½" (500 mm)

Screw accuracy:
over 12" of length ± 0.0002 "
over 1" anywhere ± 0.0001 "

Weight 2900 lb. (1300 kg)



DISTRIBUTORS AND STOCKISTS FOR THE UNITED KINGDOM




MORTIMER ENGINEERING
PROPRIETORS **COMPANY** S. GUTERMAN & CO. Ltd



Showroom & Sales: 204/206 ACTON LANE • HARLESDEN • N.W10 • Tel: ELGAR 3834

When answering advertisements kindly mention MACHINERY.



*New techniques
present
new problems*

HARD ENGINEERING CERAMICS CAN BE THE SOLUTION

With a hardness between diamond and sapphire, highly resistant to wear and possessing excellent physical properties, REGALOX hard ceramics have been the solution to many difficult problems in the engineering industry—chemical—mechanical—electrical.

OUTSTANDING ADVANTAGES

- WEAR & HEAT RESISTANT
- DIMENSIONALLY STABLE UNDER ALL CONDITIONS
- LOW CO-EFFICIENT OF FRICTION
- HIGH PHYSICAL PROPERTIES

Our Technical Development Advisory Service is immediately available to tell you where REGALOX can be applied with advantage to your own products.

*Already in use for
jig bushes, plug gauges,
tool tips, wire guides, textile
guides, grinding balls, etc.*

*Write now for this free
catalogue and test piece*



**THE WORCESTER ROYAL PORCELAIN COMPANY LIMITED
INDUSTRIAL CERAMICS DIVISION**

Sales Department—TONYREFAIL, GLAMORGAN, SOUTH WALES
Telephone: TONYREFAIL 135/136 Telegrams: PORCELAIN, TONYREFAIL



**REGALOX
ALUMINA CERAMICS**

NEARLY DIAMOND HARD

When answering advertisements kindly mention MACHINERY.


— improve the quality of your product by

VACUUM DIECASTING

an exclusive new process that:—

- INCREASES PRODUCTION
- ELIMINATES POROSITY
- REDUCES REJECT RATE
- LOWERS FINISHING COSTS
- PRODUCES STRONGER CASTINGS

This equipment can be supplied for Herbert/Reed-Prentice Machines, either new or already installed, and also for machines of other makes. It is necessary for intending users, before ordering, to apply for a licence to Sparklets Ltd., Queen Street, Tottenham, London.



Herbert / Reed - Prentice 1½E
Diecasting Machine fitted with
Vacucast equipment.

ALFRED

HERBERT

LTD., COVENTRY

Factored Division, Red Lane Works.




AD 460

When answering advertisements kindly mention MACHINERY.



AT THE HEART OF
PRECISION ENGINEERING

S I L C O M S



Limits of accuracy were set at $\pm .005$ " on the overall dimensions of the Core Tube Nest for the Dounreay Fast Reactor—so they asked SILCOMS to build it. This most intricate assembly was fabricated entirely from stainless steel and SILCOMS had to design and build special equipment in order to overcome the difficulties involved in machining and assembling. The bottom core plate (shown above) illustrates the skill called for; it was machined from a 6" thick forging in which some 270 holes had to be bored.

We are particularly happy in devising and building special purpose machinery of the highest standards of accuracy — we have the resources, the men and above all the enterprise and the enthusiasm for a good job well done.

What can we do for you?

MANUFACTURERS OF SPECIAL PURPOSE EQUIPMENT

PRESS TOOLS • FIXTURES • JIGS

MOULDS FOR PLASTICS, GLASS, RUBBER, ETC.

SILCOMS (Proprietors: Bolton Engineering Co. Ltd.) VICTORIA WORKS • FARNWORTH • LANCASHIRE
Tel.: FARNWORTH 1305-6. AND AT 327 BURY ROAD : BOLTON : LANCASHIRE : Tel.: BOLTON 3545

5.4

When answering advertisements kindly mention MACHINERY.

the Big 5 ^{by} DROOP & REIN

1
Upside Plano Milling Machine. Can be supplied with additional milling heads.


2
Horizontal Spindle Plano Milling Machine with two dimensional tracing unit.

3
Horizontal Spindle Die Sinking Machine. Available in various capacities.

4
Floor type Horizontal Boring Machine, available in various capacities.

5
Vertical Spindle Copy Milling Machine, available in various capacities. (Also produced without tracing unit.)

EXCLUSIVE
DISTRIBUTORS
IN THE U.K.



ELGAR

MACHINE TOOL COMPANY LIMITED

172-178 VICTORIA ROAD ACTON LONDON W3 Telephone ACORN 5355


MIDLANDS SHOWROOM: 1075 KINGSWAY ROAD, BIRMINGHAM 21

Scottish Agent: ANGUS & CRICHTON (SALES) LTD. 37 DALMARNOCK ROAD, RUTHERGLEN, LANARKSHIRE.


When answering advertisements kindly mention *MACHINERY*.

NILES VERTICAL BORING MACHINES

are
Some of over
400
MACHINE
TOOLS
OF VARIOUS
TYPES SUPPLIED
and SERVICED
BY US . . .



NILES 53" VERTICAL BORING
MACHINE



NILES 6' 8" TO 26' 0" VERTICAL
BORING MACHINES


STOCK DELIVERY

SOLE
AGENTS
IN U.K.

THOS. C. WILD
Machinery
LIMITED

VULCAN WORKS
COLERIDGE ROAD SHEFFIELD 9


Telephone : 42871 Sheffield



Machining the web faces of a large, carbon-steel, six-throw crankshaft on a Herbert No. 28a Vertical Milling Machine.

A 7" diameter Herbert High-power Carbiface Face Milling Cutter with nine Grade S.200 Ardoloy-tipped teeth, is used for the operation.

Heavy stock removal permits completion of the operation in a total time considerably less than that taken by previous methods.



HERBERT Vertical Milling Machines

No. 47V. Has the power, speeds and rigidity for milling materials from aluminum to high-tensile steels. Thirty-two speeds, 21 to 1,525 r.p.m.; twenty-four feeds $\frac{1}{4}$ " to 60" per min.; quick traverse to longitudinal motion. 48" x 16" x 23".

No. 49V. For heavy work requiring large table capacity. Thirty-two speeds, 21 to 1,525 r.p.m.; electronic feed drive, infinitely variable feeds from 0.8" to 40" per min.; quick-traverse to longitudinal and transverse motions. 62" x 29" x 28½".

No. 28A. For heaviest class of work. Thirty-two speeds, 12 to 540 r.p.m.; electronic feed drive, infinitely variable feeds between 0.8" and 40" per min.; quick traverse to longitudinal and transverse motions. 62" x 29" x 30½".

All models now available for Early Delivery

ALFRED

HERBERT

LTD., COVENTRY



AD.277

When answering advertisements kindly mention MACHINERY.


RICHARDS

5 FT. VERTICAL TURNING AND BORING MILL

at the
Bergius Co. Ltd.

Set-up with one head for roughing and the other for finishing, this 5 ft. RICHARDS boring mill is keeping costs low on the medium scale production of diesel engine crankcases at The Bergius Co., Ltd., Glasgow. Eight blocks are set up at once, and our photographs show the simultaneous roughing and finishing of the sump faces.

These machines are built with capacities up to 50 ft. dia., and we will gladly tell you just where and how they could reduce costs on your own work. Write us.

GEORGE RICHARDS & CO., LTD

A MEMBER OF THE STAVELEY COAL & IRON CO. LTD.
GROUP


BROADHEATH · ALTRINCHAM · CHESHIRE

'Phone: ALTRINCHAM 4242-7

'Grams: RICHARDS, ALTRINCHAM

SOLE AGENTS—

ALFRED HERBERT LTD., FACTORED DIVISION, COVENTRY



When answering advertisements kindly mention MACHINERY.



ASQUITH

N.L.D. Radial Drilling Machine
a light-duty machine for fast, accurate production

This is the ideal radial for many drilling and tapping jobs where comparatively light duty is required, often with a large radial swing. The Asquith NLD is available with maximum radius spindle centre to pillar centre from 3ft. 6in. up to 6ft. Available for early delivery.

Write today for full details.

WILLIAM ASQUITH LTD.
 HALIFAX • ENGLAND

Sales & Service for . . .

DRUMMOND-ASQUITH

. . . the British Isles

DRUMMOND-ASQUITH (SALES) LTD., KING EDWARD HOUSE, NEW ST., BIRMINGHAM

*Phone: Midland 3431 (7 lines) *Grams: Maxishope, B'ham. Also at LONDON: Phone: Trafalgar 7224 (5 lines) and GLASGOW: *Phone: Central 0922

A 153

When answering advertisements kindly mention MACHINERY.

D


*when one second
is vital . . .*



*Magnified view
through eyepiece showing
scale readings 62° 1' 40"*

Whether for inspection purposes or highly accurate positioning of workpieces featuring compound angles, only the new O.M.T. 12" and 16" Optical Rotary and Inclination Tables provide scale readings direct to one second of arc for both movements. Combining accuracy with reliability, each model is fitted with a twin eyepiece unit to facilitate reading of the rotary at any position throughout the axis of inclination.

**A PRECISION PRODUCT OF
OPTICAL MEASURING TOOLS LTD
MAIDENHEAD BERKS**



OMT

full details on request to

NEWALL GROUP SALES LIMITED

PETERBOROUGH ENGLAND

WRIGHT

Self-contained—Motorised Grinding Heads

(COVERED BY BRITISH AND FOREIGN PATENTS)

An ideal supplementary attachment to
PLANING, MILLING, BORING & TURNING MACHINES
and most types of heavy lathes





Illustration shows a Model 1.5/2P Motorised Grinding Head attached to a Fritz Werner Hydraulic Slide-way Grinding Machine. In this instance the surface of a Ward No. 7 Capstan Lathe bed is being re-ground.

- ★ Available in Five Sizes
- ★ Independent Operation
- ★ Locking device for securing the "Depth-of-Cut" position
- ★ Calibrated Scale Ring

Compensation for wheel wear and/or fine adjustment of depth of cut is obtained through traverse of the rotor by means of a hand-wheel

Illustration shows Model 1.5/2P Grinding Head attached to a Ward No. 7 Lathe, a hardened steel distance piece being ground in this instance.



WRIGHT ELECTRIC MOTORS (HALIFAX) LTD
CENTURY WORKS · PELLON LANE · HALIFAX · ENGLAND
MANUFACTURING ELECTRICAL & MECHANICAL ENGINEERS
ESTABLISHED 1900

Phone 60201-2-3 Cable: "Motor" HALIFAX

When answering advertisements kindly mention MACHINERY.

**CARBIDE****TIPPED**

REAMERS

MADE TO B.S.S. 122

Unequalled Performance
Quick Delivery

Diameters

$\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ",
 $\frac{5}{8}$ ", $\frac{11}{16}$ ", $\frac{3}{4}$ ", $\frac{7}{8}$ ", & 1"

Delivery ex-stock or 7 days

The same delivery and price
will also apply to any size
within plus .005", minus .015"
of the above fractional sizes.

VERALOY


VERALOY PRODUCTS LIMITED

BEECH ROAD, THE MARSH,
HIGH WYCOMBE, BUCKS.
Telephone: High Wycombe 2795/6/7/8
Telegrams: VERALOY HIGH WYCOMBE

When answering advertisements kindly mention MACHINERY.

CONOMATIC

high production automatic bar machines



4, 5, 6
and 8
spindle
machines



For full details of the range of CONOMATIC machines
please write to the sole agents:

CHARLES CHURCHILL & CO. LTD
COVENTRY ROAD, SOUTH YARDLEY, BIRMINGHAM, 25
Branches: London, Glasgow, Newcastle, Manchester

C.C.17

When answering advertisements kindly mention MACHINERY.

BOAC introduces the SHIPPERS' SERVICE UNIT



BOAC's Shippers' Service Unit offers you something entirely *new* in air cargo service. For instant action on any consignment 'phone BOAC (VICTORIA 2323), and ask for "SKYLOAD". You will go straight through to the freight experts of the Shippers' Service Unit . . . get immediate information on costs, transit times, delivery dates and Customs regulations.

All over the world

B·O·A·C

*takes good care of
your cargo*

Your local BOAC Appointed Forwarding Agent is also at your service


BRITISH OVERSEAS AIRWAYS CORPORATION

**INTRODUCING
THE NEW
No 2G SERIES
AUTOMATICS**

**Brown
&
Sharpe**
of course!

**THE NEW 2G SERIES
AUTOMATIC
SCREW MACHINE**

WITH EITHER $\frac{3}{4}$ in.— $1\frac{1}{4}$ in.— $1\frac{1}{2}$ in.
CAPACITY SPINDLES



NEW CONSTRUCTION

Allows complete interchangeability of attachments, turret tooling and cams for all three spindle sizes—provides savings in tooling costs and greater versatility for planning and machine loading. Ensures dependable precision, with continuous high production on broader range of materials and work diameters.

AUTOMATICALLY Brown & Sharpe

To check these, and many other advantages against your present equipment write for full details to Sole Agents in United Kingdom for the Manufacturers—Brown & Sharpe Ltd., Plymouth.

BUCK & HICKMAN LTD

MACHINE TOOLS, OTTERSPOOL WAY, WATFORD BY-PASS, HERTS
Head Office: P.O. Box No. 74, WHITECHAPEL ROAD, LONDON, E.1
Branches: ALPERTON • BIRMINGHAM • BRISTOL • GLASGOW • LEEDS • MANCHESTER



F.B.T.
FIRTH-BROWN TOOLS LTD.
SPEEDICUT WORKS, CARLISLE STREET EAST,
SHEFFIELD ENGLAND


Our customer produces Iron Pipe fittings. Normal tap life when machine tapping was only 40/50 components. A Technical Representative from Speedicut Works studied the problem and made recommendations on design and treatment which increased tap life on this operation to over 1,500 components.

**Take advantage of the latest techniques in tool making
—SPECIFY SPEEDICUT.**

Specify

**SPEEDICUT
TOOLS**

When answering advertisements kindly mention MACHINERY.



When wallpapers are printed, cleanliness is all-important. Oils and greases that splash, drip, or run, are out of the question. At the works of The Wallpaper Manufacturers Ltd., Leeds (a member of the Crown Group) conventional oils and greases cannot be used on the fast-moving conveyor chains of the drying unit, which operates at a temperature of 220° Centigrade. After testing all possible lubricants, Crown adopted an Acheson dry-film lubricant, 'dag'* Dispersion 2404 (colloidal graphite in white spirit), and this product has been standard at the Leeds works for many years. For effective, economical and long-lasting lubrication of conveyors, chains, and other equipment working to "no-soilage" rule, Acheson dry-film technique is the answer. If you feel that 'dag' dispersions could help to solve problems for you, we shall be pleased to send a Field Engineer to carry out a lubricant survey without obligation on your part. *Conveyors and chains are dealt with in our Information Sheets P1 and P2. We shall be pleased to send copies.*

*Registered trade mark of Acheson Industries (Europe) Ltd; licensed user—Acheson Colloids Ltd.

dag
REGD TRADE MARK

dispersions speed production

ACHESON

COLLOIDS LIMITED



Subsidiary of Acheson Industries (Europe) Ltd.

PRINCE ROCK • PLYMOUTH • DEVON

Enquiries to: TECHNICAL SALES AND SERVICE, 70 Hill Street, Richmond, Surrey Phone: RICHmond 5481 (3 lines)


Also Acheson Colloids Company, Port Huron, Michigan U.S.A., and Acheson Colloiden N.V., Scheemda (Gr.) Netherlands

*The fastest method of
grinding two surfaces
simultaneously!*

ROWLAND


DUPLX SURFACE GRINDERS

* Illustrated here are but a few of the very many types of 'Duplex' surface grinding machines that we manufacture.




BRAKE DISCS

30in. Type ADD/H




CIRCLIPS

30in. Type ADD/P



CALCULATOR PARTS

20in. Type HDD/C



CONNECTING RODS

30in. Type ADD/O

* All machines are capable of extremely impressive rates of production, coupled with high degrees of accuracy and surface finish.

Our technical representatives are ready, able and willing to co-operate with you.

**F.E. ROWLAND
& CO. LTD.**

Telephone :
HEATON MOOR
3201-2-3
Telegrams :
HEROIC, REDDISH

REDDISH • STOCKPORT • ENGLAND

Sole Export Agents: DRUMMOND ASQUITH (Sales) LTD., Halifax House, Strand, London, W.C.2. Tel: TRAlgalgar 7224

YOU'LL BE MUCH BETTER OFF WITH A HARRISON

Built to a standard above its price
— your Harrison 11" swing lathe
will be giving you accurate service
for more years than you expected.


SPECIFICATION

Swing over bed 11"
Swing in gap 18"
Between centres 24" or 40"
8 or 16 spindle speeds

11" SWING

£370.0.0

With inbuilt hydraulic copying equipment
£700.0.0



SEND FOR FULLY DETAILED
LEAFLET TODAY

T. S. HARRISON & SONS LIMITED • HECKMONDWIKE • YORKSHIRE

When answering advertisements kindly mention MACHINERY.

Fescol certainly started more than something...

When London's buses looked like this and catered more for health than comfort FESCOL pioneered their process for the electro-chemical deposition of nickel for building up worn engineering parts. Two years later, in 1922, FESCOL again led the way with the deposition of hard chromium and have now perfected the deposition of hard chrome on light alloys. The FESCOL process has saved industry hundreds of thousands of pounds by restoring worn components to their original dimensions. The process protects new products against corrosion and provides a hard, long-wearing, low-friction surface. Are you up-to-date with the full range of engineering components that can be FESCOL-ized in Chrome or Nickel? For further information please write for publication M13.



1ST HEAVY NICKEL DEPOSITION
was pioneered by FESCOL in 1920

1ST HARD CHROME DEPOSITION
was introduced by FESCOL in 1922

and
NOW HARD CHROME DIRECT
ON LIGHT ALLOYS



Established 1920

FESCOL LTD • NORTH ROAD • LONDON N.7

Branch Works at

Port Glasgow, Huddersfield, and Brownhills, Walsall

Sole Licensees for Australasia: De Havilland Aircraft Pty. Ltd., Milperra Rd., Bankstown, N.S.W.

TGA 748

When answering advertisements kindly mention MACHINERY.




CENTRE LATHES

HIGH Removal rates


CLOSE Limits of accuracy

SUSTAINED Performance

WITH OR WITHOUT HYDRAULIC PROFILING EQUIPMENT



**CHURCHILL-REDMAN
"L" SERIES CENTRE LATHES**
22" 28" or 36" swing 5' 0" to 11' 0" centres



Close-up of the headstock and gearbox on 22L Model

These famous lathes have many notable features, including:

18 Headstock spindle speeds

Range of speeds

22L Model: $7\frac{1}{2}$ - 500 r.p.m.
alternatively 15 - 1000 r.p.m.

28L & 36L Models: 6 - 400 r.p.m.
alternatively 12 - 800 r.p.m.

Self-adjusting hydraulic main drive clutch

20 H.P. Main Drive Motor

Hydraulically operated spindle brake

Automatic pressure lubrication

Built-in Ammeter and Tachometer

30 speed totally-enclosed gearbox

Quick power traverse to saddle

Bed chip clearance chutes

AVAILABLE ON EARLY DELIVERY



CHURCHILL-REDMAN LTD

HALIFAX · ENGLAND


A COMPANY OF THE CHARLES CHURCHILL GROUP
Brookway/cr/3

When answering advertisements kindly mention MACHINERY.

There is no substitute for experience

Experience counts in every walk of life, but in no other job is experience so vitally necessary as in the design and building of machines such as large power presses, where the ability to turn out large numbers of high quality pressings at an economic rate depends so much on inbuilt robustness, accuracy and reliability.

The up-to-date design and extra massive proportions of all C.W. presses are not the sole features which give C.W. presses their absolute dependability but it is also the real old fashioned craftsmanship such as the accurate hand scraping of every slideway and the careful bedding of every main bearing that make the difference between a COWLISHAW WALKER POWER PRESS and just another press.



COWLISHAW, WALKER & CO. LIMITED

Biddulph, Stoke-on-Trent. Telephone: Biddulph 3254. Telegrams: "Cowlshaw" Stoke-on-Trent
LONDON OFFICE: 117, Victoria Street, Westminster, London, S.W.1. Telephone: VICTORIA 5472


When answering advertisements kindly mention MACHINERY.



BORING CONNECTING RODS . . .

MACHINERY
December 3, 1958

65



** 220 per hour!*

This is a typical EX-CELL-O set-up in a well-known automobile factory, where EX-CELL-O machines have proved their ability to reduce costs and improve finish on a wide variety of work. Both the large and small ends of the rods are machined and the production rate is 220 pieces per hour. We invite you to investigate the cost reducing possibilities of EX-CELL-O machines for your own work. No obligation.



EX-CELL-O

**STYLE H2C SENIOR
PRECISION BORING
MACHINE**


EX-CELL-O CORPORATION
HASTINGS RD., LEICESTER, ENG.

(MACHINE TOOLS) LIMITED
TEL: LEICESTER 68101 (10 Lines)




EFCO ISOTHERMAL QUENCH BATHS

for austempering and martempering up to 500°C.
Publication R.18.



HIGH SPEED STEEL FURNACE—TWIN CHAMBER

Preheating up to 1000°C. and hardening up to 1350°C. without decarburisation.
Publication RF.1017.



EFCO-UPTON CONTINUING GRAPHITE ELECTRODE SALT BATH

Hardening high speed steels, aluminium brazing and all processes up to 1300°C. with bath free from metallic oxides.
Publication R.27.



EFCO-LINDBERG CYCLONE FURNACES—GAS OR ELECTRIC

for fast and accurate tempering and general heat treatment up to 750°C.
Publication R.17.




EFCO FORCED AIR CIRCULATION FURNACES

For tempering, stress relieving, aluminium alloy heat treatment and all processes up to 700°C.
Publication R.2.


EFCO BOX TYPE FURNACES

Box carburising and general treatment to 1150°C.
Publication R.3.




EFCO ELECTRIC SALT BATHS

Cyanide hardening, carburising, neutral treatment to 1000°C.
Publication R.1.



EFCO SALT BATH FURNACE MIDGET TYPE

with interchangeable pots for processes from 600 to 1350°C. for small outputs.
Publication R.16.




EFCO SENTRY FURNACE

Diamond Block method of atmosphere control for high speed steel hardening up to 1350°C. Vertical or horizontal.
Publication R.6.




EFCO VERTICAL MUFFLE TYPE FURNACES

for heat treatment of long or slender parts.
Spec. Sheet 1729.



EFFICIENCY IN YOUR TOOL ROOM

In this age of ever increasing productivity, quality control and necessity for reduction of costs, efficiency in your Tool Room is vital. EFCO have introduced major improvements in furnaces for all processes. May we send you our brochures describing some of the furnaces which can modernise your plant.



ELECTRIC RESISTANCE FURNACE CO LTD

NETHERBY : QUEENS ROAD : WEYBRIDGE : SURREY

MRP 2330/R3050

Telephone : 3891 Telex : 22849
Telegrams : Resistalor, Weybridge

When answering advertisements kindly mention MACHINERY.

E

Something New! CEJ "HI-TEN" TAPS

**HAVE YOU ANY REALLY TOUGH
TAPPING PROBLEMS
IN HIGH TENSILE STEELS?**

A NEW MANUFACTURING PROCESS IS GIVING
AMAZING RESULTS AND MUCH LONGER TAP LIFE
ON THESE DIFFICULT MATERIALS

CEJ JOHANSSON LTD.


★ Tell CEJ about your problems and they will
find the answer

SOUTHFIELDS ROAD, DUNSTABLE, BEDS.

DBH/7097

When answering advertisements kindly mention MACHINERY.

SLIDING RAM
GIVES 27 $\frac{1}{2}$ in.
AUTO CROSS
FEED



HEAVY DUTY MILLING

ANGULAR COMPOUND HORIZONTAL VERTICAL

HURON SUPER UNIVERSAL MILLERS

Integral double swivelling universal head provided with 27 $\frac{1}{2}$ in. automatic cross feed by the sliding ram, can be set to the horizontal or vertical position, or to any angle instantaneously—permits the heaviest production cuts. Head can be retracted completely from table line. 27 spindle speeds from 30 to 2,066 r.p.m. 27 feeds from $\frac{1}{16}$ in. to 30in. Rapid traverses in all directions. All operating controls duplicated. Table slides directly in the knee without cross movement or swivel. Double guides of knee permit components in excess of 1 $\frac{1}{2}$ tons to be machined. The double swivelling universal head requires an opening of only 14in. to enter work pieces and the whole sliding ram with its 27 $\frac{1}{2}$ in. automatic cross movement needs only 18in. clearance.

Type	Table	Automatic Feeds		
		Long	Cross	Vert.
KU4	56 $\frac{1}{2}$ in. x 15 $\frac{1}{2}$ in.	43 $\frac{1}{2}$ in.	27 $\frac{1}{2}$ in.	19 $\frac{1}{2}$ in.
KU5	64 $\frac{1}{2}$ in. x 15 $\frac{1}{2}$ in.	51 $\frac{1}{2}$ in.	27 $\frac{1}{2}$ in.	19 $\frac{1}{2}$ in.
KU6	78 $\frac{1}{2}$ in. x 16 $\frac{1}{2}$ in.	59in.	27 $\frac{1}{2}$ in.	19 $\frac{1}{2}$ in.
L7	157in. x 39in.	118in.	27 $\frac{1}{2}$ in.	39 $\frac{1}{2}$ in.


Type 'L' Open-side Traversing Head Universal Miller will mill, bore, slot and drill the largest work-pieces at one setting.

The unique design permits greatest variety of operation on large work-pieces; the component remains stationary on the large work-table. Upright slides full length of base table, and the sliding ram moves vertically and horizontally.

DUFOUR UNIVERSAL MILLERS

Table surface 43 $\frac{1}{2}$ in. by 9 $\frac{1}{2}$ in. or 47 $\frac{1}{2}$ in. by 10 $\frac{1}{2}$ in. Auto long. feed, 26 $\frac{1}{2}$ in. or 30 $\frac{1}{2}$ in. Auto vert. feed, 15 $\frac{1}{2}$ in. or 18 $\frac{1}{2}$ in. Auto cross feed 9 $\frac{1}{2}$ in. Rapid traverse in all directions. No. 40 International taper for main spindle, universal head, and rotary table. Direct reading dial change for speeds and feeds. All parts subject to wear hardened and ground and completely interchangeable. Built to closest tolerances. Spindle speeds 21 to 1,600 r.p.m. Twin overarms. Separate motor for rapid traverses.

Also table 63in. by 15in., with auto feeds: 40in. long., 21in. vert., 14in. cross; 25in. auto-univ. head feed. 36 spindle speeds 6 to 1,500 r.p.m.




SCULFORT LATHES

Swing over bed 20, 22 or 25in.
and 28, 32 or 66in.
and 40, 47 or 60in.

Speed ranges: 6-2,000;
12-1,600;
or 3 $\frac{1}{2}$ -325 r.p.m.

18-45 h.p. motor drives for max. output. Totally enclosed gear box provides 90 different pitches. Flame hardened bed. Large spindle bore. All head stock gears hardened and ground. Built-in coarse screw cutting device.

Other products: Copying lathes, Locomotive and Carriage Wheel Turning Lathes, Centreless Bar Turning Machines, Facing Lathes and Special Purpose Centre Lathes.



We
supply
Ex-Stock
and demonstrate
CLARE Chucks & Collets.

Send for full particulars: All Machines available for Demonstration

Rudolph Carne & Co. Ltd.

SWAN WORKS, FISHERS LANE,
CHISWICK, LONDON, W.4.

Telephone: CHISWICK 0514 & 6585. Inland Telegrams: RUDCAR, CHISK, LONDON. Overseas Telegrams: RUDCAR, LONDON.

When answering advertisements kindly mention MACHINERY.

Electric Motors

NETTLEFOLD & MOSER

have available from stock:—

"BROOK" & "NEWMAN" FRACTIONAL

and INDUSTRIAL ELECTRIC MOTORS

and are the *Sole London Stockists* for

"G.E.C." INDUSTRIAL

ELECTRIC MOTORS

When the call is for Electric Motors...

ring

Nettlefold & Moser

first

NETTLEFOLD & MOSER LIMITED
LONDON: Box 378, 170-194 Borough High St.,
S.E.1. Phone: HOP 7111 (40 lines).
BOOTLE: Dunning's Bridge Road, Bootle 10,
Lancs. Phone: Aintree 4171 (6 lines).
HULL: 201 Sculcoates Lane, Hull.
Phone: Central 41341 (3 lines).

When answering advertisements kindly mention MACHINERY.



Electroset FINE BORING

'Well, what's so new in that anyway?'

... said one of our more cynical customers. We could only reply that it was a fact that setting up time on our machine was much less than customary, that maintenance of our hydraulic unit being completely portable was much simpler and that almost any work cycle could be obtained by the flick of a switch or turning of a valve. 'Is it competitive?' he countered, to which we modestly rejoined, 'Ask for a quotation, you will be impressed at the value for money we offer'.

It occurs to us it would be a good thing for you to find out more about our F.B.I Fine Boring Machine and equipment.

Table travel, 15in.

Table surface Pad, 26in. by 8½in.

Height centre of spindle to table, 10in.

Table feeds, ¼in. to 60in. per minute.

Stuart
DAVIS

STUART DAVIS LTD · MUCH PARK STREET · COVENTRY · PHONE: COVENTRY 63091-2

When answering advertisements kindly mention MACHINERY.

GREASE



for smoother
running -

The life and efficiency of a machine tool depends upon the correct application of the right lubricant in the proper place. The design of machine tools is complex and many factors have to be considered in selecting the most suitable lubricant—working conditions, operating temperatures, speed of rotation, bore of feed pipes. In the compact range of ALMARINE greases one can find lubricants to satisfy all these basic requirements economically and efficiently. Ask for Publication SP178.

LUBRICATION AT YOUR FINGERTIPS

Machine shop maintenance is always complicated but the task can be simplified by a FLETCHER MILLER Lubrication Survey—Your maintenance requirements are expertly analysed and grouped with all data clearly set out in a permanent record. May we help you in this way?

FLETCHER MILLER

Machine Tool Lubricants

ALMARINE FOR ALL GREASE POINTS

VETA FOR HYDRAULIC SYSTEMS GENERALLY

GENA THE MACHINE TOOL LUBRICANT

FLETCHER MILLER LTD., ALMA MILLS, HYDE, CHESHIRE.

Telephone: HYDE 3471 (5 LINES)

Telegrams: EMULSION, HYDE

Also at LONDON, WEST BROMWICH, NEWCASTLE-ON-TYNE, CARDIFF, GLASGOW AND BELFAST


MTL 35

When answering advertisements kindly mention MACHINERY.

MULHEAD

Standardized MULTI SPINDLE DRILLING AND TAPPING SETS

Now available in
 $\frac{3}{16}$ in. to $\frac{3}{8}$ in. capacity—
 $2\frac{5}{8}$ in. to $10\frac{1}{2}$ in. p.c.d.



Standard H.11 set, comprising ten spindle multi-tapping head and standard base casting with fitted guide pillars, mounted to No. 5 Muller controlled-pitch tapping machine. Note special two-position sliding fixture mounted to standard base casting.



Standard H.13 set, comprising ten spindle multi-drilling head, jig bush plate, and standard base casting with fitted guide pillars, mounted to type "C" Herbert Machine.

Note: Special two position sliding fixture mounted to standard base casting.

THE MULHEAD ENGINEERING CO LTD

VICTORIA WORKS,

136-8 GREAT NORTH ROAD, HATFIELD, HERTS

TELEPHONE: HATFIELD 2296/7



When answering advertisements kindly mention MACHINERY.

Covering Every Field -

OF GEAR AND SPLINE HOBBLING

The unparalleled range of
Original Pfauter hobbers
meets every manufacturing
need.

May we forward literature?



Model P type Production Machine. P.500

Original **PFAUTER** *Hobbers*
FOR PACE • POWER • PRECISION

MANUFACTURING PROGRAMME Vertical Work Mounting

Pfauter Type No.	Max. Gear Dia. ins.	Max. Gear width ins.	Max. D P
R 16.....	3½	2	25
RS 00.....	10	6½	10
P 250.....	10	6½	7
DRA duplex	10	10	3
P 400.....	15½	11½	4½
P 500.....	20	14	3
RS IV.....	29½	12½	3
P 900.....	35½	15	3.2
RS 2V.....	39½	14½	2½
P 1250.....	49½	19½	2.1
RS 3V.....	71	21	2½
P 1800.....	71	24½	1½
P 2500.....	100	24½	1½

Horizontal Work Mounting



P i60.....	7	13½	6
RS 9K.....	11½	27	2½

Worm and Thread Milling Machines

SF 1.....	11½	27	1½ CP
-----------	-----	----	-------



Model R.16
for Instrument
Gears.




RS type Universal Machine. Model RS.3V.

VAUGHAN
ASSOCIATES LIMITED

Please let us demonstrate to you.

4 QUEEN STREET • CURZON STREET • LONDON, W.1. Telephone: GROsvenor 8362-5
Midland Office: Wilford Crescent, Nottingham. Telephone: Nottingham 88008



+GF+ Fully automatic Copying Lathes

Automatic programme:

Loading and unloading
Spindle actuation
Multi-cut cycle
Automatic diameter control

Setting up and changeover remains quick and easy.




The programme may be cut into at any time.

No rejects.

Two or more machines may be coupled together to form a fully automatic group.

One man can attend to several machines or groups of machines.

Every motion may be preselected individually, thus also permitting operation of the machine by hand.



Sole Agents in the U.K.

VAUGHAN ASSOCIATES LIMITED

4 QUEEN STREET, CURZON STREET,
LONDON, W.1. Telephone: GROsvenor 8362-5

Midland Office & Demonstration Room
WILFORD CRESCENT, NOTTINGHAM
Telephone: NOTTINGHAM 88008



ACHIEVEMENT IN STAINLESS STEEL CASTING

We must confess that we at BAKER'S are rather proud of this stainless steel casting. It involved a very difficult core technique to produce an internal spiral hole, true to size and with a good surface finish.

If you require carbon or alloy steel castings, simple or complicated, in large batches or small, from a few pounds up to 30 cwts., you can rely on BAKER'S OF NEWPORT to meet your most exacting demands.

Bakersteel

**CARBON AND ALLOY STEEL CASTING
UNSURPASSED FINISH AND QUALITY**

**W. A. BAKER & CO. LTD., WESTGATE WORKS, NEWPORT, MON., PHONE: NEWPORT 64845
DIVISION OF BLACK-CLAWSON INTERNATIONAL, LTD., MAKERS OF PAPER MILL PLANT**

When answering advertisements kindly mention MACHINERY.

ORIGINAL
EUTECTIC
WELDING ALLOYS

Head Office
and Factory
Feltham · Middx

HISTORY OF "EUTECTIC LOW TEMPERATURE WELDING ALLOYS"
Surface alloying at low heat was first discovered by "Eutectic" in 1904—used today in over 100,000 plants. "Eutectic" is the originator and sole manufacturer of "Eutectic Low Temperature Welding Alloys" for bonding metals at low heat, minimizing distortion, warping and stress.

EUTECTIC

Welding News

PUBLISHED BY EUTECTIC WELDING ALLOYS COMPANY LIMITED FELTHAM, MDDX

"LOW HEAT INPUT" INCREASES PRODUCTION JOINING 500%


Excessive and costly rejects in fusion-joining three copper pipes to a machined bronze casting, led a manufacturer of heating equipment to investigate the savings possible with modern fabricating techniques.

A high-melting silicon bronze rod was used, with three fusion welds, to obtain suitable density, strength and corrosion resistance. Top welders did the work to overcome the problems of distortion, warping and keeping the pipes parallel.

The manufacturer was satisfied (Photo A) until Eutectic's Technical Representative recommended EutecRod 1801, a thin flowing high silver alloy, used together with Eutector Flux 1801.

The three tubes were pre-fluxed with Eutector Flux 1801 and set up simultaneously. A large torch tip with a broad flame was used to heat the work and when the flux liquified, EutecRod 1801 was fed into the joint. Continuous motion of the torch, and the superior capillarity of the alloy, prevented localised overheating and distortion, allowing uniform fillets to form around the entire circumference of each tube (Photo B).

Due to the extreme ease of application of EutecRod 1801, perfect joints were produced. Filler alloy was reduced by 56 grammes to the 6.2 grammes of EutecRod 1801 required by the three joints. The joints showed superior strength, corrosion resistance and "eye appeal". EutecRod 1801 reduced working temperature by at least 300° C, and rejects were diminished.



EutecRod 1801, a thin flowing high silver content alloy with medium plastic range, is one of the lowest melting but strongest of all silver bearing alloys, with an ultimate tensile strength of 40 tons/sq. in. Joints are ductile and leakproof, offering exceptionally good corrosion resistance and electrical conducting properties.

EutecRod 1801: Available in sizes $\frac{1}{16}$ ", $\frac{3}{32}$ " dia., and strips to order from .020 x $\frac{3}{32}$ " to .003 x 1".

EUTECTIC WELDING ALLOYS CO. LTD.

NORTH FELTHAM TRADING ESTATE · FELTHAM · MIDDX · Phone: FELtham 6571
NEW YORK · LAUSANNE · FRANKFURT (m) · PARIS · MONTREAL · SAO PAULO · MEXICO



EUTECTIC WELDING ALLOYS CO. LTD. NORTH FELTHAM TRADING ESTATE · FELTHAM · MIDDX



Here is the completely revised 100 page Welding Data Book for 1959. Thousands of welding users keep this handy book within easy reach—every page is crammed with practical, valuable information—so much so that many call it the welder's 'Bible'. And it's yours free... from "EUTECTIC".

- ☐ Please send me further details of EutecRod 1801
☐ Please send my free copy of Eutectic's Welding Data Book

☐ Please send your Technical Representative for free consultation/demonstration

NAME

TITLE

ADDRESS

MAC. 12

EUTECTIC · LOW TEMPERATURE WELDING ALLOYS · FORMULATED FOR
· LOW HEAT INPUT · BONDING OF ALL METALS INCREASE SAVINGS
BY SALVAGE AND REPAIR, SOLVE PRODUCTION PROBLEMS

When answering advertisements kindly mention MACHINERY.


WILHELMSBURGER

MECHANICAL

Guillotine Shears

HYDRAULIC HOLD-DOWN · PNEUMATIC CLUTCH · AUTOMATIC ELECTRICAL CONTROL


WILHELMSBURGER



NOW AVAILABLE WITH

Power Tilting Table

*for cutting plate
at an angle
ready for welding*



MANY EXCLUSIVE ACCESSORIES
FOR UNIVERSAL USE



PAUL GRANBY & CO. LTD.

39 VICTORIA STREET · WESTMINSTER · LONDON · S W 1

Telephone: ABBEY 5338 Telegrams: POWAFORGE, SOWEST, LONDON Cables: POWAFORGE, LONDON

NRP 2162

When answering advertisements kindly mention MACHINERY.

We specialise in **CIRCULAR SAWS**

—and hold one of the largest stocks in the
United Kingdom of

Metal working high speed steel
SLITTING SAWS
SIDE CHIP CLEARANCE SAWS
and **SCREW SLOTTING SAWS**



our range also includes
MICA UNDERCUTTERS
SHEARING KNIVES
PAPER CUTTING KNIVES

and full range of cutting tools in
SOLID TUNGSTEN CARBIDE

- MOST COMPETITIVE IN PRICE ● BEST RESALE DISCOUNT
- FINEST FINISH AND PERFORMANCE
- and of course **IMMEDIATE DELIVERY**


Write today for stock list and prices to

ALEXANDER S. NEWALL
MACHINE TOOL CO. LTD.

287 FINCHLEY ROAD • LONDON N.W.3
Tel: **HAMPSTEAD 3855/9949**

When answering advertisements kindly mention **MACHINERY**.





THE NEW FULMER HONING MACHINE

for fast precision finishing of internal cylinders.

The Purfection Engineering Co. (Coleshill) Ltd., of Coleshill, near Birmingham, the United Kingdom makers exclusively recommend EVCO MEDIUM HYDRAULIC OIL for use in the NEW FULMER HONING MACHINE.

Evco Medium Hydraulic Oil is a product of

Edgar
Vaughan
Co Ltd

BIRMINGHAM 4, ENGLAND

Works at:

*Birmingham, Manchester, Liverpool, Southall
(Middx.), Bristol, Glasgow*

When answering advertisements kindly mention MACHINERY.

... *British-Built*

FULMER

HONING MACHINES

—Unsurpassed for precision with stock removal up to 1.2 cubic inches per minute.

AUTOMATIC FEED

RUGGED—RELIABLE—Automatic sizing or timed cycle on Open End—Blind End—Ported, Slotted or Shouldered Holes.

FULMER honing machines entirely eliminate the need for fine boring. The most economical production is obtained by ROUGH boring within 0.012in. to 0.015in. of finished sizes and then FULMER honing.

**STANDARD SIZE RANGE
FROM 1in. TO 30in. DIA.
STROKE 15in. TO 15ft.**

Write for descriptive leaflet.

PE

PURFECTION ENGINEERING

CO. (COLESHILL) LTD.

STATION ROAD • COLESHILL • WARWICKSHIRE

Telephone : COLESHILL 3351 P.B.X.




When answering advertisements kindly mention MACHINERY.

HEAVY PLATE WORKING MACHINERY

MACHINES FOR CUTTING AND FORMING HEAVY STEEL PLATES ARE NOW AVAILABLE FROM THE CONTINENT

We have the sole agency in the United Kingdom for Heavy Guillotines, Bending Rollers and Press Brakes, Hydraulic Presses and machines for shipyards, boiler makers, etc., dealing with plates up to 2in. thick. Quotations will be sent on receipt of your needs.

MODEL	LO 200-A	LO 200-C
Capacity	200 tons	200 tons
Working length	12ft. 3 $\frac{1}{2}$ in.	13ft. 11 $\frac{1}{2}$ in.
Between housings	102 $\frac{1}{2}$ in.	140in.
Throat	12in.	12in.
Weight (approx.)	20 tons	25 tons



200 tons PRESS BRAKES

Forming capacity in mild steel, 12ft. by $\frac{1}{2}$ in., with minimum flange, 4in.

These heavy duty straight sided press brakes are perfect specimens of good engineering design and construction. The main members are made from high-strength steel plates, electrically welded to form rigid units, with suitable braces which do not interfere with the setting, maintaining or operation of the machines. The ram and table have an extended horn for trunk or box work. The ram adjustment is by electric motor.

All high-speed shafts run in self-aligning roller bearings and a central lubrication system is operated from the crankshaft.

The control of the brakes is by a multiple-disc clutch operated by hand lever or treadle. The main drive motor is mounted for easy maintenance. Tools can be supplied to suit the job.

Delivery of both Machines Ex Stock, subject to prior sale. Fuller details on application.

Agents in the U.K. for Sirojexport
F.J. Edwards Ltd

EDWARDS HOUSE, 359-361 EUSTON ROAD, LONDON, N.W.1

Telephones: EUSton 4681 (7 lines) 3771 (4 lines)

Telegrams: Bescotools Norwest London

LANDSOWNE HOUSE, 41 WATER ST., BIRMINGHAM, 3

Telephones: CENtral 7606-8


Telegrams: Bescotools Birmingham 3

When answering advertisements kindly mention MACHINERY.



Practical extraction of the
performance of cutting
oils on a special lathe
at the BP Research
Station.

Quality control
for better
protection is
**... smoothing
the way
to higher
production**



Distributors

THE POWER PETROLEUM CO. LTD.


Head Office: 76/86 STRAND · LONDON · W.C.2 (Branches and Depots throughout the country)

Our Technical Department will be
pleased to advise on your lubrication
requirements and problems

When answering advertisements kindly mention MACHINERY.

GOOD TEETH...*Strength and Usefulness*

BEVEL GEARS
From $\frac{1}{4}$ in. to
8 in. diameter
Maximum DP 5

**WEEKS AND WILSON LTD.***GEARS AND GEAR CUTTING*

581, GREEN LANES, HARRINGAY, LONDON. N.8. TEL: FITZROY 0055-6

PARMEKO**Low Voltage Transformer Unit**

for safe
localised
lighting

Complete low voltage lighting systems, greater productivity, lower lighting costs, increased safety. By concentrating the light where it is most wanted, glare and shadows are avoided and precision work made easier. Lamp-life is increased since low voltage lamps withstand constant vibration much longer. Absolute safety is assured. The only design Parmeko Transformer Unit provides standard mains supply voltage to 25, 50 or 100 volts, thus eliminating the whole of wiring costs. The unit is self-contained, merely being mechanically disconnected from the consumer when circuit is required—and provides oil-tightness and safety. Complies with B.S. 704 and 171.

Lighting fittings can be supplied. A complete range of the transformer unit, incorporating low voltage sockets, is also available.



Write for the free 32p brochure and sample.
PARMEKO LTD., 100, GERRARD ROAD, LIVERPOOL, L15 3AB. Tel. 2238

Stepless speed variation over a 9 to 1 output speed range ($1/3$ to 3 times the input speed).

Constant horse-power transmitted throughout the speed range.

Flange mounted motors (when required) giving output speeds from 320 to 2880 r.p.m. and from 480 to 4320 r.p.m.

Output speeds as low as 3 to 27 r.p.m. can be obtained with flange mounted Reduction Gears. Special units are available for even lower output speeds.

Exceptionally light, sensitive and accurate control of speed setting

3 h.p. motorised variator

Kopp

VARIABLE SPEED GEARS

Co-axial input and output shafts which rotate in the same direction.

Service reliability resulting from a simple design manufactured to high precision limits.

Compactness, with consequent ease of mounting as an integral part of a machine.

Vibrationless and silent performance.

Standard range $1/33$ h.p. to 15 h.p.

**GEARLESS
GEARBOX**



PLEASE ASK FOR ONE OF OUR DEMONSTRATION
VARS TO CALL AT YOUR WORKS

ALLSPEEDS LIMITED

Wolverhampton Works • Clayton-le-Moors, Astrington, Lancs.
Telephone: Astrington 3461 (4 lines)

LONDON: 35 PARK ROAD NORTH, ACTON, W.3. TEL: ACORN 7155
BIRMINGHAM: BOX No. 1, CHALKTON, GLASGOW. TEL: BURY 2738
BIRMINGHAM: HIGH PARK STREET, COVENTRY. TEL: COVENTRY 4160
TORKENHURST: ALFATH ROAD, BIRMINGHAM. TEL: 3-146 3-0200
SOUTH WALES: P.O. BOX No. 1, 88TH CROSS, GLANMOR LANE. TEL: WALSLEY 322



Do you remember the test conducted recently where users were given a New Clarkson Truesize Reamer to test and asked to report on the results?

Clarkson New Truesize Reamers were tried under actual working conditions and the results show users to be overwhelmingly in favour of this new system.

Here are a few typical reports from satisfied users:—

"We are very pleased with the definite cutting qualities of your reamer as opposed to the heat generating characteristics of the more normal pattern."

"Your reamers are excellent. They give a quick cutting action with a perfect finish. We shall now use this type of reamer only for all our bore work."

"Your reamer has everything you claim for it, and we are very pleased with its great accuracy."

"Dead size. Very good finish on 200 aluminium castings with no sign of wear."

Try them yourself—and be another satisfied user!

Clarkson

TrueSize

REAMERS

*Use the Aximatic
Floating Holders
with Clarkson Reamers
for perfect control.*

CLARKSON (ENGINEERS) LTD. Head Office: Nuneaton. Phone: Nuneaton 2261
NEWCASTLE 241 Westgate Rd., 1 NEWCASTLE 1-5245 BRISTOL 17 Cumberland St., 3 Bristol 1-4444
BIRMINGHAM 15 Heath Mill Lane, 7 VICtoria 394 BELFAST 32 Shaftesbury Square Belfast 2075
LONDON 124 Hammermith Rd., W4 RIVERSide 841 GLASGOW 42a Crown St., C1 504th 1942
MANCHESTER 78 Oxford Road, 11 ARDwick 4104 LEEDS Room 6a, Britannia House, 1 Leeds 16390

When answering advertisements kindly mention MACHINERY.



*** LIES THE SECRET**
of successful Automatic Production

ON BATCHES AS SMALL AS 40 COMPONENTS

This new machine will give you on short runs three to four times more production than a capstan. It is worth while investigating.

Only

TAREX

GIVES TURRET ROUGHING & HYDROCOPY FINISHING

ensuring **SIMPLE TOOLING • FAST SETTING • QUICK CHANGEOVERS •**
HIGH PRECISION • FINE FINISH ELIMINATING MANY GRINDING OPERATIONS

SIX TYPES FOR BAR WORK FROM 1/2" TO 2 1/2" DIA.

TWO TYPES FOR CHUCKING WORK UP TO 2 1/2" DIA.

THREE UNIVERSAL MODELS FOR BAR WORK

UP TO 2 1/2" DIA. CHUCKING UP TO 2 1/2" DIA.

TAREX (England) LTD

22 BUCKINGHAM GATE

LONDON, S.W.1.

TELEPHONE
GATE GALLERY 3191

When answering advertisements kindly mention MACHINERY.

ZBROJOVKA**MILLERS****for heavy duty**

**Immediate delivery
of most models from
our London Showrooms**

**Sole Agents**

Precision heavy duty milling is a speciality of ZBROJOVKA MILLERS which operate with complete rigidity at the highest speeds. The illustration shows a FA5V Vertical Miller installed in the works of Messrs. C. J. C. Developments (Portsmouth) Ltd., by whose courtesy this photograph is published. Write or telephone for full information.

BRIEF SPECIFICATIONS OF HORIZONTAL, UNIVERSAL AND VERTICAL MILLERS

Sizes	No. 2	No. 3	No. 4	No. 5
Working surface of table (approx.)	40" x 8"	50" x 10"	64" x 12"	80" x 16"
Power longitudinal travel (approx.)	25"	32"	40"	50"
Power cross travel (approx.)	8"	9"	12"	16"
Spindle speeds	62-2800	45-2000	32-1400	18-1400

The Selson Machine Tool Co. Ltd

41-45 MINERVA ROAD, NORTH ACTON, LONDON, N.W.10

Telephone: Elgar 4000 (10 lines) Telegrams: Selsamachi, London, N.W.10




When answering advertisements kindly mention MACHINERY.

Increase production with NEW

PHILIPS 'Magna-Drum'

COOLANT CLARIFIER




Incorporating 'Magnadur'
ceramic magnets

- Higher Production rates
- Finish improved
- Completely automatic
- Fewer wheel dressings
- Coolant saved
- Sludging of settling tanks prevented

The heart of the New Philips 'Magna-Drum' coolant Clarifier is a compact unit which is magnetic over its whole surface area, and incorporates 'Magnadur' high power ceramic magnets. The equipment will filter straight cutting oils or soluble oil coolants without any modification. A very high proportion of grinding abrasive is always entrained in the ferrous swarf collected. Standard 'Magna-Drum' Clarifiers are available for handling flows of 300 g.p.h. to 7,500 g.p.h. British Patent No. 765495.

Larger equipments can be designed to suit special applications.




PHILIPS ELECTRICAL LTD

FILTRATION DEPARTMENT

Century House · Shaftesbury Avenue · London · W.C.

(190895A)

When answering advertisements kindly mention MACHINERY.



**ask for advice on
production holding
problems**

Have you thought that the most difficult production holding problems are being solved every day by the application of "Eclipse" magnetic chucks and tools? Why not pass your problems over to "Eclipse"?

Expert advice is available to you without obligation.



the only name for magnetic tools

Made by James Neill & Co (Sheffield) Ltd—the originators of this equipment
Supplies through your usual 'Eclipse' dealer.

PH. 144

When answering advertisements kindly mention MACHINERY.




PUZZLE CORNER?


Maybe some modern art *is* bewildering; but let's be fair. Perhaps if you were as skilled in art appreciation as you are in production engineering, you could answer this one too.

We pride ourselves at Webster and Bennett that we know most of the answers when it comes to boring and turning, and our customers agree. In fact, our own "puzzle corner" is always busy translating customers' drawings into machinable possibilities, and quite often remarkably favourable floor-to-floor times result.

If you have to machine castings and forgings up to 80" swing, perhaps we can help you. Send us drawings of your components; our technicians will be glad to submit production proposals.



"A standard Webster and Bennett Boring Mill with 60" Chuck, admitting 35" under the turret and 24" under the cross-slide".



WEBSTER & BENNETT LTD., COVENTRY, ENGLAND

When answering advertisements kindly mention MACHINERY.

F+

CHRISTMAS GIFTS FOR ENGINEERS

A "MACHINERY" TECHNICAL BOOK IS A THOROUGHLY PRACTICAL GIFT ... IT WILL BE TREASURED BY CONSTANT DAY-TO-DAY USE LONG AFTER FESTIVITIES ARE FORGOTTEN

Write for a Book Catalogue with details of MACHINERY'S Plan for Payments by Instalments.



Here are a few suggestions which will appeal:

	Cash C.O.D.	Instal Price
MACHINERY'S HANDBOOK	72/-	80/-
ELEMENTARY MATHEMATICS	12 6	13 9
MACHINE TOOLS AT WORK	52 6	58/-
CENTRE LATHE WORK	18 6	20/-
JIG & FIXTURE DESIGN	40/-	44/-
MACHINE SHOP TRAINING COURSE (2 Vols.)	75/-	82 6
PIPE & TUBE BENDING	43/-	48/-
TESTING MACHINE TOOLS	17 6	19 3
MACHINE TOOL RECONDITIONING	129/-	132/-
PRACTICAL ENGINEERING METROLOGY	30/-	33/-

	Cash C.O.D.	Instal Price
INGENIOUS MECHANISMS (3 Vols.)	132/-	146/-
INDUCTION HEATING	12 6	13 9
STRENGTH OF MATERIALS	40/-	44/-
FUNDAMENTALS OF PRESS TOOL DESIGN	12 6	13 9
INDUSTRIAL LUBRICATION PRACTICE	75/-	82 6
DIE DESIGN & DIE MAKING PRACTICE	65/-	72/-
DRAWING OFFICE HANDBOOK	16/-	17 6
DIE CASTING DIE DESIGN	18 6	20/-
CAPSTAN & TURRET LATHE PRACTICE	18 6	20/-
TOOL & CUTTER GRINDING	18 6	20/-
MACHINERY'S SCREW THREAD BOOK	10/-	11/-

MACHINERY'S YELLOW BACKS (Over 60 Titles) 5/- each

You can buy
MACHINERY'S BOOKS
by CASH, C.O.D. or
INSTALMENTS.

All titles sent (U.K. only)
ON APPROVAL
NO DEPOSIT.
Write for complete
Catalogue.

To MACHINERY, National House, 21 West Street, Brighton, I.
Please send me.....

For CASH herewith or by C.O.D. or ON APPROVAL
when I will return in 5 days, or
pay FULL CASH, or by INSTALMENTS, as stated above.




Name..... Position.....

Address..... Firm.....

When answering advertisements kindly mention MACHINERY.

Schaublin SV 13

A SWISS PRECISION MILLING MACHINE
MADE FOR ALL WORK




Write to-day
for catalogue
giving further
details of this
machine.

For precision milling in tool and die-making shops, development and research departments, and wherever highly accurate work is the first requirement. A truly universal machine built to exceptionally high Swiss standards.

WICKMAN & SONS LIMITED

FACTORED MACHINE TOOL DIVISION, FLETCHAMSTEAD HIGHWAY, COVENTRY

Telephone: Coventry 74821



Have
you
a
pressing
need?



KE 47A is an excellent general purpose oil hardening tool steel. When worked under normal conditions it is trouble free and ideal for a wide variety of blanking, pressing and piercing operations.

KE 47B is a first class low temperature oil hardening tool steel with deep hardening properties. It is an excellent steel for gears and tools of intricate shape where final grinding after hardening is not permissible.

KE 57B is an oil hardening tool steel with deep hardening properties and extra wear resistance. Due to its toughness it is suitable for processes involving greater tool wear.

KE 58B is a 2% Carbon 14% Chrome High Duty Tool Steel, used for a variety of stamping, blanking and pressing operations. For increased toughness at a slight loss in hardness we supply KE 58F 1 1/2% Carbon 12% Chrome Steel.

KAYSER ELLISON & CO LTD

CARLISLE STEEL WORKS SHEFFIELD
TELEPHONE: SHEFFIELD 22174 ESTABLISHED 1925

London Stock Warehouse:

4 Parkbridge House, Notting Hill Gate, W.11 Tel. Rm 9042/3


Midland Stock Warehouse:

Station Road, Colcham, Birmingham. Tel. Colcham 3041/2

This booklet gives greater detail.
It is available free on request.

When answering advertisements kindly mention MACHINERY.

A new automatic
wheel turning lathe
with hydraulic
copying attachment



*a pair
of mounted wheels $37\frac{1}{2}$ D.^{1A}
reprofiled in $6\frac{1}{2}$ mm.*

Etablissements
SCULFORT-FOCNEDEY VAUTIER & C^o
HAUDENGE (FRANCE)

Write for bulletin 6417 and literature

TOUR **Sculfort**



JOSEPH


RHODES

& SONS Ltd

Of WAKEFIELD ENG. *Etab. 1824*
THE LATEST DEVELOPMENT IN

FLUID-DRIVEN**SHEARING MACHINES****RHODES****HYDRAVERSAL**

Patent applied for



Does the work of 5 machines
Costs less than 1

When answering advertisements kindly mention MACHINERY.




94 years of **REXITE** Service

TO USERS OF GRINDING WHEELS •

GRINDING WHEELS AND
SEGMENTS FOR ALL
PURPOSES

VITRIFIED AND RESINOID
BONDS

CATALOGUES ON REQUEST



MITCHELL'S EMERY WHEEL CO. LTD.

EST-1862

PROGRESS WORKS • OPENSHAW • MANCHESTER 11 •

TELEPHONE: EAST 1254 (3 LINES)

When answering advertisements kindly mention MACHINERY.



YOU TOO *can now buy the world's finest electric tools*

I know from your hundreds of letters (said the Managing Director) how you have *longed* to own a Desoutter Electric Tool. Now you can go to your usual Tool Merchant or Ironmonger and buy one. It is as easy as that! This does not mean we are discontinuing our 30-year old policy of supplying customers direct nor that we are going into the 'home handicrafts' business with a cheap tool. If your usual

supplier by some extraordinary oversight is not stocking Desoutter Tools, write at once to any of our main distributors (the first three are shown below) or direct to me at Hendon and you'll be supplied even if it means I have to bring the blessed thing along personally! My one aim and intention is to serve you!

*("At a certain profit" muttered
a rather cynical customer)*

G. A. Robinson
(Stoke-on-Trent) Limited
Hartshill, Stoke-on-Trent

Buck & Hickman Limited
London & all branches

A. J. Howard
19 Alexandra Street
Southend-on-Sea


DESOUTTER ELECTRIC TOOLS FOR YOU

Desoutter Brothers Limited, The Hyde, Hendon, London NW9. Tel: Colindale 6346.


CRC 308

- Horizontal Lathes, Vertical Turning and Boring Mills, Face Lathes of heavy and medium size.
- Rolling Mill Roll Lathes. Special Roll Grooving Lathes with copying device.
- Rolling Mill and Paper Mill Roll Grinders.
- Heavy and medium size Planers.
- Heavy and medium Plano-Milling Machines.
- Crankshaft Roughing Lathes.
- Square, round and polygonal Ingot Lathes.

Planer with planable width 80"



Parallel Lathe, swing 120"





STABILIMENTI
S. EUSTACCHIO
BRESCIA (ITALY)



- Sheet Straightening Machines.
- Automatic Selfcompressor Hammers.
- Mechanical and Hydraulic Presses.
- Complete Rolling Mills for steels and soft metals.
- Designing and building of any special heavy machinery.
- Special cast iron rolls for rolling mills and for all industrial uses.
- Cast iron ingot moulds of all types and sizes.

Roll grooving and turning lathe, swing 28"



AMAR***interchangeable* TOOL SET****Bigger range and new features**

Now available in four sizes of bolster sets to accommodate twelve sizes of dies from 3" x 3" to 7" x 9". Tool changing is achieved on the press within seven minutes, without disturbing bolsters. Bolsters on the larger sizes incorporate ball-bearing bushes, for easy assembly and freedom from jamming.

Manufactured under British Patent No. 709066

For full information write for publication 1109


AMAR TOOL AND GAUGE COMPANY LIMITED

Amar Works, Grove Road, Chadwell Heath, Essex

Telephone: Seven Kings 3471-2-3, 5090 and 5369 • One of the Plessey Group of Companies

 P.T.4a

When answering advertisements kindly mention MACHINERY.




1

The range of **VICTORIA** VICES




2



3

**ALL VICTORIA VICES
ARE GUARANTEED
AGAINST BREAKAGE**



4

- 1 **SELF CENTERING SHAFT VICE**
4 1/2 in. width of jaws. Round bar capacity, 3/4 in.—3 1/2 in. dia. Bases accurately machined at 90° to each other.
- 2 **ALL STEEL UNBREAKABLE MACHINE VICE**
3 1/2 in., 4 1/2 in. or 6 in. width of jaws. Plain or swivel base models. Precision ground jaws.
- 3 **HEAVY DUTY MACHINE VICE**
7 1/2 in., 9 1/2 in., 10 1/2 in. or 11 1/2 in. width of jaws. Hardened and precision ground jaws.
- 4 **SEMI STEEL MACHINE TOOL VICE**
3 in., 4 1/2 in. or 6 in. width of jaws. Two 6 in. models either 5 in. or 6 1/2 in. opening. All sizes available with either plain or swivel base. New design eliminates use of dovetails and provides clear flat supporting area between the jaws.

OBTAINABLE FROM LEADING ENGINEERING TOOL MERCHANTS

Manufactured by
B. ELLIOTT (MACHINERY) LTD.
 (MEMBER OF THE E. ELLIOTT GROUP)
 VICTORIA WORKS, WILLESDEN, LONDON, N.W.10
 Telephone: ELGAR 488 (10 lines) Telegrams: Ellittons, Harles, London
 Overseas Subscribers: CANADA, U.S.A., AUSTRALIA, S. AFRICA



When answering advertisements kindly mention **MACHINERY**.

wisdom teeth...

Gas carburising in a Birlec furnace gives the young gear-wheel a good start in life. Hardened to resist daily wear and tear, toughened to withstand shocks, he is assured of a long and honourable career.

BIRLEC GAS CARBURISING FURNACES are available in batch and continuous types with reliable atmosphere control equipment and cooling or quenching facilities.



BIRLEC LIMITED

An A.E.I. Company

ERDINGTON : BIRMINGHAM 24

SM/B4107

When answering advertisements kindly mention MACHINERY



LONDON
SHEFFIELD
GLASGOW
NEWCASTLE-ON-TYNE
JOHANNESBURG

MACHINERY is registered as a newspaper at the General Post Office and the name is a registered trade mark

Published every Wednesday by
The Machinery Publishing Co., Ltd.

© The Machinery Publishing Company, Limited, 1958. All rights of reproduction and translation reserved by the publishers by virtue of the Universal Copyright and International Copyright (Brussels and Berne) Conventions and throughout the World
Price 1/3

LESLIE R. MASON
Managing Director

CHARLES H. BURDER
Editor

LONDON OFFICE

REGISTERED OFFICE, EDITORIAL, SMALL AND CLASSIFIED
ADVERTISEMENTS DEPARTMENT AND ENQUIRY BUREAU

CLIFTON HOUSE
83-117 EUSTON ROAD
LONDON, N.W.1.

Telephone: Euston 8441/2
Telegrams: Machtool, Norwest, London

HEAD OFFICE

SUBSCRIPTION, ADVERTISEMENT, SERVICE,
PHOTOGRAPHIC, ACCOUNTS AND BOOK DEPARTMENTS

NATIONAL HOUSE
21 WEST STREET
BRIGHTON, 1

Telephone
Brighton 27356
(4 lines)



Telegrams:
Machtool,
Brighton

NEW YORK:
93, Worth Street

PARIS
15, Rue Bleue

SUBSCRIPTIONS:—Inland and overseas,
52 shillings per annum, post free. Cheques
and Money Orders should be made payable
to the Machinery Publishing Co., Ltd.

ADVERTISEMENTS:—Copy or displayed
advertisements, if proofs are required, should
reach the Brighton office 21 days in advance
of publication. Rates on request.
Small (classified) advertisements can be
accepted, space permitting, at the London
office up to Wednesday, for publication
on the following Wednesday. For rates,
see p. 165.

Blocks are held at advertisers' own risk;
no responsibility for loss is accepted by the
publishers

MANUSCRIPTS FOR BOOKS covering all
branches of engineering production will be
received with careful consideration and should be sent
to the Manager, Book Dept., MACHINERY,
National House, 21 West St. Brighton 1.

MACHINERY

A JOURNAL OF METAL-WORKING PRACTICE
AND MACHINE TOOLS

Vol. 93, No. 2403

December 3, 1958

COPIES PRINTED.....11,500 per week

CERTIFIED DISTRIBUTION11,376 per week

CERTIFIED PAID DISTRIBUTION10,566 per week

CONTENTS

Editorial

Russia—A Challenge 1271

Principal Articles (For Abstracts see next page)

Aspects of Russian Engineering Industry..... 1272
Electronically-controlled Press Feed for Transformer Lamination Strip 1287
Operations on Ford Rear Axle Differential Spiders 1289
Optical Location System for a Turret Punch Press..... 1292
Machining Operations on Honeycomb Structures 1295
Set-up on a Conomatic for Producing Wedge Gate Valve Seats 1310
The New Ludwigsburger Factory 1313
Buswell & Sweeney Master Bar Jig Borer 1317

Short Articles

Ball Bearings Made from Plastics 1286
G.E.C. Reversing Starters 1291
Installation for Hot-forging Stainless-steel Bolts 1293
Birlec Dual-frequency Billet Heating Installation 1294
New Michigan Spline-rolling Technique 1300
Crosland Work Tables with Automatic Adjustment for Height 1312

New Production Equipment

Norton Industries 40-ton Inclined Power Presses..... 1301
Baker Perkins Taccone Diaform Diaphragm Moulding Machine 1301
Leifeld Type Plb 1200 Hydraulic Spinning Lathe 1302
Prototype Developments Optical Projector 1303
Large Michigan Gear Shaver 1304
Bammesburger Special-purpose Machines 1305
D'Andrea Boring and Facing Head 1305
Digimatic Automatic-positioning Work Table and Control System..... 1306
Startrite-Meba Horizontal Bandsawing Machine 1307
Brown & Ward Automatic Bar Feed Unit 1308
New Wheel Dresser for Churchill Type BW Plain Grinder.. 1309

News of the Industry

Bradford 1319
British Machine Tool Imports and Exports (Classified)..... 1326
Classified Advertisements..... 165
Index to Advertisers..... 193

CONDITIONS OF SALE AND SUPPLY.—MACHINERY is sold subject to the following conditions:

That it shall not, without the written consent of the publishers first given, be lent, resold, hired out or otherwise disposed of by way of trade except at the full retail price of 1s. 3d. and, that it shall not be lent, resold, hired out or otherwise disposed of in a mutilated condition or in any unauthorized cover by way of trade; or affixed to or as part of any publication or advertising literary or pictorial matter whatsoever

[p. 1269]g

Abstracts of Principal Articles

Aspects of Russian Engineering Industry P. 1272

In this article, which concludes the series on Russian engineering plants and other establishments, reference is made to two closely associated works in Leningrad. The Metallic plant is the largest in the U.S.S.R. for the construction of steam and water turbines. Of particular interest are the facilities that have been provided for the machining of large water turbine components, in order to meet the demands of the latest electrical power programmes for the Volga and Siberian rivers. The equipment includes a large duplex copy-milling machine for semi-finishing the surfaces of propeller blades; a grinding machine for finishing the blade surfaces; a special horizontal turning and facing machine for operations on the blade flanges; and a double-end horizontal turning machine for guide vanes. Electrical equipment for the steam and water turbines is supplied by the Electrosila plant, which is claimed to be the largest for this type of equipment in Europe. There are separate shops of large area for the building of generators of each type, and some very large machine tools are installed. Welding is widely employed for the construction of large generator components. (MACHINERY, 93—3/12/58.)

Electronically-controlled Press Feed for Transformer Lamination StripP. 1287

Subsequent to an earlier article in MACHINERY on the flow-line methods employed by Ferranti, Ltd., for the manufacture of distribution transformers, details are here given of the production of laminations for the lock-wound cores. The laminations are produced from 0.014-in. thick coiled material on a 40-ton Hordern, Mason & Edwards type L40 press to which the company have fitted a motorized coil cradle and a fully-automatic electronically-controlled feed unit, whereby laminations of any length required can be cut to an accuracy of 1/64 in. The required length of feed is pre-set on a Londex electronic unit which has four knobs that represent units, and units $\times 10$, $\times 100$, and $\times 1,000$. There are four dekatron counters operating in conjunction with a photo-electric cell and a large-diameter slotted disc, which is driven from the lower feed roll shaft. When the required length has been advanced, the feed is automatically stopped and the press clutch is engaged. During the press stroke, a cam on the crankshaft resets the feed unit. (MACHINERY, 93—3/12/58.)

Operations on Ford Rear Axle Differential SpidersP. 1289

Differential spiders employed in Ford commercial vehicles are machined from alloy steel forgings of cruciform shape. At the first major operation, the four arms are roughed on a special hollow-turning machine. After two of the arms have been turned, the component is automatically indexed, to bring the other

arms into position. Rough grinding follows, and the arms are then induction surface hardened on general purpose equipment which provides for the treatment of 18 different components. (MACHINERY, 93—3/12/58.)

Machining Operations on Honeycomb StructuresP. 1295

An account is here given of a series of experiments which have been carried out by General Electric Co., U.S.A., on various methods of machining honeycomb structures. Of nine different types of milling cutters which were specially designed, only two were wholly successful, and both of these were of the knife-edged disc type. Both could be operated at surface speeds between 2,400 and 3,200 ft. per min., at feed rates as high as 30 in. per min. The use of various types of filler material is discussed, including sodium silicate mixed with either iron powder or stainless steel powder. Holes can be produced in honeycomb structures by the electrolytically-assisted grinding process, using a special solution of non-corrosive electrolytic salts in place of the standard coolant. For sawing the structures, a DoAll bandsaw was used which had a maximum speed of 10,800 ft. per min. Various types of blades were employed, including the conventional toothed type, but single- and double-bevel knife edge blades proved most satisfactory from the standpoint of cleanness of cut. (MACHINERY, 93—3/12/58.)

Set-up on a Conomatic for Producing Wedge Gate Valve SeatsP. 1310

A specially-equipped British-built Conomatic 1½-in.-6 machine is employed for machining wedge gate valve seats from stainless steel bar in a cycle time of 38 sec. The valve seat has a 5-deg. angular front face, which is machined by means of a special angular facing attachment mounted on the end-working slide. The tool-holder is prevented from rotating, and the required pivoting movement is imparted by a co-axial spindle driven in synchronism with the work spindles. A zero mark, coincident with the low point of the 5-deg. taper, is scribed at the sixth position by a rotating attachment on the end working slide. (MACHINERY, 93—3/12/58.)

Contributions to MACHINERY

If you know of a more efficient way of designing a tool, gauge, fixture, or mechanism, machining or forming a metal component, heat treating, plating or enamelling, handling parts or material, building up an assembly, utilizing supplies, or laying out or organizing a department or a factory, send it to the Editor. Short comments upon published articles and letters on subjects concerning the metal-working industries are particularly welcome. Payment will be made for exclusive contributions.

Russia—A Challenge

In this issue of MACHINERY is published the concluding article in the series on the Russian engineering industry, which was prepared by a member of our editorial staff who visited Moscow and Leningrad earlier this year. An attempt has been made in this series to give a factual account of some typical factories in what are still two of the most important industrial centres of the Soviet Union. The plants described have covered a wide range of products, which have included machine tools, cutting tools, motor vehicles, ball and roller bearings, steam and water turbines, heavy electrical equipment, and steel strip and wire. These articles have been published solely because we believe that British engineers should be kept informed of Soviet industrial progress.

During the past 10 to 15 years, some remarkable advances have been made in Russian industry, and the rate of advance is being maintained, if not accelerated. The results achieved have been due partly to careful overall planning, but even more, perhaps, to the very extensive research facilities that are available to industry, and to the ample supply of trained scientists, technologists and engineers provided by Russian educational establishments. Two research institutes have been discussed in this series, one of which has a total staff of 4,000, the other, more than 2,000. These figures include the employees in the workshops for building experimental machines and equipment, but technicians, designers, and higher-grade research workers form the major proportion of the staff of each institute. It should be pointed out, moreover, that these institutes are only two among many similar centres for industrial research in various parts of Russia.


From information obtained during the visit it would appear that the Russian educational system is inclining increasingly towards the sciences and technologies. Every encouragement is given to industrial employees of all grades to improve their standards of education, for example, each qualification that is gained entitles the holder to a specific increase in salary. Almost all factories have provisions for technical training, and these facilities form part of a planned system of scientific and technological education for the whole of Russia. As an indication of the trend of Russian education, attention may be drawn to the arrangements for higher education in Moscow. Here, the old

university, near the centre of the city, accommodates about 1,000 students of the humanities, whereas some 24,000 students of the exact sciences occupy the new university in open surroundings on Lenin Hills. Again, it should be noted, this new university is only one of many establishments for higher scientific training in the Soviet Union.

In contrast to what is being done in most Western countries, large numbers of women are studying engineering and allied subjects in Russia. In the majority of the factories visited during the preparation of these articles, women formed more than 50 per cent of the technical staffs, and it may be noted that women were in charge of several of the technical departments. At one of the largest machine tool plants in Moscow, moreover, a woman had the post of deputy director, and engineering is generally held to be a suitable and worthwhile career for women in Russia. Indeed, the engineering industries enjoy a very high status, which may account for the enthusiasm that was evident among all grades of workers, whether men or women. This enthusiasm is further stimulated by propaganda associated with the drive to beat the industrial output of the West, which is assuming the nature of a "crusade."

In spite of the efforts that have been made during the past 15 years, in connection with the building of new plants, research into new materials, equipment and techniques, and the provision of increasing numbers of scientists and technologists, Russia is still faced with formidable tasks in the development of her natural resources, the further expansion of her industries, and the provision of the consumer goods that are necessary for the improvement of the living standards of the people. Nevertheless, she is already directing her attention towards export markets for her engineering products, particularly in some undeveloped countries. In this connection, it may be of interest to note that one of the largest machine tool works in Moscow exports about 40 per cent of its output, mainly to countries of the communist bloc, but also to India, Egypt and the Middle East. Once her own needs have become less pressing there can be little doubt that Russian efforts in the export field will be substantially increased. As a result of planning and rationalization of industry, it has been possible to provide high-output plants for the

(Continued on page 1322)



Aspects of Russian Engineering Industry

Some Impressions Based on a First-hand Study of Soviet Plants

Earlier articles in this series* have been concerned with the growth of the Russian machine tool industry; the design of some modern Soviet standard and special machines; automatic transfer machining lines; representative Russian machine tool and cutting tool works; two of the large industrial research establishments that serve Soviet industry; a large works for the manufacture of ball and roller bearings, which incorporates an automatic plant for the production of two types of bearings; a large factory building commercial vehicles and bicycles; and a works for the rolling and drawing of steel wire and strip. In this article—which concludes the series—two important manufacturing plants in Leningrad will be considered, namely, the Metallic Turbine Works and the Electrosila Electrical Plant.

THE METALLIC TURBINE WORKS

The Metallic plant is claimed to be the oldest in Leningrad, and the centenary of its foundation was celebrated in 1957. Even before the revolution, the plant was engaged in the building

of steam turbines, which were of foreign design, for driving generators of 200 kW. output. The plant has been greatly expanded since the revolution, and it is still the largest in the Soviet Union engaged in turbine work, with separate sections for building steam and water turbines. Considerable assistance in connection with the expansion of the plant was received from the Metropolitan-Vickers Electrical Co., Ltd., and this company is held in high esteem by the senior engineers of the Metallic works.

Some 11,000 people are employed at the plant, of whom 2,000 to 2,500 are technical staff, and, as in other Soviet plants, there are well-organized training facilities and welfare services. Forty per cent of the technical staff, and 15 to 20 per cent of the factory workers, are women. We were informed that the time required to build a new steam turbine is two years from receipt of order, including the period required for research and development. The actual time required in the production shops was stated to be six to eight months, and it was indicated that the latter period suffices for executing a repeat order. Each water turbine is designed to suit the requirements of the particular power station in which it is to be installed, and the building times for such turbines do not vary

* MACHINERY, 93/4-2/58; 93/137-16/7/58; 93/174-23/7/58; 93/288-6/8/58; 93/345-13/8/58; 93/456-27/8/58; 93/572-10/9/58; 93/864-15/10/58; and 93/1272-3/12/58.

appreciably from those quoted. The generating equipment for both steam and water turbines is supplied by the Electrosila works.

STEAM TURBINES

Before 1941, the turbines built by the Metallic plant were of the low-pressure type, and the largest was for a generating set of 100 MW. output. At that time, a development programme was in hand for the construction of a turbine for a 25-MW. generating set, with a maximum working pressure of 425 lb. per sq. in. All work associated with turbine production was abandoned during the second world war, and when work was resumed in 1944, it was decided to concentrate on the development of high-pressure machines.

The first large turbine of this type was completed in 1946, and had a maximum working pressure of 1,320 lb. per sq. in. This machine was built for a 100-MW. generator set, and for a considerable period the output of the Metallic plant consisted mainly of units of similar type. At the same time, development work was proceeding in connection with turbines of greater output, and, in 1951, work was started on a turbine to operate at a maximum pressure of 2,500 lb. per sq. in., for a 150-MW. generator. Several very large turbines have been built for Moscow and other power stations, and this

year a high pressure turbine for a 200-MW. generator will be completed. All steam turbines built by the plant operate at 3,000 r.p.m., and preliminary development work has been initiated in connection with a turbine operating at 2,500 lb. per sq. in. for a 300-MW. generator set. We were informed that the plant has the necessary facilities for building a machine of this large size, and that it was hoped to have such a machine in operation within the next few years.

Turbines built by the Metallic plant operate with a steam inlet temperature of 565 deg. C. (1,049 deg. F.). Generally, a steel casting is employed for the high-pressure cylinder, but the low-pressure cylinder is of welded construction. Blades are made from a pearlitic stainless steel, which contains up to 13 per cent of chromium, and 0.15 to 0.20 per cent of carbon. The longest blade normally employed is 66 cm. (25.984 in.), but trials are now being carried out to determine the effectiveness and practicability of blades up to 76.5 cm. (30.118 in.) long.

WATER TURBINES

In comparison with the building of steam turbines, the design and construction of water turbines is a fairly recent development. At first only low-power units were built, but by 1941, the plant had




Fig. 1 The runner and casing for a large water turbine built by the Metallic plant, Leningrad, are here seen at one end of the main bay of the water turbine shop

constructed several water turbines with rotors of 30 ft. diameter for generators of 65 MW output, and it may be of interest to note that these units are still in operation. An extensive programme of development and research work relating to water turbines has been carried out, and since the last war many large units have been built. Among these turbines may be mentioned three replacement units for the large Dnepropetrovsk power station which was seriously damaged during the war. Originally, this station was equipped with nine American Francis turbines, and six of the new units were obtained from the U.S.A. The new Russian turbines are designed to operate at 83 r.p.m.

A large water turbine building programme is now in progress at the plant in connection with the Volga power development scheme. Turbines for this scheme are the largest that have been built at the Leningrad works, and will drive generators of 126 MW. output. The turbine rotors are 30 ft. 6 in. diameter and each complete turbine weighs 420 tons. Twenty such turbines have been installed in the Kurbushev power station and operate at 68 r.p.m., and at the time of our visit, similar units were under construction for the station at Stalingrad, where 22 turbines will eventually be installed. A typical turbine runner and casing are shown in Fig. 1, and it will be observed that the runner is of the feathering Kaplan type. An indication of the size of the runner can be obtained by comparing it with the workman seen below one of the vanes at the left.

During the next four years, similar turbines are

to be built for other power stations on the Volga, in addition to those mentioned, and because of the large number that is required and the delivery dates that have been specified, new production techniques have had to be developed, to which reference will be made later in this article. Further developments in manufacturing methods are also planned in order to facilitate the building of hydro-electric generating equipment for the power projects on the main rivers in Siberia. Here, several new stations will be built, each of which will have an output of 4,000 MW. The turbines at these stations will drive generators of 200 to 300 MW. capacity, and it is planned to build and install this equipment within the next few years.

The water turbines mentioned so far have been of the conventional type, with vertical runner shafts and generators mounted above the runner casings. It may be noted, however, that two propeller turbines have been built with horizontal shafts, and these units are now being employed for trials and development work. Each turbine has a runner of 10 ft. 10 in. diameter, with feathering blades, which runs at 125 r.p.m. The runner shaft is mounted in bearings housed in a "torpedo," coaxial with the turbine casing, and the torpedo is supported by aerofoil-section struts at each end of the casing. A vertical strut at the down-stream end provides for the passage of the blade-feathering control shaft, and control vanes are mounted radially at the up-stream end. The 6,300-kW. generator surrounds the runner casing, and we were given to understand that the rotor of the generator is connected to the outer ends of the runner blades.

STEAM TURBINE SHOP

Steam turbines are now built in a shop which was first laid down in 1928, with the collaboration of the Metropolitan - Vickers Electrical Co., Ltd. At that time, it was the only shop for the specialized construction of steam turbines in the U.S.S.R.,





Fig. 2. Turning a large component for a steam turbine on a Craven lathe in one of the machining bays of the Metallic plant

Fig. 3. This shaft for a large gas turbine has been built up, by electric arc welding, from seven components of austenitic stainless steel with a total weight of 6 tons



and even now 50 per cent of the Russian-built turbines are constructed here. The shop has been extended from time to time, and it now measures 656 ft. long by 180 ft. wide. It is divided longitudinally into two bays, one of which provides for heavy machining operations, and the other for the erection and testing of turbines. There are four gantry cranes in each bay, and, by using two cranes simultaneously, loads weighing up to 50 tons can be lifted. The height to the underside of the cranes is 59 ft. Turbine components are transported from the machining bay to the erection bay by means of an electrically-driven truck, which runs on rails in the shop floor.

At the time of our visit, three turbines were being built, and these units were for driving generators of 50, 100, and 200 MW. capacity. The largest turbine, which was complete, operates at a maximum pressure of 1,900 lb. per sq. in. This machine is being retained in the Metallic plant for research work, including investigations concerned with long turbine blades.

A variety of Soviet and foreign machine tools is installed in the machining bay, including a large Sellars vertical boring mill with a capacity for machining workpieces of 20 ft. diameter, also Schiess and Richards mills of similar size, all these machines being fairly old. There is a battery of Russian and other horizontal boring machines, among which we noted several by Giddings & Lewis, and a Skoda machine with a 7 $\frac{1}{2}$ -in. spindle and a 20-ft. column, which was engaged in machining a high-pressure cylinder.

Among the lathes were three large Craven machines which were about 10 to 12 years old. These lathes accommodate workpieces up to 8 ft. diameter, and the beds are 50 ft. long. A close-up view of one of these machines is given in Fig. 2, and they are mainly employed for machining shafts,

although some outside contract work is undertaken. At the time of our visit, one of the lathes was being used for turning a large blooming roll for a works in the Leningrad area.

The plant includes heavy-duty balancing equipment for checking completely assembled turbine rotors. Since the rotor of a 200-MW. turbine weighs approximately 38 tons, special provisions are made for starting at driving shaft speeds as low as 2 r.p.m., with a very high torque. Other equipment included a rig developed in the plant for high-frequency induction heating rotor discs before they are shrunk on to the associated shaft. This method of heating is very rapid and it is stated that the temperature difference between the bore and the periphery of the disc is less than 30 deg. C.

Much work has been carried out at the Metallic plant in connection with rotor shafts of built-up welded construction. A shaft of this type has been fitted in a water turbine for the Kurbushev power station, and is of approximately 7 ft. diameter. When this article was being prepared, a large built-up rotor shaft for a gas turbine was being welded in the steam turbine shop, and a view of this shaft is given in Fig. 3. The shaft is made from seven rings of austenitic stainless steel, and has a total weight of 6 tons. Welding is performed by hand, using the electric arc process, and the time required for the complete welding operation is 1 month. When the shaft is finished, the maximum run-out must not exceed 0.3 mm. (0.011 in.). The gas turbine is designed to run at 3,000 r.p.m. and will drive a generator of 12,000 kW. capacity.




Fig. 4. Boring the apertures for the propeller blade shafts and seating flange registers in the body of the runner for a large water turbine on a Schiess-Defries turning and boring mill

WATER TURBINE SHOP

The water turbine shop, which was built in 1935, is 853 ft. long by 108 ft. wide, and comprises a central main bay, with secondary bays at either side. There are five gantry cranes in the main bay, the largest crane having a lifting capacity of 150 tons. Among the equipment installed is a cast-iron erection plate measuring 65 ft. square, but this plate is stated to be inadequate for building the largest turbine assemblies. There is a variety of very large machine tools, including some which have been specially built for operations on large water turbine components. When necessary, however, certain of the machines are also employed for operations on the larger components for steam turbines.

There are several conventional vertical boring and turning mills of the largest size, one of which was built jointly by a number of Leningrad plants, and has a table of 30 ft. diameter. At the time of our visit, this machine was being used for opera-

tions on the rotor of a Francis-turbine for a 85-MW. generator. This rotor was a steel casting, weighing about 75 tons, but it may be of interest to note that, in future, these components are to be fabricated by welding.

The largest machine in the shop is the Schiess-Defries vertical turning and boring mill seen in Fig. 4, which can be used for operations on workpieces weighing up to 180 tons. Diameters up to 50 ft. can be swung on the table, and the latter member is made in two parts, which are independently driven. The inner table is 20 ft. diameter and the maximum diameter of the outer ring is 36 ft.

In addition to that mentioned earlier, the Russian-built vertical boring mills include a Kolonna machine with a table of 13 ft. diameter, and a cross-beam which can be raised to a height of 10 ft. to facilitate loading. This machine has two power-driven spindles for machining holes, and trepanning-type cutters are used for this work, the core material being used for the production of certain small turbine parts. A Novosibirsk machine of similar type has a 23-ft. diameter table and can be employed for operations on workpieces with a maximum height of 16 ft. This machine was used at one time for turning the mounting flanges of water turbine propeller blades, but this work is now performed on one of the special machines which will be described.


SPECIAL MACHINE TOOLS

Specially-designed equipment for the production of water turbine components includes the large horizontal turning and facing machine seen in Fig. 5. This machine is employed for turning operations on the mounting flanges of propeller blades, and was designed and built by the Sverdlov Machine Tool Plant, which was described in an earlier article* in this series. The machine is of massive proportions and the headstock, seen at the right in Fig. 5, is mounted on a flat bed plate. T-slots are provided in the bed plate for securing three self-contained clamping units which hold the workpiece, and one of these units is indicated at *M*. For the machining operations, the propeller blade is held stationary, and the complete headstock unit can be traversed along guideways on the bed plate by means of a short, motor-driven, coarse-pitch screw, at one end, which engages a stationary rack, of arcuate cross-section, mounted between the ways.

The machine is driven by a motor of 100 h.p., and the headstock spindle is fitted with a facing

* MACHINERY, 93/288-6/8/58.

Fig. 5. This special horizontal turning and facing machine has been built by the Sverdlov works, Leningrad, to facilitate the production of propeller blades for large water turbines. The work is held by three clamp units and the tool is rotated in a special facing head



head, within the hinged wire-mesh guards *N*. The tool-carrying slide of this head can be traversed radially, under power, to permit of machining surfaces up to approximately 9 ft. diameter. The spindle can be driven at speeds up to 30 r.p.m., whereas when the workpiece was machined on a conventional vertical turning and boring mill, the maximum speed that could be employed was 10 r.p.m.

Switches and push-buttons incorporated in a control panel on the headstock provide for the application and release of the clamping units, and for the control of the traversing motions of the tool-carrying slide and headstock. The distances travelled by these two units are shown on large indicators, mounted above and below the control panel. Each indicator has a central dial for fine measurement which is surrounded by an annular calibrated ring for coarse measurement, the two members being coupled together by epicyclic gearing. There is a fixed cursor in front of both members, and the calibrations of the ring are seen through a rectangular aperture in the cursor, the calibrations of the dial being read with reference to an index mark on the lower part of the surrounding frame. The size of the dials and rings allows widely-spaced calibrations to be used, which enable readings to be taken from a considerable distance away.

Each of the clamping units *M* is mounted on the rectangular-section guideways of a sub-base, and can be traversed along these guideways by means of a coarse-pitch worm and rack. The rack is located between the guideways, and the worm is driven through reduction gearing by a flange-mounted electric motor, as indicated at *P*. Each clamping unit has a heavy column, set at an



Fig. 6. Close-up view of one of the clamp units on the Sverdlov machine, with a propeller blade in position. Each unit has two electro-mechanically operated clamping rams and a stop member which can be adjusted horizontally

angle of about 10 deg. to the vertical, and the column casting is roughly C-shaped. A yoke of heavy-section steel bar is fitted to the upper part of each column so that it may be lifted by means of an overhead gantry crane, and repositioned on the bed plate of the machine to suit different workpieces.

A close-up view of one of the columns is given in Fig. 6, and it may be seen that it has an adjustable ram *R*, which serves as a stop for locating the propeller blade in the horizontal direction. The upper and lower arms of the C-form house the clamping rams, protected by bellows-type covers as at *S*. These rams are advanced and retracted by electro-mechanical drive systems, and the motor for the lower ram is indicated at *T*. When the rams have been advanced into contact with the propeller blade *U*, they can be locked in position by hydraulically-powered mechanisms, and the cylinder for the upper ram is seen at *V*. Interlocking arrangements are incorporated to prevent operation of the machine unless the rams of each unit are in engagement with the work and are locked in position. The hinged guards at each side of the

turning and facing head, as indicated at *N*, Fig. 5, are connected to sliding plungers which actuate limit switches, as at *W*. If these guards are not closed the machine cannot be started.

SPECIAL PLANO-MILLING MACHINE

After the mounting flange of each blade has been machined it is transferred to a large plano-milling machine, seen in Fig. 7, which has been specially developed for semi-finishing both sides of propeller blades simultaneously, and is equipped with an electro-mechanical copying system. Built by the Gorki Machine Tool Works, it has a table approximately 28 ft. long by 8 ft. wide, and the distance from the table to the underside of the cross-beam is 19 ft. 6 in. A power-operated carriage moves on twin flat guideways on each upright, and can be secured by electrically-operated clamps. Guideways in each carriage support a horizontally-disposed ram, and these rams can be moved towards and away from each other by power. At the end of the ram there is a support bracket which can be swung through 360 deg. about the axis of the ram, and





Fig. 7. The special duplex copy-milling machine built by the Gorki Machine Tool Works for semi-finishing the surfaces of propeller blades. Separate masters are provided for each head, and trip dogs on a drum at one side control the table traverses and the elevating motions of the ram carriages

Fig. 8. Close-up view of the master and trip drum at one side of the Gorki profile-milling machine. The master is made one-fifth full size and an electrical follower unit is employed



the bracket carries a cutter head that can be pivoted through the 360 deg. on an axis at 90 deg. to that of the ram. The cutter spindle in this head is driven from a motor housed in the ram. Each assembly—comprising a carriage, ram and universal cutter head—is counter-balanced by twin chains and weights within the upright, and can be controlled independently from a pedestal at one side of the machine, also from a platform on the carriage.

Automatic control of the two ram units is provided by means of master and follower units at either side of the bed, and the unit at the left-hand side (as viewed in Fig. 7) also serves to control the movements of the table and the two carriages on the uprights. The water turbine blade is mounted on the table of the machine with the massive flange held in six self-contained hydraulic clamp units, which are secured to the table with T-bolts. Under automatic control, the table is traversed between the cutter heads, which mill both sides of the blade simultaneously, in a series of horizontal shallow grooves, in accordance with the forms of the masters. At the end of each traverse, the cutter head carriages are raised on the uprights by a predetermined amount, and the table motion is reversed, so that the next cut is made during the return movement of the table.

Fig. 8 is a close-up view of the left-hand master and follower unit, and the right-hand unit is of similar design, except where mentioned to the contrary. Each unit has a bed member *A*, with guideways for a table *B*, which can be power traversed in phase with the work-table of the machine, but at one-fifth of the work-table speed. The sub-base *C* of the master carrier is bolted to the table *B* and has a top member *D* which can be adjusted longitudinally. Pivotaly mounted on the top

member *D* is a support *E* to which the master *F* is secured. The master is made to one-fifth scale, and corresponds to one side of the propeller blade. By means of the adjustments, the master can be readily set in the correct position lengthwise and angularly to correspond to the setting of the work-piece after the latter has been clamped on the machine table.

At one side of the bed *A* there is a column *G*, with vertical guideways whereon slides a carriage which has dovetail ways for a horizontal arm. The end of this arm is indicated at *H* in Fig. 7. An electrical follower unit is adjustably mounted on the end of the arm by an arrangement similar to that employed for the cutter head of the machine, and the follower itself takes the form of a disc of 60 mm. (2.363 in.) diameter, to correspond to the cutters, which are of 300 mm. (11.811 in.) diameter. The follower-carrying arm can be adjusted transversely, and its carriage is raised and lowered under power, to correspond to the vertical setting of the left-hand machine ram, to a scale of one-fifth.

On the left-hand master and follower unit only, the column *G* also supports a drum *J*, and a lever-actuated switch *K* is mounted on a bracket that projects from the vertically-moving carriage of the column. A series of annular T-slots is machined in the drum, and the pitch of the slots is arranged to correspond, at one-fifth scale, to twice the vertical spacing of the milling cuts that are to be made on the propeller blade. Trip dogs are secured




Fig. 9. Details of the tungsten carbide tipped, inserted tooth milling cutters employed for profile-milling propeller blades on the Gorki machine

to the drum by means of the T-slots, and angularly-disposed projections on the dogs lift or depress the lever of the switch K. The drum is oscillated in phase with the motion of the machine table, and the circumference of the drum is such that the distance (round the drum) between two dogs that are abutting corresponds to the maximum travel of the table.

With the workpiece and masters in the correct relative positions, and the trip dogs spaced correctly round the drum, the arrangements are such that, when the machine cycle is initiated, the machine table and the two follower tables move together. The workpiece is then traversed past the cutters, which produce a shallow arcuate cut on each side of the propeller blade, in accordance with the forms of the masters. At the end of the first cutting pass, the switch K is re-set by one of the trip dogs in the lowermost slot in the drum. In consequence, the motion of the work-table is stopped, the carriage on each upright of the machine is unclamped, both carriages are moved upwards by a predetermined amount, and the carriages are then re-clamped. At the same time, the follower carriage at each side of the machine is raised through a corresponding distance (to one-fifth scale). At the end of these re-setting motions, the machine table, workpiece and master are moved in a direction opposite to that of the first cutting traverse, and a second pair of cuts is made under control of the two masters. The length of this cutting movement is again governed by a trip dog on the drum, which resets the switch K, so that the cutters and followers are re-positioned before the workpiece and masters are moved in the same direction as for the initial traverse. This sequence of forward and reverse cutting traverses, with automatic resetting of the cutters and


followers is repeated until both sides of the complete blade have been machined by a series of profile milling cuts. The switch K and its support bracket are moved upwards with the follower support arm of the left-hand unit, but the trip dogs are of an angular design, which ensures that the switch is actuated by both dogs in each drum groove, in spite of the small amount of upward displacement.

The cutters employed on the Gorki machine are of the inserted blade type, with mechanical clamping, and a typical cutter is seen in Fig. 9. Tungsten carbide tipped blades are used, and each blade can be adjusted individually by means of a dog-point screw in a ring which is screwed on to the cutter body. Each blade is held in position by a screw-actuated wedge. The cutting speeds employed range from 250 to 300 ft. per min., and the table feeds from 4 to 7 in. per min. Depth of cut ranges from 0.6 to 1 in., and the average life of the cutters between regrinds is stated to be 4 to 6 hours. Previously, using manually operated conventional machines, the milling of the surface of a propeller blade occupied 2,000 hours, but with the new machine only 100 hours are required, and a superior finish is obtained.

BLADE GRINDING MACHINE

Following the profile-milling operation, the blade is transferred to a special automatic grinding machine. Fig. 10, developed by the Kharkov Machine Tool Works. On this machine, each side of the blade is finished separately. The machine has a massive vertical column, of circular section, whereon swings an arm, fabricated by welding from steel sections. This arm incorporates guide-ways along which a carriage can be power-traversed. Two hydraulic rams are vertically mounted in the carriage, and to their lower ends is secured a self-contained, motorized grinding head, with a horizontal spindle carrying a large-

Fig. 10. General view of the special grinding machine built by the Kharkov Machine Tool Works for finishing the surfaces of water turbine propeller blades



diameter, cylindrical abrasive wheel. The propeller blade is mounted below the arm of the machine on adjustable supports which embrace the flange, and with the opposite end resting on adjustable jacks, so that the blade is in a nominally horizontal position.

In certain respects, the grinder resembles the special Robertson machine for finishing plough bodies which was described in *MACHINERY*, 89/1335—14/12/56, notably in that the workpiece itself acts as a master. The arrangement of the Kharkov machine is such that the arm is swung about the column, from side to side, so that it sweeps over the propeller blade, and the carriage is traversed along the arm in increments. A constant downward thrust is applied to the grinding head below the arm by the rams of the travelling carriage, so that a predetermined pressure is maintained between the grinding wheel and the surface of the workpiece, and the wheel follows the milled profile. The grinding head is moved over the work in a series of arcuate traverses, until the shallow ridges formed during the mill-

ing operation have been removed, and the milling cuts have been blended to form a smooth surface. The finishing operation on each side of the blade, including setting, occupies one shift of eight hours.

DOUBLE-END TURNING MACHINE FOR GUIDE VANES

The guide vanes for water turbines have integral shafts at each end, and a special double-




Fig. 11. The special double-ended Sverdlov horizontal machine for turning the shafts of guide vanes for water turbines at the Metallic Plant, Leningrad

end horizontal machine has been built by the Sverdlov plant for machining these shafts. This machine is shown in Fig. 11, and it may be observed that it is somewhat similar to other special-purpose machines described in the earlier article on the Sverdlov plant. The headstock units, moreover, resemble that of the machine for turning propeller blade flanges. A long bed, sunk below floor level, has inverted-V and flat guideways whereon are mounted two saddles, one of which is indicated at *M*. Each saddle is adjustable along the bed and can be secured by means of keeper strips, which engage the underside of the guideways. A cross-slide on each saddle can be adjusted transversely and locked in position. The guide vanes are of aerofoil section and on each cross-slide there is a massive cast support with a shallow V-form in its inner vertical face, with which the leading edge of the vane is engaged. The support on the saddle *M* is adjustable to facilitate alignment of the vane. At the end of each cross-slide remote from the support for the leading edge of the vane, there is a bearing surface for the under-side of the blade at the trailing edge. The vane is thrust on to this surface by a roller, carried at the end of a clamping arm, as indicated at *N*. This arm is of massive construction, and is swung downwards, or upwards clear of the work, by a motor-driven screw. The headstock unit at each end of the bed is driven by a 70-h.p. motor. A separate feed motor, as at *P*, is provided for traversing the headstock on the bed ways, drive being transmitted through reduction gearing to a coarse-pitch worm, which

engages the arcuate-section rack *R*, between the ways. The travel of the headstock on the bed is registered on a dial indicator *S*, of the type that has already been described. A second dial indicator *T* is provided to register the movement of the tool-carrying slide of the large-diameter turning and facing head mounted at the front of the headstock spindle. Each headstock can be controlled from a push-button station, as at *U*, and a portable push-button unit is provided which is mounted on the end of a long cable for convenience when setting up the machine. Both headstocks can also be controlled from the pedestal seen at the left.

The spindle speeds of the headstocks range from 5 to 125 r.p.m., and the feed rates for the headstocks longitudinally, and the turning and facing slides transversely, from 0.0019 to 0.393 in. per rev., both the speeds and feed rates being steplessly variable. Before this machine was installed, the shafts of the guide vanes were machined on a conventional lathe. By using the Sverdlov machine, it is stated, the time for machining the shafts has been reduced by 70 per cent, and the finish of the machined surfaces has been greatly improved. The machine will accommodate workpieces with overall lengths from 13 to 23 ft., and with shafts of 9% to 15% in. diameter, the maximum length that can be turned being 5 ft.. Fig. 12 is a close-up view of one end of the machine during an actual turning operation, and in this instance the spindle speed employed was 125 r.p.m. and the feed rate 0.039 in. per rev.

Other special equipment installed in the water turbine shop includes a horizontal machine of similar design to that shown in Fig. 5, with a revolving cutter spindle that is radially adjustable in the facing head. This machine is employed for drilling and boring the fixing holes in the flanges of propeller blades, the holes being arranged on a pitch circle, concentric





Fig. 12. Close-up view of one end of the Sverdlov machine during turning operations on the shaft of a large water turbine guide vane

Fig. 13. The casing for a large water turbine which is built up from four steel castings. All the other major structural components are fabricated by welding



with the flange. Another machine provides for grinding the surfaces of the guide vanes. The wheel head is traversed along the cross-beam of a portal-type frame, which spans the reciprocating work-table whereon the blade is mounted. A very large horizontal turning and facing machine has been developed by the Sverdlov works, but was not installed at the time of our visit. This machine has a headstock that is similar to those already described, which can be traversed on inverted-V and flat guideways of a bed-plate. The spindle of the machine has a central boring quill, which can be advanced and retracted under power, and a large diameter facing head. At the facing-head end of the bedplate there is large circular, power-driven work-table sunk in the floor. There are hydraulic clamping units and jacks on the table for holding and supporting large workpieces, such as turbine hubs, while radial holes and tangential faces are machined. All movements of the head and table are controlled from a floor-mounted desk at one side. The headstock is driven by a 75-h.p. motor, and work up to 16 ft. diameter can be accommodated.

At the time of our visit, one of the 20 new turbines for Stalingrad was under construction. This unit has a rotor of 30 ft. 6 in. diameter, and a stator of 52 ft. 6 in. diameter. Electric arc welding is being widely employed for this machine, and the only major structural component that is not weld fabricated is the body, which is similar to that seen in Fig. 13. This unit is built from four steel castings and weighs 85 tons.

THE ELECTROSILA PLANT

As has already been intimated, the electrical equipment for the steam and water turbines built by the Metallic organization is supplied by the Electrosila Electrical Plant. This plant is situated on the western outskirts of Leningrad, and was

established, 65 years ago, as an assembly shop for small machines made by Siemens Schuckert. Before the first world war, the employees numbered about 1,000, of whom about 900 worked in the shops, but the works were closed down during the war. Reconstruction of the plant began in 1922, and, following the introduction of State Programme for the Electrification of the U.S.S.R., the production of electrical generators of 500 to 1,500 kW. output was started in 1924.

In 1926, the building of generators for use with water turbines was initiated, and a machine, of 7,500 kW. output, was built for the first hydroelectric power station to be constructed in the U.S.S.R. Since that time, the plant has continued to build generators for both steam and water turbines, and during the period from 1932 to 1939, generators for steam turbines were developed and built which had outputs of 25, 50 and 100 MW. It may be of interest to note that the output of the largest machine was greater than the combined capacity of all the machines produced in a year, before the revolution.

The construction of electrical machinery was stopped during the second world war, and the plant was engaged in the production of munitions. At one time, the front line was only three miles from the works, and the plant suffered extensive damage from shelling and bombs, but continued to function. When the siege of Leningrad was raised, at the end of 1944, the reclamation of the plant was begun and, under government direction, plans were made to restore it to its pre-war condition over a number of years. The plant is now claimed to be not only




Fig. 14. Machining the rotor for a large synchronous motor on a Kolomna duplex milling machine at the Electrosila works, Leningrad. The workpiece remains stationary and the two milling units can be traversed in two directions on the bedways

the largest in the Soviet Union, but also in Europe, and builds generators and other equipment. Most of the generators are for Soviet power stations, and the capacity range is the same as before the war. It is planned, however, to build generators for steam plants with outputs up to 400 MW., and hydro-electric generators of 800 MW. capacity.

Many new shops have been built since the war, and about 10,000 people are now employed at the plant, some 7,000 workers being engaged in the production departments. Large A.C. and D.C. motors are built in addition to generators, and we were informed that the combined energy of all the machines made in a year is 2,000 MW. Before the second world war, many of the engineers employed in the plant studied in Great Britain, notably at Metropolitan-Vickers and C. A. Parsons, and there are still a few of these engineers in senior positions in the plant, including that of director.

There are two very large shops, one for building generators for steam turbines and the other for generators for water turbines. Before the war, most of the equipment was of foreign origin, but apart from German machines which were sent to the plant under the reparations scheme, only Russian-built machines have been installed since the war. The main erection bay of the steam-turbine generator shop has two overhead gantry cranes with 120-, 110- and 90-ton hoists, and there are two smaller gantry cranes of 10 tons capacity. In addition, travelling jib cranes are installed along


each wall. There are similar lifting facilities in the adjoining heavy machining bay. Most of the plant in this bay appeared to be fairly old, but had been maintained in good condition. In Fig. 14 is shown a large duplex milling machine built by the Kolomna Machine Tool Works. The machine has an independent vertical milling unit at each side of the bed, and the column of each unit can be traversed crosswise on guideways in a sub-base, which, in turn, can be moved longitudinally on the twin rectangular guideways of the associated base. In the illustration, the machine is seen set up for milling flat faces along the sides of a rotor for a large synchronous motor. The rotor is of 4 ft. diameter, and 18-in. facing cutters are used, which have inserted blades with carbide tips. A face-milling head is secured to each column and is driven from the vertical milling spindle.

A number of large generators was under construction in the erection bay, and some had reached the final-test stage. These units included a 30 MW generator with an experimental water-cooled stator which will eventually be installed in Leningrad. Hollow stator bars are employed and each has an inlet and outlet pipe, of a special grade of rubber, for the cooling water. A new range of water-cooled generators for steam turbines is being developed in which the bars are grouped for cooling purposes, the water supply arrangements being thus simplified. The general trend of development at the Electrosila plant is towards generators with water-cooled stators and forced hydrogen cooling for the rotors. A small experimental machine has been designed, however, in which both the stator and rotor are water cooled.

Fig. 15. Spot-welding the windings to complete the circuit in the stator for a generator to be used in conjunction with a large steam turbine

Among the machines under construction was a generator of 60 MW. output, and in Fig. 15 spot welding operations are seen in progress on the stator windings of this machine to complete the electrical circuit.

At one end of the erection bay there are pits for the balancing and overspeed testing of rotors, and a view of one of these pits is given in Fig. 16. Balancing is carried out with the rotor supported by its own journals, and portable electronic equipment is used. The maximum distance between the support bearings is 26 ft., and rotors of 3 ft. 4 in. maximum diameter can be tested. Rotors can be driven at speeds up to 3,600 r.p.m. by a motor of 4,700 h.p., and it is the usual practice for generators to be designed so that the normal operating speed lies between the first and second critical speeds. The rotor seen in Fig. 16 is of the hydrogen cooled type, and has internal passages for



the flow of hydrogen, these passages being connected to scoops on the periphery of the rotor. The scoops are arranged in groups, those in one group facing in one direction, and those in the next group, in the opposite direction. As the rotor is rotated, hydrogen is picked up by the scoops that face in the direction of rotation, is forced through the internal passages, and is discharged from the scoops in the next group.

The hydro-generator shop has separate machining and welding bays, and in the latter bay, at the time of our visit, there was a large stator for a generator to be installed at Stalingrad. Welding is being increasingly employed for the stator frames and other structural members of large hydro-generators, and this example was of approximately 50 ft. diameter. Special care is necessary to avoid distortion, and considerable attention is given to the method of supporting the work and the sequence of the welding operations. It is claimed that close limits can be maintained, and that, in this instance, important dimensions were held to a tolerance of ± 0.5 mm. (0.020 in.). Using the submerged arc process, steel plates up to 200 mm.




Fig. 16. One of the overspeed test pits in the steam turbine generator shop at the Electrosila Works, Leningrad. A hydrogen cooled rotor is seen being prepared for testing and balancing with portable electronic equipment

(7½ in.) thick have been welded satisfactorily, and it is intended to employ welding for the construction of rotors for large hydro-generators.

Various heavy machine tools are installed in the machining bay of the hydro-electric generator shop, including a large vertical turning and boring mill built by the Starakramatorski Machine Tool Plant. It has capacity for machining workpieces up to 32 ft. diameter by 13 ft. high, with weights up to 200 tons. A Ward-Leonard system is employed for the main drive, the motor-generator set being of 225 h.p. There are two angularly adjustable

tool rams, and all motions are controlled from a pedestal at one side, as well as from separate stations on the cross-rail. This machine was installed in 1952, and we were informed that boring mills of similar design have since been built with a capacity for machining workpieces of 60 ft. diameter. At the time of our visit, the turning and boring mill was being employed to machine the bore, end-face and certain seating faces on the housing for a 7,500-h.p. D.C. motor. The housing was 14 ft. diameter by 6 ft. high, and the machining operations required 200 hours.


Ball Bearings Made from Plastics

The ball bearing shown in the accompanying illustration is made entirely from plastics with the exception of the aluminium screws. Designated No. 85, this bearing is one of several types made by Aircraft Armaments, Inc., Cockeysville, Maryland, U.S.A., and is employed in the mounting for a 0-30-in. calibre machine gun on a tank landing craft. Designed to replace a steel bearing, the plastics assembly has a diameter of approximately 10 in. and incorporates two rows of balls. The load-carrying balls are of 0-406 in. diameter and are separated by idler balls of 0-394 in. diameter, which act as spacers. Excess loads, which have the effect of compressing the larger balls slightly, are carried partly by the idler balls. The balls

employed in this bearing were centreless ground from cast phenolic resin rod material, but for other heavier-duty applications moulded phenolic or melamine resins could be employed.

Bearing races are machined from linen-reinforced phenolic tubing and although aluminium screws were employed in this example, it is stated that they too could be made from plastics material if it was essential that metallic materials should be avoided. Before the bearings were accepted for installation they were subjected to tests which included the equivalent of firing more than one million rounds of ammunition from a machine gun, and application of acceleration loads to simulate actual conditions of service. Such tests exceeded

requirements for the normal life of the turret in question, and after they had been completed, the bearings were found to be in excellent condition with no signs of wear or "Brinelling" indentations. The weight of the plastics bearing is only 20 per cent, and the cost about 33 per cent of that of a steel equivalent, despite the fact that it is being made in limited quantities.



This plastics bearing for a machine gun mounting has races of approximately 10 in. diameter

Electronically-controlled Press Feed for Transformer Lamination Strip

In MACHINERY, 92/888—18/4/58 an article was published on the flow-line methods employed by Ferranti, Ltd., at their West Gorton works, Manchester, for the manufacture of distribution transformers up to 1,500 kVA., 33 kV. rating. The range includes small single-phase types, extensively employed in rural electrification, which incorporate what are termed lock-wound cores, to enable more effective material utilization to be obtained.

These lock-wound cores are built up of laminations of cold-reduced, grain-oriented electrical steel ranging from 60 to 70 in. long and $1\frac{1}{2}$ to 4 wide, and each has a slot at one end and a tongue at the other, as shown in Fig. 1. The slot in one strip is engaged by the tongue in another as the core is being wound.

The laminations are produced from 0.014-in. thick, gang-slit, coiled material, on a Hordern, Mason & Edwards L40 geared, adjustable-stroke, press of 40 tons capacity, to which the company




Fig. 1. Lock-wound laminations are connected together by means of an interlocking tongue and slot, as here shown

have fitted a motorized coil cradle and a fully-automatic feed unit, whereby laminations of any length required can be cut to an accuracy of $\frac{1}{4}$ in. A description of the follow-on press tool employed was included in the previous article, and some details can now be given of the arrangement of the coil cradle and feed unit, which was developed and built by the B.H.P. Machine Tool Co., Ltd., in co-operation with Ferranti, Ltd. The unit can also be used for the manufacture of laminations for conventional cores.

A general view of the installation is given in Fig. 2, and Fig. 3 shows




Fig. 2. H.M.E. power press with automatic feed arrangement for producing laminations for lock-wound cores




Fig. 3. Close-up view of the tool and the outlet side of the feed unit adjacent to H.M.E. 40-ton power press

the press tool, with the feed unit on the left. The required length of feed is pre-set on a Londex electronic controller, seen at A in Fig. 2. The coil cradle has a variable-speed drive which is adjusted to a speed depending upon the length of lamination being produced and is arranged to operate by means of a relay while the feed mechanism is feeding strip to the press. The strip is taken from the coil between adjustable side guide plates B, and over two guide rollers, to a pair of power-driven feed rolls in the unit C. Referring to Fig. 3, at the outlet side of the feed rolls, the strip passes beneath a roller D, mounted on a pivoted arm which is lifted should the strip buckle because of incorrect feeding, and a safety switch at E is then operated to stop the feed-roll driving motor.

Drive from the motor of the feed unit is transmitted through a Warner electro-magnetic clutch (Westool, Ltd.) to a reduction gearbox which provides a strip feed rate of 40 ft. per min. To ensure an accurate cut-off length, a secondary gearbox is also incorporated, which is brought into operation, by another electro-magnetic clutch, to reduce the rate of feed towards the end of the movement, and finally a brake is applied.

The required strip length, in units of $\frac{1}{4}$ in., is pre-set by means of four knobs on a panel, which represent units, and units $\times 10$, $\times 100$ and $\times 1,000$. Control of the feed-roll drive is then effected through the medium of four dekatron counters, operating in conjunction with a photo-electric cell and a large-diameter slotted disc, which is driven at increased speed by spur gears from the lower feed roll shaft. As the disc rotates, each

a Maxam air cylinder controlled by a solenoid valve. This pneumatic control has been applied to the existing clutch pedal, as seen at F in Fig. 2. During the press stroke, a cam on the left-hand side of the crankshaft operates a switch to re-set the Londex control unit, and initiate the next feed cycle. The laminations are picked up after cutting by a small conveyor and carried to a pallet.

TACCY DUST BARRIER—The method of arresting or collecting dust by means of adhesive impregnated dusters and mats which was developed by Anti-Dust Services, Ltd., Dudley, Worcs. (formerly known as A.D. Tack Rags and Adhesive Dusters, Ltd.), has now been applied to screens, which can be employed for enclosing machines or processes that produce dust, or from which dust must be excluded. An open weave material has been developed which is impregnated with a non-drying adhesive, and can be attached to light-section steel angle frames to form screens. These screens can be arranged to provide complete enclosures, with four walls and a ceiling, half-tunnels, corner enclosures, and T-shaped erections.

A wide range of standard steel angle strips is available, with an aluminium finish, whereby enclosures of any length, width and height, in multiples of 30 in. can be constructed. The screens can be provided with castors to facilitate movement from one site to another. It is stated that, when new, the adhesive-impregnated material does not impede light or natural ventilation to any appreciable extent.

Operations on Ford Rear Axle Differential Spiders

Spiders, which carry the intermediate gears in the differential assemblies employed in Ford commercial vehicles, are made in a range of sizes to suit the different vehicles and are machined from special steel forgings of cruciform shape with pierced central bosses. A drawing showing a typical finish-machined spider for a large vehicle is given in Fig. 1. Before they are machined, the forgings are subjected to a heat treatment cycle which includes heating to 1,550 deg. F. and quenching in oil, followed by tempering at 1,000 deg. F. to obtain a Brinell hardness of 241 to 286. Pickling is then carried out to remove scale and the central boss of the forging is coined to a thickness of 0.865/0.875 in. on a Craig & Donald (Scottish Machine Tool Corporation, Ltd.) 500-ton press. A B.S.A., 6- by 20-in. automatic lathe is then employed to turn the outside ends




Fig. 1. The differential spider which carries the intermediate gears in the rear axles of large Ford commercial vehicles is machined from an alloy steel forging

of the four arms to the nominal diameter of 7.000/7.010 in., after which the bore of the central boss is enlarged to 1.697/1.700 in., on a Pollard 21-in. drilling machine, for location purposes.

At the next operation on the spider, the four arms are turned to a common diameter of 1.025/1.030 in. for a length of 2.09 in. and the outer ends are drilled and chamfered, and this work is performed on a special Witzig & Frank (B.P.S. Machinery & Spares Co., Ltd.) double-ended hollow turning machine, a general view of which is given in Fig. 2. From this illustration it will be observed that the machine has a long bed with a spindle




Fig. 2. General view of the Witzig & Frank automatic machine for hollow turning, chamfering and centre-drilling the four arms of the differential spider




Fig. 3. Close-up view of the work-holding arrangements and tooling on the Witzig & Frank machine. Following the initial turning operations on the horizontal arms, the component is indexed through 90 deg. to bring the other arms into position

head at each end, arranged to slide on the bedways. An extension at the rear of the machine carries the work-holding spindle, on which the spider is positioned by its bore, angular location being provided by spring-loaded V-blocks arranged to engage the two vertical arms of the forging.

Some further details of the work-holder and of the tooling on the spindle noses may be seen in the close-up view, Fig. 3, the component being

clamped on the spindle by means of a loose C-washer and draw-bar. The spindle is indexed through 90 deg., by an automatic mechanism within the housing at the rear, after the completion of the turning, chamfering and centre-drilling operations on the two horizontal arms, to enable the other two arms to be machined. Each machining head is equipped with two turning tools which share the total cutting load, also a single chamfering tool and a centre drill, and is driven at a speed of 1,120 r.p.m., to provide a cutting speed of 330 ft. per min.

Loading and clamping of the spider is accomplished with the aid of the push-buttons on the panel at the right in Fig. 2, and the automatic cycle cannot be started until two micro-switches A, Fig. 3, have been operated by the action of closing the guard, which completely encloses the cutting area and confines flying chips. The two spindle heads




Fig. 4. An area near the boss end of each arm is induction hardened to a depth of 0.060/0.080 in. on this general purpose unit which is supplied by a generator of 60 kW capacity

are advanced at a rapid traverse rate, by electric motors, to the cutting position, and the feed rate, which is steplessly variable, is then engaged at 0.0045 in. per rev. for the cutting operation. During the machining cycle, the heads are fed by means of hydraulic motors, and after the heads have reached full depth they dwell momentarily to permit escape of chips from the spaces between the tools and the work. The rapid-traverse drive is then engaged to retract the tools to the position shown, and the central shaft carrying the spider is indexed to bring the vertical arms to a horizontal position.

When the machining cycle has been repeated, the heads are again retracted and the spindles are stopped in readiness for unloading. Soluble oil coolant is employed, and the cycle time for turning the four arms is 1.10 min. Rough grinding of the arms to a common diameter of 1.003/1.007 in. is next carried out on a plain cylindrical machine, which operates on one arm at a time, and the components are then inspected. Subsequently, the arm surfaces are induction hardened for a distance of 1 in., near the central boss, to a depth of 0.060/0.080 in., on a general-purpose unit sup-

plied by the English Electric Co., Ltd., as shown in Fig. 4.

This unit consists of a series of cabinets, with sliding transparent panels at the front, in which provision is made for mounting some 18 different designs of inductor, for the treatment of various axle components produced in the shop. These inductors are supplied with high frequency current by a generator of 60-kW. output, which can be connected to any of the cabinets, as required. With the set-up shown in Fig. 4, the spider is located in the inductor coil which is fitted with a spray type quench ring, and the current is switched on for a controlled period of 5 sec., followed by the water spray for 9 sec. This procedure is repeated for each of the spider arms, and the surfaces are thus hardened to 60 to 65 Rockwell C.

Finish-grinding of the arms to a diameter of 0.997/0.998 in., with a surface finish of 27 micro-in. C.L.A. is then carried out on a 12- by 24-in. Newall machine, after which the flats shown in Fig. 1 are formed by surface grinding on a Lumsden machine. Finally, the spiders are deburred, de-magnetized, inspected and passed to the assembly lines.

G.E.C. Reversing Starters


A range of direct-to-line reversing starters, incorporating vertical-lift contactors similar to those in their XB and XC non-reversing types, has been introduced by the General Electric Co., Ltd., Magnet House, Kingsway, London, W.C.2, for starting motors of 1 to 12½ h.p.

An example from the new range is shown in the accompanying illustration. The 4-pole forward and reverse contactors are interlocked mechanically so that when either is closed, the other is locked open, and there is a further electrical interlock through side switches operating in conjunction with each contactor, which prevents the two operating coils from being energized together. Additional side switches for controlling associated circuits can be fitted, if required. The triple-pole overload units have adjustable oil dash-pot time lags.

Any starter can be supplied with a cam-operated, double-break, triple-pole, interrupter switch, capable of breaking the stalled motor current. The 10-h.p. and 12½-h.p. sizes have a plug-in mount-

ing which permits removal without disturbing incoming and outgoing cables.

Push buttons for "forward," "reverse" and "stop/reset" control are mounted on the case, and motors may be controlled remotely, if desired, by push buttons or pilot switches. An ammeter can be fitted on top of the case, and accommodation for control fuses is available inside the starter.



G.E.C. Reversing Starter Showing the 4-pole Vertical-lift Contactors

Optical Location System for a Turret Punch Press

An optical locator has been combined with a conventional stylus system to extend the field of application of an 80-ton turret punch press. Built by the Wiedemann Machine Co., U.S.A., the RA-101 press is shown in Fig. 1, and it is stated that the equipment permits savings in the preparation time for punching panels measuring up to 48 by 60 in. at a single setting, or 48 by 120 in. at two settings.

These savings are obtained because detailed shop drawings are not required. Only the outside dimensions of the blank need be given. With a rough sketch as a guide, a sub-template for each opening is taped or pasted on to a sheet of transparent vellum. This non-dimensioned master drawing is reproduced photographically on two sheets of sensitized paper, one opaque and one transparent. (Paper shrinkage or stretching is held to a minimum during this process.)




Fig. 1. Wiedemann turret punch press equipped for both optical and stylus hole location




Fig. 2. A hole location on the photo-copy of the master drawing is projected on the ground-glass screen of a 10× magnification optical viewing head

The transparent photo-copy is used for checking hole location on the finished part, and the opaque copy serves as a template and is held to a vacuum table on the punch press. With the work blank in position, the cross-slide is moved until the centre lines of a hole location on the template are aligned with the cross hairs on the ground-glass screen of a 10× magnification optical head, as seen in Fig. 2. After tripping the press, the operator locates the next hole in the same manner.

This photographic template method is intended only for small batches. If a number of identical parts is to be made, $\frac{3}{8}$ -in. diameter holes can be punched in the first piece at the various locations. This piece can then be used

as a template, in conjunction with the conventional Wiedemann stylus to increase speed of operation and ensure positive hole duplication.

Change-over from optical to stylus control, or vice versa, is simplified by the fact that both units are mounted on a movable locating head. This head can be unlocked and indexed to left or right

to bring either the optical system or the metal stylus into the operating position. Interlocks ensure correct operation of the machine when either unit is in the control position.

The Wiedemann Machine Co. are represented in this country by Dowding & Doll, Ltd., 346, Kensington High Street, London, W.14.

Installation for Hot-forging Stainless-steel Bolts

A hot-forging installation for the production of stainless-steel bolts has recently been put into operation by Sandiacre Screw Co., Sandiacre, near Nottingham. The stainless-steel billets are induction heated in the Wild-Barfield furnace seen in Fig. 1, which is capable of raising a $\frac{1}{2}$ -in. diameter billet to a temperature of 1,150 deg. C. in 8 sec. This type of furnace was installed because it provides for fast and localized heating. In addition, distortion is avoided, and scaling is reduced. Quantity-production, hardening, tempering, brazing, and soldering can also be undertaken with this equipment, which can readily be changed over from one type of work to another.

The forging temperature is controlled automatic-



Fig. 1. The Wild-Barfield induction heating furnace installed at the works of the Sandiacre Screw Co. for heating stainless-steel bolt billets prior to a hot-forging operation. A $\frac{1}{2}$ -in. diameter billet is heated to 1,150 deg. C. in 8 sec.




Fig. 2. After being heated, the stainless-steel billets are hot-forged in this Eumuco split-die press

ally, to ensure uniformity throughout a batch, and the desired grain formation in the heads of the bolts.

From the furnace, heated billets are transferred to an adjacent forging press, which can be seen at the extreme left in Fig. 1, also in Fig. 2. This German-made, Eumuco (Wickman, Ltd.), machine is of the split die type. Short bolts can be produced by cropping from the bar, and the flash left after the forging operation, which is on the top of the head, can be removed during the normal facing operation.


It is stated that the stainless-steel bolts produced by this plant have increased strength and accuracy, also improved appearance. Furthermore, it is claimed that, as a result of the improved grain formation, there is less likelihood of fatigue cracks

occurring at the junction of the head with the shank, than with bolts which are machined from solid bar material. In addition to the technical advantages mentioned above, there are important savings in material. By using the hot-forging technique, the weight of material saved, per gross, as compared with that required for bolts turned from bar, ranges, for example, from 17 lb. for a $\frac{3}{8}$ -in. diameter by 2-in. long size, to 196 lb. for a $\frac{3}{4}$ -in. diameter by 6-in. long bolt, these figures representing, in each case, an economy of the order of 50 per cent. It is estimated that the company will obtain an overall saving of some 70 tons of stainless steel per year.

Birlec Dual-frequency Billet Heating Installation

A 400-kW., dual-frequency, billet heating installation has recently been supplied by Birlec, Ltd., Tyburn Road, Birmingham 24, to Forgings & Presswork, Ltd., Birch Road, Birmingham 6, for operation in conjunction with a Massey high-speed forging press.

With this equipment, which is shown in the figure, pre-heating of billets, to a temperature of 700 deg. C., is carried out with current at mains frequency, and a high-frequency supply, at 3 kilocycles per sec., is provided by a B.T.-H. motor alternator for the final stage of the heating cycle.



Birlec dual-frequency billet heating equipment installed adjacent to a Massey forging press. Current at mains frequency is employed for pre-heating, and the billets then fall through a high-frequency coil

to bring the billets to the forging temperature. In consequence, a high-frequency generator of only fairly small capacity is required, and rapid heating of the billet ensures that the formation of scale is reduced to a minimum.


Apart from the loading of unheated billets on to an elevator, the equipment is automatic in operation, and is designed to deliver heated billets continuously at pre-determined intervals, to inclined chutes, down which they slide by gravity towards the forging press. It will handle from 7 to 20 cwt. of steel billets per hour. There are two horizontal heating units each fitted with mains- and high-frequency coils which are brought into use alternately by the action of air-operated, pusher-type, billet feeding mechanisms. Interchangeable coils are supplied for heating of billets of various sizes up to 4 by 4 in. cross-section by 7 in. long.

Thermally-insulated tunnels are provided between the pre-heating and high-frequency coils, which ensure that heat losses are reduced to a minimum when the billets are being transferred from one position to the other. A knock off arrangement is incorporated at the discharge end of the heating units, which prevents heated billets from adhering to one another. The elevator at the loading end will accommodate sufficient billets to ensure continuous operation of the forging press for a period of 10 min. Two micro-switches are fitted, the first of which operates an alarm

system when the loading of fresh billets on to the elevator becomes necessary to ensure continued working of the installation. Operation of the second switch causes the power supply to be interrupted. In consequence, the risk of overheating of billets in the coils is prevented, when the supply of fresh billets has been stopped.

An 850-kW. dual-frequency billet heating installation of similar design has also been supplied recently by the company to Beans Industries, Ltd., Tipton, Staffs.

Sales of Birlec induction heating equipment are handled by Birlec-Efco (Melting), Ltd., Aldridge, Staffs.



Machining Operations on Honeycomb Structures

By R. G. KELLNER*

Honeycomb sandwich structures may be regarded as engineering material fabricated in sheet form, with physical properties which are particularly desirable in aircraft construction. Ideally, this material would be made in a single manufacturing process to the desired total thickness, with high-strength integral skins and an internal cellular structure somewhat resembling that of foam plastics or rubber. Moreover, the outer skin and cellular centre structure would be so well controlled that optimum stiffness-to-weight ratio would always be obtained.

The attractive strength-to-weight ratio of honeycomb sandwich structures is due to the location of the relatively dense, high-strength material in the extreme fibres where in flexure the unit stress is greatest. The low-density, weak material is in the core where the unit stress is least. Any aircraft not being propelled as a projectile is essentially a flying flexural member, and sandwich structures are therefore of great importance in this field.

If this material is to be used effectively, its

composite physical properties must be recognized in order that structures may be confidently designed with the knowledge that they can be readily fabricated. The working of honeycomb structures presents many unusual problems because the thin (0.010 to 0.025 in. thick), tough skins are not well supported. Somewhat similar difficulties would be encountered, for example, if an attempt were made to drill a ½-in. diameter hole through a piece of 0.010-in. thick steel sheet, backed by a pad of sponge rubber; to machine 0.002-in. thick steel foil by ordinary shop techniques; or to clamp a piece of sponge rubber to a machine table without crushing it.

It is evident that support for the core must be provided if honeycomb material is to be machined, and that operations must be performed with little or no tool pressure. Any filler to be used as support material for the honeycomb core should be readily obtainable and inexpensive; be easily applied with little or no special equipment; be easily removed and suitable for re-use; and should provide adequate support during the machining operations.

Filler materials were used for mounting honey-

Aircraft Gas Turbine Division, General Electric Co., U.S.A.




Fig. 1. Nine special cutters which were designed for use on honeycomb cores. Only No. 5 and 6 proved successful

which are shown in Fig. 1.

Cutters No. 1 and 3 were designed to cut out the facing sheet in the manner of an end-mill. During the test, the core collapsed, since it could not resist the pressure necessary for proper functioning of these two cutting tools. Cutters No. 2 and 4 were intended to follow No. 1 and 3, respectively, to remove the core of the

comb cores during tests carried out by the General Electric Co. For this purpose, a 16-gauge, sheet-steel tray was employed, which measured approximately 1 in. larger on all sides than the part to be held, as seen in the heading illustration. The edges of the tray were about $\frac{1}{8}$ in. high and were bent inwards at an angle of 30 deg. Clamps were used to secure the tray, containing the mounting filler (in this case Cerrobend), and the work to an angle bracket on the machine table.

MACHINING WITH SPECIAL CUTTERS

During machining tests of honeycomb material, various special cutters were constructed, nine of

sandwich structure. Although the knife-like, peripheral cutting edge sliced through the core material as planned, the internal end-mill portions of the cutters failed to remove those parts of the facing sheet left by the first two cutters.

Only cutters No. 5 and 6 proved to be satisfactory. Cutter No. 5 was made from 18-4-1 high-speed steel hardened to 58-62 Rockwell C. It is a mushroom-shaped tool, of 6 in. diameter, with an included knife-edge angle of 5 deg. and a dish angle also of 5 deg. Cutter No. 6 is of the same material, of 3 in. diameter, with an included knife-edge angle of 5 deg. and a dish angle of 10 deg.

Both these cutters performed well at speeds of 2,400 and 3,200 surface ft. per min. and good tool life was obtained with feed rates as high as 30 in. per min. Slices as thin as 0.025 in. were consistently cut, leaving the trimmed surface straight and the edges of the cells clean and practically free from burrs, as can be seen in Fig. 2. The machine set-up for this slicing





Fig. 2. The fragility of honeycomb core is evident from this test sample. A slice has been removed from the top surface with the No. 5 cutter in Fig. 1. The cut edges are straight and almost free from burrs

Fig. 3. After filling these core cells with a mixture of iron powder and sodium silicate, cuts were taken with a staggered-tooth side mill. Some break-out of the filler is evident



operation is shown in the heading illustration. It was found that the three fly-type cutters designated No. 7, 8 and 9 in Fig. 1 could not be used satisfactorily for cutting recesses or shoulders because, except that the cut is intermittent, they function in the same general way as the slicing cutters, No. 5 and 6.

MILLING TESTS ON HONEYCOMB CORE MATERIAL

Apart from tests involving the slicing of core material, milling of honeycomb has received considerable attention.

The honeycomb must be made rigid to withstand the action of a milling cutter. To this end, several core sections were filled with different materials to determine the merits of each. One operation was performed with a side-milling cutter, $\frac{1}{4}$ in. wide by 6 in. diameter, with 36 staggered teeth. The core was filled with a mixture of iron powder and sodium silicate. Climb-milling cuts were taken at speeds up to 150 r.p.m. and at feed rates of $1\frac{1}{4}$ to $6\frac{1}{4}$ in. per min. Results of this test can be seen in Fig. 3. The edges are fairly clean, but it is evident that some break-out of the filler occurred.


Another core section of the same general con-

figuration was filled with a mixture of stainless-steel powder and sodium silicate. The same cutter was run at speeds of 130 to 500 r.p.m. with feed rates varying from $1\frac{1}{4}$ to 16 in. per min. and a $\frac{1}{8}$ -in. deep cut. All the cuts were satisfactory. As seen in Fig. 4, the edges of the honeycomb were clean, and there was no break-out of the filler.

Several other tests were carried out with different fillers. Among the less successful of these materials were certain epoxy resins. No combination of speeds and feeds proved satisfactory due to the brittleness of the fillers which invariably broke away from the core metal, and severe burrs were formed.

While using the same 6-in. diameter, side-milling cutter, Shell Chemical Corporation epoxy No. 1007 was tried. It was found that this material, which has a higher melting point than those previously tried, was suitable from the machining standpoint. A $\frac{1}{4}$ -in. diameter, 4-flute end-mill was used for another series of tests. The fillers employed were Shell epoxy No. 1001, 1004, and 1007; also Furane Plastics, Inc., Epocast H-583, and all were satisfactory. This method of producing slots in honey-

Fig. 4. For this honeycomb, the filler was stainless-steel powder and sodium silicate. Using the same cutter as for Fig. 3, at various speeds and feeds, noticeably improved milling cuts were obtained






Fig. 5. This clean hole was made through a honeycomb sandwich by electrolytically-assisted grinding. Angular holes in the top surface of the metal-bonded cup wheel directed the electrolytic coolant to the cutting edge

comb cores was successful with a feed rate of 6 in. per min. and a speed of 56 r.p.m.

PRODUCING HOLES IN HONEYCOMB SANDWICHES

So far, grinding is the only method that has proved satisfactory for producing an accurate hole in a honeycomb sandwich structure. There is not enough inherent support to permit of drilling with either conventional or modified tools without the use of a filler. Drills with a point angle of 60 deg. standard and modified centre drills and flat-point (166-deg. negative angle) drills have been tried without success.

For each grinding test, a flat sample of honeycomb sandwich was clamped to a faceplate, or held in a chuck, and rotated. A cup-type grinding wheel, of a grit suitable for the work material, was rotated at a speed of 16,000 r.p.m. and fed into the sandwich. The centre line of the wheel was eccentrically located with respect to the hole centre.

It is also possible to produce holes by electrical-discharge machining, but the time required—more than 15 min. for a 1-in. diameter hole in ½-in. thick material—was such that the method was not considered practical. In special tests conducted at the Anocut Engineering Co., however, holes were

successfully produced by the electrolytically-assisted grinding process. A wheel for this purpose and the hole obtained are shown in Fig. 5.

The test was carried out on a Delta drill press which had been modified to provide a speed of 2,000 surface ft. per min. for the 1½-in. diameter, metal-bonded cup wheel. Current was supplied to the spindle from an Anocut power unit by means of a slip ring and two motor car starter brushes. Plastics sheets placed beneath the work and the clamping bars effectively insulated them from the machine.

For this process, a special solution of non-corrosive electrolytic salts in water replaces the standard coolant. Material to be removed is stripped away by electrolytic action as current passes between the grinding wheel and the work. During the hole-grinding operation, the coolant stream was applied to the top of the cup wheel, in which angular holes had been drilled to direct the flow to the cutting edge.

Good quality holes were produced in time periods varying from 1½ to 2 min. Holes can be produced in cores with cell wall thicknesses of only 0.001 in. without forming burrs. Difficulty was at first experienced due to arcing at the top of the cup wheel, which was the same diameter as the cutting end. To eliminate this trouble, the diameter at the top was reduced.

Core material may be drilled by conventional methods if rigidity is imparted by the use of suitable fillers. Table 1 shows the results of tests made with a ½-in. diameter drill having a 118-deg. point angle and a 9-deg. lip-relief angle. A filler of Shell Epoxy 1001 was melted in an oven at a temperature of 300 deg. F. It was then removed from the oven and poured into the honeycomb, with the core resting on a flat plate. Filling progressed satisfactorily with no apparent formation of air pockets in the cells.

TABLE 1. DRILLING TESTS ON HONEYCOMB CORES FILLED WITH SHELL EPOXY NO. 1001

Drill speed, surface ft. per min.	Feed, in. per rev.	Hole size, in.	Remarks*
150	0.003	0.512	Resin melted and stuck to drill
50	0.003	0.505	Resin melted and stuck to drill
50	0.009	0.506	Slight melting
50	0.009	0.499	Slight melting
50	Hand	0.519	Heavy through feed—resin did not melt
80	Hand	0.517	Through feed with oil coolant—resin did not melt
80	0.012	0.505	Oil coolant—no melting
70	0.012	0.500	Water coolant—no melting

* All holes had burrs at the bottom due to brittle nature of resin. Subsequent tests with Shell Epoxy No. 1007 eliminated this trouble.

TABLE 2. DRILLING TESTS ON HONEYCOMB CORES FILLED WITH SODIUM SILICATE AND METAL POWDER

Drill Speed, Surface ft. per min.	Feed, in. per rev.	Filler Metal	Remarks
150	0-003	Titanium ...	Excessive drill wear—honeycomb torn
75	0-003	Titanium ...	Slight reduction in drill wear—honeycomb torn
50	0-003	Titanium ...	Normal drill wear—tearing reduced
50	0-003	Stainless steel	Normal drill wear—clean hole
75	0-003	Stainless steel	Normal drill wear—clean hole
200	0-003	Aluminium	Normal drill wear—honeycomb torn
150	0-003	Aluminium	Normal drill wear—best hole in aluminium
50	0-003	Aluminium	Normal drill wear—honeycomb torn
75	0-003	Cast iron ...	Normal drill wear—clean hole
150	0-003	Cast iron ...	Normal drill wear—poor hole
50	0-003	Cast iron ...	Normal drill wear—clean hole, accurate size
150	0-003	Cast iron ...	Normal drill wear—clean hole, oversize

A second group of tests was made on a Buffalo drill press using a drill of the same form. For these tests, the honeycomb was bonded to an aluminium backing plate with an epoxy resin and was filled with a mixture of sodium silicate and powdered metal. Various metal powders were used, with the results indicated in Table 2.

SAWING HONEYCOMB STRUCTURES

Sawing tests on honeycomb sandwiches were carried out on a DoAll band saw with a maximum speed of 10,800 ft. per min. The work was hand-fed against a 24-pitch, $\frac{1}{2}$ -in. thick blade running at speeds ranging from 350 to 6,000 ft. per min. Every cut left burrs which had to be removed by abrasive-belt grinding. The higher cutting speeds are recommended because they give the smallest burr and produce the cleanest cuts.

Honeycomb cores present a slightly different problem. It is not desirable to saw this material parallel to the axis of the core cells with a toothed blade because of the excessive tearing of the thin (0-002-in. thick) material. Such an operation would require substantial support for the cell walls.

Core material can be cut parallel to the axis of the cells if a knife-edge band is used and is operated at a minimum speed of 10,000 ft. per min. All types of knife-edge bands will operate satisfactorily, including single-bevel, double-bevel, wavy-edge, and scalloped-edge. The single- and double-bevel edges proved most satisfactory from the standpoint of cleanliness of cut.

Band-sawing across the core—at right angles to

the axes of the core cells—has not been particularly successful due, mainly, to the absence of a kerf when knife-edge blades are used. It is suggested that the core material should be fabricated to the required height rather than sliced to size with a band saw. Results of tests in which a single-bevel blade was used for cross-cutting core material are shown in Table 3.

After machining cores that have been temporarily filled, the material must be completely removed. Two methods were employed to remove epoxy resins and Cerrobend (the latter was used to mount the core material for slicing tests)—oven-heating and steam cleaning. In every instance, a thin film (epoxy resin) or a few globules (Cerrobend) remained on the ribbons.

Blasts of hot air at a pressure of 20 lb. per sq. in. and a temperature of 300 deg. F. failed to remove the film or the globules. The epoxy film, however, can be dissolved in methyl, ethyl, ketone, or acetone. It is recommended that Cerrobend be avoided, due to the contaminating effect of the the residual tin-lead alloy in subsequent brazing operations.

Iron-powder and sodium-silicate filler is the most easily removed. For this purpose, the part may be immersed in boiling water for approximately 30 min., or subjected to a water-steam jet for about 10 min. The iron powder can be salvaged and re-used.

CONCLUSIONS

1. On the basis of extensive tests, it can be stated that high-temperature honeycomb sandwich and core materials can best be machined by elec-

TABLE 3. BAND-SAWING TESTS ON HONEYCOMB CORES (AT RIGHT ANGLES TO THE CELL AXIS) WITH A SINGLE-BEVEL BLADE*

Saw speed, ft. per min.	Feed, in. per min.	Remarks
LOOSE BLADE GUIDES		
4,320	Rapid	Crooked cut—straightened out when feed was reduced
5,400	6	Straight cut—small burr
5,400	6	Slight run-off
TIGHT BLADE GUIDES		
6,120	8 $\frac{1}{2}$	Straight cut—slight burr
7,560	15	Cut ran out
7,560	6	Cut ran out
10,800	1-2 to 6	Cut ran out—unsatisfactory

* Mist coolant (Johnson's wax with water—1:20) was used for all tests at the rate of 40 drops per min.

trolytically-assisted grinding with metal-bonded abrasive wheels.

2. Rough-cutting of the sandwich and core parallel to the core axis can be carried out on a band saw with commercially available blades, and at appropriate speeds and feeds.

3. Conventional shop equipment can be used to machine honeycomb cores if the cell walls are first

supported by an adequate filler. This method is not recommended, however, because the filler must be removed, and incomplete removal may result in contamination during later brazing operations.

4. Where required, the core may be finished to height limits of ± 0.001 in. by means of a special slicing tool, followed by electrolytically-assisted grinding.

New Michigan Spline-rolling Technique

New tooling which has been developed by the Michigan Tool Co., Detroit, Michigan, U.S.A., enables long splines or serrations to be rolled, on Roto-Flo machines, on solid shafts or tubular parts with comparatively thin walls, as shown in Fig. 1. It is stated that the dimension from the root of the spline to the bore of a tube may be as little as 0.075 in.

For the new method, cylindrical racks of the form shown in Fig. 2 are employed, the teeth being of the same height throughout. These racks are reciprocated over the work rapidly, with a fairly short stroke, and the force exerted is only of the order of 3,000 to 4,000 lb. As the racks reciprocate, the work is fed axially at the rate of $\frac{1}{16}$ to $\frac{1}{8}$ in. per sec. until splines of the required length have been rolled. Thin walled tubes may be mounted on mandrels for the rolling operation, to avoid risk of bore distortion.

The cylindrical racks, which are 8 to 10 in. long, are made from alloy steel. When a portion




Fig. 1. Thin-walled parts on which splines have been rolled by a new Michigan technique

of the periphery becomes worn, a rack may be turned in its holder to present a fresh section to the work. To enable splines to be rolled fairly close to a shoulder, a rack may be employed which has a right-angle notch extending for the full length.

Gaston E. Marbaix, Ltd., Devonshire House, Vicarage Crescent, Battersea, London, S.W.11, represent the Michigan Tool Co. in this country.




Fig. 2. The cylindrical rack employed for the new Michigan spline rolling process, and a shaft with long splines produced by rolling

New Production Equipment

Norton Industries 40-ton Inclinable Power Presses


Norton Industries, Ltd., Stafford House, Norfolk Street, Strand, London, W.C.2, have introduced a 40-ton inclinable power press which is available in both geared and ungeared types, the latter being shown in the accompanying illustration. Inclination of the cast-iron frame is effected by screw and nut, and there is provision for locking the adjustment in the 16, 26, and 36 deg. positions. Steel tie bars, which can readily be removed, are incorporated.

Drive from the motor to the flywheel is transmitted by V-belts, and phosphor-bronze shaft bearings of large proportions are fitted throughout. On the ungeared press, the ram speed is 100 strokes

per min., and the stroke is adjustable in eight increments, from 1½ to 4½ in., through the medium of a phosphor bronze eccentric on the crankpin. The geared press runs at 50 strokes per min. and the stroke is adjustable from ¾ to 3½ in. The high-duty cast-iron ram moves in adjustable V-guides, and height adjustment is effected by a ratchet mechanism. A maximum daylight of 13 in. is provided, and the minimum distance from ram to bolster, with stroke and adjustment down, is 5 in. An adjustable top ejector is incorporated. The bolster measures 27 by 20 in., and has an 11½ in. diameter hole fitted with a removable ring of 6-in. bore.

An improved clutch has been specially developed which incorporates a solid key of chrome-vanadium forged steel, hinged in a knuckle joint formed in the clutch hub keyed to the crankshaft. The key engages a forged steel driving ring spigoted in the flywheel. When engaged, the key is in direct compression only, and it is stated that, apart from lubrication, the clutch requires no attention. Control of the press is by foot lever, and a selector can be set for single-stroke or continuous running.

Automatic lubrication is normally provided by a Tecalet-Bijur high-pressure system, but alternative systems can be fitted to suit customer's requirements. Additional equipment which can be incorporated includes Udal interlocked or other types of guards, a ram balance cylinder, a cushion cylinder, a pneumatic control for the clutch, and a stroke counter.



Norton Industries 40-ton inclinable press

Baker Perkins Taccone Diaform Diaphragm Moulding Machine

The Foundry Plant Division of Baker Perkins, Ltd., Hebburn on Tyne, Co. Durham, has recently introduced the Taccone Diaform diaphragm-type moulding machine, as shown in the accompanying illustration. These machines are made in a range of sizes to accommodate moulding boxes from 12 by 18 in. to 35 by 96 in., and special sizes can also be supplied. Built under licence from the U.S.A., the machine incorporates a flexible rubber diaphragm for applying the pressure required to

consolidate the sand round the pattern projections, and it is claimed that this system offers several important advantages. In particular, the pressure applied to the sand is approximately equal at all positions, and the density of the resulting mould is therefore uniform. The high pressures exerted on the sand, which may be of the order of 80 lb. per sq. in., depending on the hardness required, result in a reduction of its original volume by about one-third, and it is stated that the mould is harder than those obtainable on conventional jolt-squeeze machines.

The use of the rubber diaphragm results in the outer surface of the mould taking up roughly the same contours as the pattern plate, and the process is sometimes termed contour moulding. An accurate reproduction of the pattern shape is obtained, and castings can be made to close tolerances. Air which is squeezed out from the sand, and from the space beneath the diaphragm, escapes at the pattern face, and it is believed that good venting of the mould is thus ensured.

A squeeze head, supported on posts at each corner, carries the diaphragm and the necessary air pressure control equipment, the diaphragm being held up clear of the moving parts of the machine by vacuum when it is not in use. The diaphragm is not subjected to excessive stress and will usually suffice for some 70,000 moulds before replacement is necessary. A substantial base, which carries the four posts, is extended beyond the head at one side. On this base there are

ways for a wheeled carriage, which is moved by a long-stroke horizontal air cylinder. Mounted on this carriage is the stripping unit, which is also powered by an air cylinder, and above it, the pattern plate.


With the normal installation, the sand supply is taken from a metering hopper, fed from a conveyor band, and as the pattern plate, fitted with a moulding box and an additional frame to retain the excess sand, is moved towards the squeeze head, the sand is released. The arrangement is such that the sand is evenly distributed in the box and is ready for squeezing without further treatment. As soon as the carriage has moved the mould into position beneath the head, air pressure is applied above the diaphragm and the mould is consolidated in about 2 sec. Suction is then exerted to retract the diaphragm, and the carriage is moved outwards to the stripping position, and the mould removed. A normal moulding cycle occupies between 15 and 20 sec., according to the efficiency of the handling system employed for the moulds, so that high rates of production can be maintained.

Leifeld Type Plb 1200 Hydraulic Spinning Lathe

The type Plb 1200 hydraulic spinning lathe, shown in the figure, has recently been added to the range built by the German firm of Leifeld, who are represented in this country by Embassy Machine & Tool Co., Ltd., 248 Watford Way, Hendon, London, N.W.4.

The 48-in. centre, all-gear, headstock, and the bed, are mounted on a well-ribbed cast iron base, which is normally sunk, for the greater part of its depth, in a pit in the shop floor. Drive to the headstock is taken from a 25-h.p. motor mounted at the rear, through V-belts, and 18 spindle speeds, ranging from 5 to 625 r.p.m., are provided. Mounted in parallel and taper roller bearings at the nose end, and a plain roller bearing at the rear, the spindle is bored to take a pusher rod for a hydraulically-operated ejector mechanism which facilitates the removal of formed workpieces from the chuck. The spindle nose has a quick-acting cam lock flange, and a short, tapered, locating portion to receive the spinning chucks.

Provision is made for moving the bed, which carries the tailstock and saddle, in adjustable guide-ways on the base by means of a hydraulic cylinder, either for performing the actual spinning operation, or for adjusting the length of the gap from 16 to 54 in. This motion is controlled by a conveniently placed lever, and movement of a second lever operates a hydraulic clamping arrangement




Baker Perkins Taccone Diaform diaphragm moulding machine

whereby the bed is secured to the base. If required, bases can be supplied which enable gap lengths of 74 and 94 in. to be obtained. The tailstock barrel has a maximum stroke of 30 in., and variable clamping forces from 0 to 5 tons can be applied to the work hydraulically, a control valve and pressure gauge being mounted on the front of the body. A freely-rotating end piece on the barrel, to which back-up plates can be bolted, runs in taper roller bearings. The body is traversed on the bedways by rack and pinion, and, if required, cross-adjustment can be provided, to enable certain operations, such as necking, to be performed on the work.

A support bracket for the saddle, which slides on a separate base, can be attached to the front of the bed, as shown. The saddle can be turned through a full circle on the swivel base, which is secured either to the bed or the support bracket by four clamps. T-slots for the clamping bolts extend lengthwise in the top surface of the bed and crosswise in the support bracket, to enable the saddle to be mounted in various positions.

The compound slide, which carries the spinning roller, is traversed on inverted vee and flat guide-ways by a hydraulic motor mounted at the headstock end of the saddle, through 2-speed reduction gearing and a screw and nut. Adjustment of the steplessly-variable spinning feeds, and reversal of the slide, are obtained by means of a lever on the motor housing, and rapid power traverse is engaged by a second lever. The cross-slide may be moved either by a handwheel, through a screw and nut, or by a hydraulic cylinder, and an interlocking arrangement is incorporated to prevent simultaneous engagement. For stepless variation of the contact pressure between the spinning roller and the work, there is a control valve on the cross slide, and a hydraulic pressure gauge is fitted to facilitate setting. The hydraulic cross slide permits of spinning certain non-circular shapes without the need for special equipment, and, if required, a template-controlled copying system can be provided.




Leifeld type P1b 1200 hydraulic spinning lathe

Mounted on the rear of the bed, the hydraulic unit incorporates a 3-stage pump driven by a flange-mounted motor. Pressure oil is delivered to the hydraulic motor through passages formed in the swivel base and the saddle, and with this arrangement the amount of piping at the front of the machine has been reduced. If required, the push-buttons for controlling the electric motors can be mounted on a swivel pendant unit, as shown.

Prototype Developments Optical Projector

The bench-type optical projector shown in the accompanying illustration has recently been introduced by Prototype Developments, Ltd., Arundel Road, Luton, Beds., for viewing threaded and other components up to 3 in. diameter. Work is held between two horizontally opposed centres, one of which is spring loaded and the other locked by a retaining screw. If required, a micrometer may be fitted in place of the fixed centre to facilitate accurate positioning of the work with reference to a thread form or other pattern outlined on the viewing table. Fixtures of special design may also be used for holding the work, in place of the centres normally provided.

The head in which the centres are held has vertical and lateral adjustments, to enable the work to be correctly positioned in the light path. In addition, the head can be inclined for viewing a thread at the helix angle, and turned horizontally



Bench-type optical projector made by Prototype Developments, Ltd.

through 360 deg. This latter movement enables the work to be loaded at the front, and then swung into position between the light source and the lens, as shown in the illustration. Illumination is provided by a 12-volt, 100-watt, projection lamp, which, together with a double condenser and a continuously-rated mains transformer, is contained in a ventilated housing, secured by sliding clamps to two tubular guides.

Two fixed-focus lenses, providing magnifications of 10 and 20 \times are normally supplied, but lenses of higher power are available on request. The image is displayed on a rotatable plastics-faced viewing table, on which drawings can be made in pencil, and removed at


will. Daylight viewing is permitted by a curtain which prevents extraneous light from falling on the viewing table. The equipment is 37 in. high, and has a 13-in. square base.

Large Michigan Gear Shaver

The type V.200 gear shaver, here shown, has recently been built by the Michigan Tool Co., Detroit, Michigan, U.S.A., and is installed at the West Lynn, Mass., plant of the General Electric Co., for finishing reduction gears for marine turbine drives.

Stated to be the largest of its type yet built, the machine has a capacity for shaving gears up to 200 in. diameter with face widths up to 74 in., which may have integral shafts up to 40% in. diameter. It will handle internal and external spur, helical, and double-helical gears. The 178-in. diameter table will support gears with weights up to 67 tons, with fixtures weighing up to 22½ tons, and rotates on a variable-pressure oil film with an accuracy, it is claimed, within 0.0002 in. for concentricity, and run out in the plane of the working surface. Steplessly-variable table speeds ranging from 0.93 to 15.16 r.p.m. are provided by a d.c. driving motor.

There are two shaving heads, which can be adjusted independently for angle, and will take cutters from 7 to 12 in. diameter, with 2½-in. bores, and face widths up to 3 in. The upper shaving head is adjustable for height. For the shaving operation, the cutter spindles are set at an angle



Michigan type V.200 shaver for large marine reduction gears (reproduced by courtesy of The General Electric Co., U.S.A.)

to the axis of the gear, and the saddle which carries the heads is reciprocated slowly on the column ways. Since two cutter heads are employed, comparatively short cycle times are obtained, and both ends of double helical gears are shaved simultaneously. Swarf is removed by means of a magnetic-type conveyor.

Provision is made for mounting inspection equipment on the machine, so that the work can be checked without the need for removing it from the table.


Weighing approximately 76 tons, the machine has an overall height of 14 ft. 2 in., and occupies a floor space of 36 ft. 7 in. by 19 ft. 3 in.

Gaston E. Marbaix, Ltd., Devonshire House, Vicarage Crescent, London, S.W.11, are the agents in this country for the Bammesberger Tool Co.

Bammesberger Special-purpose Machines

The German firm of Bammesberger, who are represented in this country by Mortimer Engineering Co., 202-206 Acton Lane, London, N.W. 10, build a variety of special-purpose machine tools incorporating their standard electro-hydraulic unit heads and slides. A representative example, of the 5-station trunnion-type, seen in the illustration, performs both machining and assembling operations on pedal shafts, one of which is shown inset.

Blanks cut from drawn-steel tubing are first rough- and finish bored at each end. Next, two oil holes are drilled at right angles to the axis and deburred, and, finally, bushes from a vibratory feeder are pressed into the counterbored ends. When the machine is operated at 80 per cent efficiency, the pedal shafts are produced at the rate of 130 per hour. For the first two operations, two type BS 16 single-spindle drilling heads, of $\frac{1}{2}$ -in. diameter capacity in steel, and two type DS 16 single-spindle precision boring heads, are employed. The latter have built-in equipment for controlling the operating cycle and for stepless adjustment of the feed rate. A type KS 16 standard slide unit with a 2-spindle drilling head,



Bammesberger 5-station trunnion-type special-purpose machine for operations on pedal shafts


a de-burring unit, and two cylinders for inserting the bushes, are also provided.

Included in the range of Bammesberger heads is a single-spindle tapping unit, designated type GW 33, which has positive pitch control by lead-screw and nut. There is also a slide-mounted type SG 80 head which is designed for performing turning and countersinking operations on relatively large parts. This unit can be supplied with a facing head and a built-in cylinder to provide the transverse movements.

Machines can be supplied for fully-automatic operation with either hydraulic or mechanical work clamping, or with hand-operated loading, clamping, and unloading arrangements. Among special-purpose equipment recently built may be mentioned a rotary indexing machine for facing, drilling, milling, reaming, and tapping windscreen-wiper parts; a 2-way machine for facing wedge-type slide valves; a 5-station rotary machine for producing eye-bolts; a 2-way, 3-station, transfer machine for operations on both sides of cast aluminium gear casings; boring and facing machines for rear axle housings; and a 16-spindle drilling machine of single-way horizontal design.

D'Andrea Boring and Facing Head

Herbert Widdowson & Sons, Ltd., Canal Street Works, Nottingham, are the sole distributors in this country for the Italian-made D'Andrea boring and facing head shown in the figure.



D'Andrea boring and facing head

A noteworthy feature of the design is that radial feed can be applied to the facing slide either by hand or automatically, and may be started and stopped, as required, while the spindle of the associated machine is running. The head is available in three sizes, with radial movements of the facing slides of $1\frac{1}{2}$, 1 $\frac{1}{2}$ and 2 $\frac{1}{2}$ in., and capacities for facing workpieces of 8, 12 and 16 in. maximum diameter. Different sizes of Morse and non-sticking taper shanks can be supplied for the attachment of the heads to the cutter spindles of drilling, milling and boring machines, for example.

The centrally-disposed housing for the feed gears is attached, by means of screws, to a ring secured to the spindle head on the machine, so that it is prevented from rotating with the body which carries the facing slide. Power radial feeds at the rates of 0.0025 and 0.0075 in. per revolution are provided, motion being transmitted to the facing slide by separate sets of differential gears, mounted, in tandem, concentric with the body, thence through a safety clutch and a precision-ground screw.

Selection of feeds is made by a lever on the side of the housing, and adjustable dogs are provided for

automatically stopping the radial movement of the slide.

A spindle extending from the housing carries a crank for hand radial adjustment of the slide, and is fitted with a dial which is calibrated to read directly in increments of 0.0005-in. on diameter. A second dial indicates the slide movements in increments of 0.05-in. on diameter. The slide incorporates a quick-acting clamping arrangement to facilitate changing cutting tools.

Digimatic Automatic-positioning Worktable and Control System

Electronic Control Systems, Inc., Los Angeles, California, U.S.A., a subsidiary of General Dynamics Corporation, have developed a worktable and automatic control system for use in conjunction with a drilling machine, for example. The complete set of equipment, which is known as the Digimatic model C-202 point positioner, comprises three main elements, namely, a punched tape preparation unit, shown in Fig. 1, a combined tape-reader and control console, and a worktable as seen in Fig. 2.

By means of the tape preparation unit, a punched tape is produced directly from the information on the working drawing. The tape is then transferred to the tape reader/control console, from which the information on the tape is automatically transmitted to the worktable. Motion is imparted to the table in accordance with the



Fig. 1. The punched-tape preparation unit for the Digimatic Type C-202 Point Positioner




Fig. 2. The worktable of the Digimatic Type C-202 Point Positioner, which is used in conjunction with a punched-tape preparation unit and a combined tape-reader and control console

punched information, and, in consequence, the work is located in the required position beneath the drill point.

The electronic circuit operates on a closed servo-loop system, whereby the table position is automatically checked to ensure accurate location. It is stated that the speed of movement of the table slides, combined with the ease with which the tape can be prepared from a drawing and the elimination of non-productive time, enables one drilling machine equipped with this system to undertake work that would require approximately five conventional machines.


The table can be positioned to within 0.001 in. of a required setting, and can be adapted for use on machines for such operations as spot-welding, riveting, engraving, tapping, countersinking, and template plotting. Nine auxiliary operations can be catered for by the system, to include such functions as magnetic clamping and unclamping, and coolant flow control, for example.

Startrite-Meba Horizontal Bandsawing Machine

Under a reciprocal agreement between the Startrite Machine Tool Co., Ltd., Bishops House, Gads Hill, Gillingham, Kent, and Meba Maschinenbau, Esslingen, vertical bandsawing machines made by the former, and horizontal machines made by the latter, are to be marketed in both countries under the name Startrite-Meba, and certain parts will be produced under licence in both works.

Designed for repetition cutting-off operations on a variety of ferrous and non-ferrous materials, the German-built machine, here illustrated, is available with capacities for cutting bars up to 10 and 12% in. diameter, or 10 by 16% and 12% by 17% in. cross-section. The moving vice jaw is initially adjusted by a hand-wheel and screw, and pressure can then be quickly applied, and released between successive cuts, by a lever and cam arrangement, from either side of the machine. Operation of the clamping lever also causes the adjustable work stop to be swung clear to prevent subsequent wedging of the severed piece, and when the lever is released, the stop is automatically returned. The vice jaws can be swivelled through angles up to 45 deg., for mitre cutting.

Drive is taken from a motor of $\frac{3}{4}$ or 1.1 h.p., depending on the size of the machine, through a taper pulley mounted on the rotor shaft. The pulley engages a point on the internally-tapered surface of a ring of friction material, which is secured to the input shaft of a totally-enclosed constant-speed gearbox. Axial adjustment of the motor along a slideway, by means of a hand wheel, with reference to a scale, causes the radius at the point of contact between the pulley and the ring to be altered, with the result that stepless variation of the speed of the cutting



Startrite-Meba horizontal bandsawing machine

saw, from 46 to 230 ft. per min., is obtained. The gearbox is arranged to pivot about the output shaft so that pressure between the pulley and the ring is maintained at different settings of the motor slide.

A 1-in. endless saw blade, with a length of 150 in., produces a cut 0.042 in. wide, and the adjustably-balanced saw frame is moved towards the work under rapid traverse, before a controlled, steplessly-variable feed is engaged. During cutting, coolant is delivered from a built-in tank in the base by a pump driven from the main motor, and the latter is automatically stopped at the end of the cut. Changing of blades is facilitated by the provision of swivelling guides. It is stated that cuts can be made with a maximum run-out of 0.005 in. from the vertical plane, and that 28-ton mild steel, for instance, can be cut at the rate of 4 sq. in. per min.

Equipment available includes an adjustable work-stand; vice jaws for bundle cutting; castors to enable the machine to be readily moved on the shop floor; and a butt-welding unit incorporating a blade shear, annealing facilities, and a motor-driven grinding head.

Brown & Ward Automatic Bar Feed Unit

An automatic bar feed unit recently introduced by Brown & Ward (Tools), Ltd., Hatherton Lane, Walsall, Staffs., has been developed from the prototype, semi-automatic, equipment which was described in *MACHINERY*, 89/353-10/8/56.

Available for use on most types of automatic screw machines, the latest unit has provision for automatically feeding fresh bar stock through the collet, which is then closed, and the end of the bar is parted-off square with the periphery. Since these motions form part of the fully-automatic working cycle, the machine can be operated continuously.

Fig. 1 shows a view of the unit with some of the covers swung clear, and fresh bar stock may be seen on the inclined magazine chute, ready for loading into the feed tube. Eighteen $\frac{1}{2}$ -in. diameter bars, or 65 $\frac{1}{4}$ -in. diameter bars can be accommodated on the chute, and the unit can be supplied to take lengths of 10 or 12 ft. Support columns for the feed unit have provision for storing additional bars, which are loaded, as required, through an opening at the top of the chute.

As with the previous unit, the bar in the feed tube is moved axially into contact with the turret or swing-stop, at the end of each working cycle of the machine, by the action of a pusher arm coupled to an endless chain which passes round free-wheel sprockets at the ends of the unit. Drive to the sprockets is taken from an electric motor through a clutch which slips during the operating cycle, and can be adjusted to suit the diameter of the bar stock.

When the remaining length of bar is insufficient for the production of another workpiece, it is automatically ejected through the collet, and a second electric motor is started to return the pusher arm rapidly to the left-hand end of the unit. At the same time, a solenoid on the headstock is operated, with the result that the auxiliary stop A, Fig. 2, is swung downwards in front of the collet. In this close-up view of the tooling area on a Brown & Ward type 575 automatic, the usual swing stop B is shown in its working position for controlling the bar feed in preparation for the production of a component.

When the pusher arm has been returned to its left-hand position, the leading bar on the chute




Fig. 1. The latest Brown & Ward automatic bar feed unit is here shown with some of the covers swung clear




Fig. 2. Close-up view of the Brown & Ward type 575 automatic, showing the auxiliary swing stop used in conjunction with the bar feed unit

falls into the feed tube, and stops are swung into position beneath the next bar. Because the pusher arm is attached to an endless chain, reversal is obtained by a virtually continuous movement, and at the beginning of the feed stroke the rapid traverse motor is stopped. The bar is now moved into contact with the stop A by the action of the feed motor, and the collet is closed. Next, the stop A is swung clear, and the end of the bar is faced by the parting-off slide. Subsequent feed movements are imparted to the bar in the usual way at the end of each working cycle of the machine. The time required for loading a fresh 10-ft. long bar is 4 sec.


New Wheel Dresser for Churchill Type BW Plain Grinder

A new wheelhead-mounted dressing unit has recently been made available for the type BW 10-by 36-in. plain grinder built by the Churchill Machine Tool Co., Ltd., Broadheath, Manchester, and a close-up view of the machine fitted with this equipment is given in the figure.

With the new unit, profile shapes can be formed on grinding wheels up to 6 in. wide, and steplessly-variable traversing speeds of the dressing slide are obtained by means of a screw driven by a small electric motor, which is interlocked with the workhead driving motor. Vertical movement of a spring-loaded plunger, which carries the diamond holder, is controlled by a template during the dressing cycle, and adjustments for applying a fresh cut to the wheel at the completion of each pass are made in increments of 0.0001 in. by a knob-operated "click" feed mechanism.

The machine illustrated, which, as reported in MACHINERY, 93/853—8/10/58, was demonstrated recently at the showrooms of the sole agents, Charles Churchill & Co., Ltd., Coventry Road, Birmingham, is also fitted with the M.P.J. electro-sizing gauge for automatically controlling the in-feed movement of the hydraulically-operated wheelhead.

(below) Close-up view of the Churchill type BW plain grinder fitted with a new wheelhead-mounted dressing unit



Set-up on a Conomatic for Producing Wedge Gate Valve Seats

The Cone Automatic Machine Company, Ltd., Aldridge, Staffs., have recently supplied to a well-known firm in this country a British-built 1½-in.-6 Conomatic, as shown in Fig. 1, specially equipped for producing valve seats from stainless steel bar, in a cycle time of 38 sec. Intended for use in a wedge gate valve, the seat has an angular front face, as seen in the drawing Fig. 5, which also shows the sequence of operations.

Features of the set-up include the provision of an angular facing attachment at position No. 5, and a scribing tool at position No. 6. High-speed steel tools are used throughout, and the spindle speed of 208 r.p.m. provides a surface speed of 73 ft. per min. At position No. 1, centring with a 1¼-in.




Fig. 2. Close-up rear view of the Conomatic, showing the angular facing attachment

diameter drill, and knee turning to 1¼ in. diameter are carried out from the end-working tool slide, and the 1.156 in. diameter is rough formed from the cross-slide. The centre hole is rough drilled part way, the 1½-in. diameter is turned with a knee tool, and the 1¼-in. diameter is finish formed from the cross slide at position No. 2.

Drilling to depth is completed at the third position, and a cross-slide form tool is applied to finish the 1.312- and 1.156-in. diameters. A spade tool, held in an auxiliary spindle on the end-working slide, is employed at position No. 4 to finish the 1-in. diameter bore, and the face at the collet side of the 1.312-in. diameter is finished, to produce the 0.343-in. dimension by means of a relieving




Fig. 1. This 1½-in.-6 Conomatic was demonstrated at the Milan Machine Tool Exhibition, set up for producing stainless-steel valve seats




Fig. 3. Part-sectional view showing the design of the angular facing head

facing attachment mounted on the cross-slide. In the close-up rear view of the machine given in Fig. 2, the spade tool is seen at A, and the facing tool slide at B.

Angular facing, to 5 deg., at position No. 5, is performed with an end-working attachment C, specially developed for the purpose. A drawing of this attachment is given in Fig. 3, and it is seen removed from the machine in Fig. 4. The attachment housing D, mounted on the end-working tool slide, carries a central shaft running in opposed Timken taper roller bearings. This shaft




Fig. 4. Close-up view of the angular facing attachment removed from the machine




Fig. 5. The tool layout employed for producing the valve seat shown above

is driven from the end column of the machine in synchronism with the work spindles. The enlarged-diameter head *E* of this shaft is recessed at the front end to an angle of 5 deg. with the axis of the attachment, and in this recess the shank of a tool-block *F* is supported on Timken opposed taper roller bearings.

The tool block, which carries a tool-bit at *G*, is prevented from rotating by two round guide rods *H* and *J*, which are free to slide axially and are connected by a pivot at *K*. As may be seen, the bar *H* is accommodated in the slotted end of the bar *J*. Rotation of the headed shaft *E* thus causes the facing tool to follow an arcuate path, and the 5 deg. angular face is produced on the component. The centre about which the tool rocks, it will be noted, is the point of intersection between the axes

of the headed shaft *E* and the tool-block shank.

An identification mark must be scribed on the 1.312-in. diameter, in line with the "low" point of the 5 deg. taper, to indicate the exact assembly position for the valve seat in the body. This line is scribed, at position No. 6, by means of a tool mounted in a rotating attachment on the end-working slide, which is driven at the same speed, and in the same direction as the work spindle. Parting-off is carried out from the cross-slide at this position, and the bar is then fed out to a stop, ready for the next cycle.

This 1½-in.-6 Conomatic was demonstrated at the recent Milan Machine Tool Exhibition, and it is of interest to note that the machine was delivered direct, by road vehicle, from the makers' works to the Exhibition, by British Road Services.


Crosland Work Tables with Automatic Adjustment for Height

Work tables with automatic adjustment for height have recently been placed on the market by William Crosland, Ltd., Bredbury, near Stockport, Cheshire, to facilitate the handling of sheet materials.

These tables are intended for use in pairs, as shown in the illustration, and each unit, which occupies a floor space of 30½ by 42 in., will support a stack of sheets up to 32 in. high, with a maximum weight of 900 lb. A stack of sheets, on which operations are to be performed, is loaded

on to a table at one side of an associated machine, with the aid of a fork-lift truck, for example. Each sheet is then removed, in turn, from the top of the stack and transferred to the machine for processing, and, when the operation has been carried out, is passed to the other table. As this procedure is repeated, the first table is raised and the second table is lowered, automatically, by a hydraulic system and springs, so that the tops of the stacks are maintained at the same height. The working height of the stacks can be adjusted.

The hydraulic system does not require power supply, and pressure fluid is passed from one table to the other through a single pipe. These tables, which are the subject of a patent application, can be positioned at a considerable distance apart and at different levels, if required.



Crosland work tables, with automatic adjustment for height, for handling sheet materials



The New Ludwigsburger Factory

Ludwigsburger Maschinenbau, G.m.b.H., Ludwigsburg, Wurttemberg, Germany, who build the Burr fine-boring and special-purpose machines, recently celebrated the tenth anniversary of the foundation of the company, and the opening of their new factory. The company originally occupied the Koenigin-Olga Barracks, in Ludwigsburg, where the drawing and estimating offices are still housed, pending the completion of further buildings on the new site. Foundations of the new works were laid in 1955, and the buildings recently completed comprise a large assembly bay, with a working area of about 56,000 sq. ft., and two machining bays, with a total area of about 65,000 sq. ft. In addition, there is a number of auxiliary departments, including a heat-treatment shop, with nitriding and other equipment, an inspection department, laboratories and development departments, and an apprentices school.

The main building of the new factory is shown in the heading illustration, and is particularly noteworthy for the high standard of natural and artificial lighting throughout, also for the imaginative use of colour. All the main production departments are on the same floor, below which there are shops for the production of electrical and hydraulic sub-assemblies, cloakrooms, and washing facilities. The space in the foreground, at present used as a car park, provides for future development, and a new office block is to be built shortly. At the rear of the main building there is a large area employed for the storage of castings and other raw materials, and it may be of interest to note that the company stress-relieve all major castings, after rough machining, by vibrating them on a special rig. This treatment occupies only two hours, as compared with the six hours that were


required previously when stress relieving was carried out by the more conventional method of heating the castings in a furnace.

About 800 people are now employed by the company, of whom 150 are engaged in the design and associated departments. There are some 450 workers in the production shops, and 80 apprentices. The latter are trained in a separate section, which is well equipped, and the company pay particular attention to their instruction, which is regarded as an important investment for the future.


All departments are served by overhead cranes and other handling aids. The machine tools and other equipment are of modern type, and many are particularly suitable for operations on large machine tool members. There is a well-equipped standards room, where the facilities include a spectrograph for the analysis of the various work-materials employed. Some of the machine tools and other units installed in the works are shown in the accompanying illustrations.

The opening ceremony was attended by representatives from German government and industry, including Dr. Karl Frank, the Finance Minister, who made the principal speech. The first speaker was Mr. Walter Trampusch, who briefly outlined the history of the Ludwigsburger Maschinenbau, and paid a tribute to his partner in founding the company, Mr. Willi Burr, who died some two years ago. There were also representatives from many leading industrial organizations in other European countries, including a number from Great Britain.


Burr fine-boring, special purpose and transfer machines are sold in this country by Geo. Kingsbury & Co. (Machine Tools), Ltd., 54 Victoria Street, London, S.W.1.



Hardened slideways of column and bed castings are ground on this special Billeteur open-side machine. Supported on a floor plate, the workpiece remains stationary, and the grinding unit is traversed past it. The grinding unit has a massive column with a cross beam that can be adjusted for height. On the beam, there are two side-grinding heads at one end, as shown, and a large face-grinding head at the other, with a segmental wheel, which can be readily swung into the working position.





In the Ludwigsburger plant, there are two Schiess vertical boring and turning mills, the smaller of which has a 5-station turret. The larger machine has an 8-ft. diameter table, and is here seen set up for machining, simultaneously, three bed castings to support the unit heads of a transfer machine.




To facilitate the wiring of control panels, support wires are attached to a frame to form a large-mesh grid. The connecting wires are secured to the support wires, and when wiring has been completed, the support wires are cut adjacent to the frame to leave a self-sustaining grid of connection wires.


The unloading end of a Ludwigsburger transfer machine for operations on the cylinder blocks for the engine of a new small car now being built in the Netherlands. This machine has nine working stations, with idle stations interposed to provide ready access for servicing and tool setting. Workpieces are mounted on platen jigs, which are moved from one station to the next by hydraulically-actuated shuttle bars. The jigs are returned to the loading station by a U-shaped conveyor at the rear



This Deckel type LKB/S jig borer has an optical positioning system whereby workpieces can be set within 0.00008 in. A grinding attachment can be fitted for finishing holes down to 0.024 in. diameter, and there is a loudspeaker system to indicate when the wheel contacts the work





One of the two Niles gear grinding machines at the Ludwigsburger factory. One tooth-flank is ground as the table is traversed in one direction, and the other flank, during the return stroke. Gears ranging from $\frac{1}{2}$ to 6 module, and up to 10 $\frac{1}{2}$ in. diameter by 4 $\frac{1}{2}$ in. wide can be ground



The slideway surfaces of columns and other machine members are flame-hardened on this Pyrodur type LMH equipment, with the workpiece mounted on the trolley whereby it is transported. A mixture of town gas and oxygen is used for heating, and the burner head incorporates jets for the quenching water which drains through grids in the floor. A hardness of 450-530 Brinell is obtained for a depth of 0.078 in. Similar equipment is installed for flame-hardening shafts up to 4 ft. long.

All the bores and faces for a housing for a 4-spindle unit are machined at one setting on this Dixi machine. The faces are held to a tolerance of ± 0.0004 in. from a datum plane. Four holes are bored at one end to 1.890 in. diameter, -0 , $+0.0012$ in., and at the other end to 1.378 in. diameter, -0.0002 , $+0.0004$ in. The machine is housed in a temperature-controlled room, where a Hydroptic 7 and two other SIP jig borers, also an Oerlikon machine, are installed. All work is brought into the room 24 hours before it is machined



This Scharmann type FB 100 horizontal boring machine is here seen set up for finishing operations on two spindle heads for Burr fine-boring units. The machine has an optical measuring system and the saddle for the worktable is supported on hardened slideways. Guide members of circular cross-section are provided for the headstock and support bearing. Other horizontal borers in the same bay of the new Ludwigsburger factory include two by Collet & Englehardt, and a large Giddings & Lewis machine

Buswell & Sweeney Master Bar Jig Borer

Recently introduced by Buswell & Sweeney, Ltd., Bolton Street, Watery Lane, Birmingham 9, the jig borer shown in Fig. 1 incorporates the patent Master Bar measuring system developed by the company.

Fig. 2 gives a close-up view of the measuring system for setting the work table longitudinally, and there is a similar arrangement for positioning the saddle on the bedways. The measuring bar A consists of a number of hardened steel gauge blocks with lapped contact surfaces, each of which has a step at one end, and is made to an overall length of 1 in. within very close limits. These gauge blocks are assembled with plain and stepped ends in contact, and are clamped endwise by a threaded rod and nuts. The measuring bar is mounted in a central slideway in the saddle, and the drum-type micrometer head B, which gives readings to 0.0001 in., is attached to its outer end. A slot is provided lengthwise in the top face of the measuring bar to take a stop, in the form of a pivoted, spring-loaded arm, mounted vertically in




Fig. 2. Close-up view of the Master Bar measuring system employed on the Buswell & Sweeney jig boring machine




Fig. 1. The Buswell & Sweeney jig borer with Master Bar measuring system

the carrier C. A cylindrical extension piece, integral with this carrier, can be moved axially in a bore in the end face of the table for adjusting the stop for reference setting, as will later be explained, and is secured by means of a clamping screw.

A table setting to the nearest inch value, short of the required position, is selected by inserting a $\frac{1}{4}$ -in. diameter roller in one of the transverse slots formed in the measuring bar by the abutting plain and stepped ends of two gauge blocks. Numerals are marked on the saddle at the sides of the measuring bar to facilitate selecting the required slot. Lengthwise adjustment of the measuring bar for any remaining part of an inch, to give the final required setting, is then made by means of the micrometer B. Next, depression of a push button mounted adjacent to the micrometer, causes the table to be traversed on the saddle guideways by a motor-driven screw. When the stop in the carrier C makes contact with the roller, the measuring bar and micrometer assembly is moved lengthwise with the table for a short distance against the action of a spring. At the end of this

travel, when the table has been brought to within 0.01 to 0.015 in. of the required position, two micro-switches housed in the casting *D* are operated successively. One of these switches interrupts the power supply to the traverse motor, and the other applies a magnetic brake to stop the table. The traversing screw is then disengaged from the driving motor by release of a knob-operated clutch, and the table—and with it the measuring bar and the micrometer—is finally moved to the required position by turning a hand-wheel until a zero reading is obtained on a dial indicator.

At the completion of a jig boring operation at one setting, the table is power traversed on the saddle ways in the opposite direction by depression of a second push button, to move the stop in the carrier *C* clear of the roller. The latter can then be removed from one slot in the measuring bar, and inserted in another in readiness for setting the table in the next required position.

When a datum point on the work has been set coincident with the centre line of the spindle at the beginning of a series of jig boring operations, a reference setting for the measuring system is made in the following manner. The micrometer *B* is set to zero, and the measuring bar and micrometer assembly is moved lengthwise, by means of a knob, until a zero reading is obtained on the dial indicator. This assembly is then held by a clamping screw, so that movement by the action of the spring is prevented. Next, the roller is inserted in the nearest slot in the measuring bar *A* to the stop in the carrier *C*. The stop is now brought into contact with the roller by movement of the carrier *C* axially, and, finally, the clamping screw is released.

The spring which holds the stop in the vertical position in the carrier *C*, exerts sufficient force to resist the contact pressure applied between the stop and the roller, during the final stage of the power traverse movement of the table when setting is being carried out. In the event of accidental over-run of the table, however, the stop pivots against the action of the spring so that it passes over the roller. Separate micro-switches are provided to stop the traverse motor when the table reaches the extreme positions at the ends of its travel.

The 42- by 25-in. table has a longitudinal travel of 30 in., and the cross movement of the saddle is 18 in. Power traverse, in each direction, for approximate setting purposes is at the rate of 60 in. per min.

The traverse screws run in oil baths, and the square-section ways on the substantial, well ribbed, bed and saddle are automatically lubricated.

THE SPINDLE HEAD ASSEMBLY

Steplessly variable spindle speeds up to 1,800 r.p.m. are provided by a Churchill-Sturm, 2½-h.p., hydraulic drive unit, and a 2-speed gear box, which are housed in the rigid, box-section column. This arrangement obviates the need for a clutch and a spindle brake. Gear changes are made by a lever on the side of the column, and two levers are mounted on the front of the bed for stepless adjustment of the spindle speeds. A large-diameter tachometer is provided on the spindle head to facilitate setting. It is proposed to incorporate a Churchill-Sturm unit of different design on future machines, and selection of spindle speeds will then be made by means of a single lever.

The spindle is mounted in line with the V-shaped guideways for the head, as viewed from the side of the column. Consequently, there is no overhang, and it is claimed that exceptional rigidity and freedom from vibration are thus ensured. Two precision ball bearings are provided for the nose end of the spindle, and roller bearings for the centre and upper end, and the quill, which is automatically lubricated, has an axial travel of 9 in. Four power feeds ranging from 0.001 to 0.008 in. per rev. are obtainable. A dial indicator spindle stop is fitted to facilitate boring holes accurately to pre-determined depths.

The spindle bore has a taper of 3½ in. per foot, and three slots are provided in the face of a locating ring at the nose end, to receive driving dogs integral with the shanks of interchangeable cutting tools. One of these slots, and the mating dog on each shank, is wider than the others, to ensure that a tool is always mounted in the same angular relationship to the spindle. The head has motorized adjustment of 16 in. on the column, and the maximum distance obtainable between the spindle nose and the working surface of the table is 30 in. Fine hand adjustment is also provided, and at the completion of setting, stresses in the traversing screw can be released by rotation of a knob, to ensure that there is no deflection of the head when the hand operated clamps are applied for securing it to the column ways.

The machine occupies a floor space of 115 by 115 in. and weighs approximately 5 tons. Stanley Howard, Ltd., 73 Devon Street, Saltley, Birmingham, 7, have been appointed distributors for Master Bar jig borers.

DELIVERIES OF ENGINEERS' SMALL TOOLS and instruments during the first half of this year averaged £5,503,000 per month, as compared with £5,721,000 for the full year 1957.

News of the Industry

Bradford

CROFTS (ENGINEERS), LTD., Thornbury, are well employed on the production of their extensive range of power transmission equipment for customers both at home and abroad. Work in progress includes air-actuated magnetic and mechanical clutches, conveyor drives, flexible couplings and drives, machine-cut gears, plunger blocks, shaft-mounted gear units, variable-speed motor gears, variable-speed pulleys, V-rope drives, and worm reduction gears. Our attention was drawn to the firm's recently-developed, stationary field, magnetic clutch and brake, which is available in wet- or dry-plate types for gearbox installation, coupling two shafts, or for use with pulleys, sprockets, or gear wheels. Other activities include the production of iron, steel and non-ferrous castings.

CARTER GEARS, LTD., Thornbury, are experiencing a good demand for hydraulic steplessly-variable speed gear units which range in size from $\frac{1}{4}$ to 35 h.p. Orders are in hand for the Continent and markets further afield. Units are available with different methods of control and mounting arrangements, in conjunction with electric motors and reduction gears, and the field of application is being steadily extended. Further developments are in progress and additional plant has been installed to facilitate production.

T. BOWERS & CO. (TOOLMAKERS), LTD., Thornbury, have a variety of jigs, fixtures, tools, gauges, reamers and special milling cutters on order, and the associated BOWERS INTERNAL GAUGE CO., LTD., report an expanding demand for internal micrometers, counterbore tool sets, and 2- and 3-point plug gauges. The internal micrometer range now includes $\frac{1}{2}$ to $\frac{3}{4}$ in., $\frac{3}{4}$ to 1 in., and 1 to 1.5 in. sizes, with either English or Metric graduations, also a 9-in. diameter instrument. Recent plant additions at these works include Jones-Shipman cylindrical and surface grinding machines, a Taylor-Hobson pantograph milling machine, and a Milwaukee swivel-head vertical milling machine.

MOORE MANUFACTURING CO., LTD., Laisterdyke, report a steady flow of orders, on both home and export account, for their full ranges of drill sleeves and sockets, in addition to lathe and grinding machine centres of all types, and standard and

special milling cutters. Extensions have now been completed and are in full operation.

STERLING MANUFACTURING CO., in addition to orders for independent and self-centring lathe chucks, are experiencing a steady demand for sub-contract machining work, which involves turning, boring, milling, and drilling operations.

BENSON VERNIERS, LTD., have a good order book for their various precision measuring instruments,

❖ ❖ ❖

Primarily to meet the needs of the dental profession for small, high-performance, silent air compressors, Alfred Bullows & Sons, Ltd., Long Street, Walsall, Staffs., have introduced three new Hydrovane units, one of which is shown, with the glass fibre cowl removed, in the illustration. It is anticipated that these compressors will also find numerous applications in industry. Known as the 2AR301E, the unit shown comprises a receiver-mounted Hydrovane rotary compressor driven by a $\frac{1}{2}$ -h.p. motor. The latter is controlled by a pressure switch with a range of 35 to 40 lb. per sq. in.



which include vernier calipers, height and depth gauges, gear tooth calipers, and beam trammels of various sizes. The recent introduction of hard chrome-plated instruments with clear-reading scales on a satin-chromium background has stimulated demand, and the chromium-plating plant which has been installed is now in full operation. Other work in hand includes reference verniers, rolling mill gauges, and linear and circular graduated scales for machine tools.

HENRY MILNES, LTD., report some reduction in the demand for their standard 13-in. swing lathe, admitting 38 and 72 in. between centres, and for the standard vertical milling machine with a table capacity of 30 by 8½ in. They are, however, increasing the production of their sliding head, elevating-table, heavy-duty fine boring machines, for which the Rockwell Machine Tool Co., Ltd., Welsh Harp, Edgware Road, London, N.W.2, are the sole selling agents. Orders have recently been booked from well-known machine tool makers, to whom the precision boring limits which can be obtained will prove of considerable value.

FLEXICON, LTD., inform us that there is a steadily-maintained demand for their various types of belting from customers in both the home and export markets. Round and V-belts are being supplied for various industrial applications, and F.S.H.O. belts for the coal-mining industry. Other types in steady request include nylon-cored V-belts and elastic-cored, miniature, fixed-centre V-belts. Orders are also in hand for link V-fasteners for use with V-section belts.

HINDLE AUTO PRODUCTS, LTD., state that the broaching and splining services which they provide are proving increasingly popular, and that orders for gear and rack-cutting and for standard and special gearboxes are maintained at a good level. Racks up to 32 ft. long, on 3" by 2½ in. section bars, have recently been cut for use in connection with pile-driving operations, and we may note that broaching and splining work has been carried out on medical instrument and cobalt ray machine parts.

MERCER PNEUMATIC TOOLS, LTD., are occupied with the production of ½-in. capacity motor-driven bench drilling machines, 9-in. circular bench wood sawing machines, automatic turret locks and coolant controls for capstan lathes and automatics, and components for pneumatic sanding equipment and hack-sawing machines.


H. B.

Ferodo Research Centre

Ferodo, Ltd., Chapel-en-le-Frith, Derbyshire, a member company of the Turner & Newall organization, have recently completed a research centre, at a cost of £750,000, adjacent to the main works. It was officially opened by H.R.H. Prince Philip, Duke of Edinburgh, K.G., on November 21.

The centre, which is a 3-storey building with more than two acres of floor space, has enabled all the chemical, physical and experimental production laboratories, test house, test fleet garage, and research administration to be brought together, for the first time, under one roof. It will perform an important function for science and industry, by reason of the effort that will be concentrated on the study of friction phenomena and the development of friction materials.

Accommodation provided in the new building is divided into four main sections. The test house wing, with accompanying workshop, garage, stores, and local administrations is on the left. Administration, conference room and library are housed in the front centre, and the physical and chemical laboratories are behind the administrative block. In the right wing, there is an experimental



The new research centre of Ferodo, Ltd., for the study of friction phenomena and the development of friction materials

production department, with associated stores and preparation rooms.

Friction materials were first produced in 1897 by Herbert Frood, founder of Ferodo, Ltd., in a small wooden hut at the bottom of his garden. Today the works cover more than 16 acres and provide employment for more than 3,000 people.

Gredag Pressing Lubricant for Titanium

It is reported by Acheson Colloids, Ltd., that The de Havilland Aircraft Co., Ltd., have adopted Gredag molybdenum disulphide grease (grade MP 30) as a titanium pressing lubricant on the basis of tests carried out by their Production Research Department. The lubricant is employed when producing hot titanium pressings on drop hammers, and the tests were carried out with the object of eliminating troubles caused by molybdenum disulphide build-up on the tools. It was found that Gredag MP 30 enabled good pressings to be produced, was easy to apply and economical in use, and did not build up, so that the need for cleaning the tools was eliminated. Gredag, it may be noted, is a registered trade mark of Acheson Industries (Europe), Ltd., of which Acheson Colloids, Ltd., are licensed users.

Machine Tool Merchants

The British Association of Machine Tool Merchants (Inc.), Effingham House, Arundel Street, Strand, London, W.C.2, held their annual general meeting luncheon at the May Fair Hotel, London, on November 25. As in previous years, there was a good attendance and the company included a number of distinguished official guests. The toast of "The Queen" was proposed by the newly-elected president, Mr. S. Plastock, and Mr. W. J. Taylor, C.B.E., D.L., J.P., M.P., Parliamentary

Secretary, Ministry of Supply, then proposed "The Association." In his speech, Mr. Taylor referred to the substantial scale of machine tool sales by the Ministry during the past two years, and expressed the opinion that the level would be maintained in the immediate future. It was now established policy to co-operate with the B.A.M.T.M. He believed that recent financial measures should be of benefit to members, particularly the reduction of Bank Rate and the relaxation of credit restrictions. The country had passed through a difficult period but he anticipated a high level of industrial activity this time next year, and he advised his hearers to look to the future with confidence.

Responding to the toast, Mr. Plastock spoke of the good relations that existed between the Association, the Ministry of Supply, the Board of Trade, and the machine tool manufacturers. He agreed that after a period of difficulty there were signs that industry had turned the corner.

Mr. H. Widdowson, immediate past-president of the B.A.M.T.M., proposed "The Guests," and in replying, Mr. J. C. Blair, C.B.E., said that the Association had a great function which it was performing very well.

At the 18th annual general meeting, which preceded the luncheon, Mr. S. Plastock (F. J. Edwards, Ltd.)—as mentioned above—was elected president for the coming year in succession to Mr. H. Widdowson (Herbert Widdowson & Sons, Ltd.), who remains a Council member as immediate past-president. Mr. R. Gidley [Martin Bros. (Machinery), Ltd.] was elected vice-president, and Mr. E. J. F. Bradley (Pidgen Bros., Ltd.) was re-elected hon. treasurer.

Chinese Orders for Machine Tools

The China National Machinery Import Corporation has placed two large orders with British machine tool firms, following the virtual lifting of the strategic ban last August in respect of Soviet bloc countries and China. It is stated that both orders were obtained in the face of severe foreign competition, particularly from Germany.

One order has gone to the Asquith Machine Tool Corporation, Ltd., Halifax. The value exceeds £600,000 and the items include some horizontal milling and boring machines of exceptionally large capacity. It is stated that the greater part of the contract is to be completed by the end of 1959, and it is pointed out that the ability to execute an order of this magnitude is a result of the far-sighted policy of the company in developing new facilities.

The second order, placed with the Machine Tool Division of the David Brown Group of companies, is for turbine gear hobbing machines to the value of approximately £500,000, complete with measuring instruments and gear cutting tools. Two of these machines will be of 216-in. capacity, and it may be noted that a similar hobber is being installed by the company in a German shipyard.



Mr. S. Plastock



Mr R. Gidley

New Foundry of John Hall & Son

The old-established firm of John Hall & Son (Oldham), Ltd., Union Iron Works, Oldham, a subsidiary of Dronsfeld Bros., Ltd., Atlas Works, Oldham, have recently completed the re-building and re-organization of their iron foundry for the production of Unihall castings. A large number of business executives attended the official opening ceremony on November 20, which was performed by the Mayor of Oldham, Councillor James Bradley, with Mr. S. W. Dronsfeld, chairman of the company, presiding.

Covering a floor area of 16,000 sq. ft., this modern foundry has good natural and artificial lighting and is served by Wharton 25- and 35-ton overhead electric travelling cranes. Castings up to 30 tons in weight are produced, and include diesel engine bedplates and columns and machine tool beds. Laboratory control facilities are available for mixing and melting ordinary, high-duty and special irons. There are three cupolas with a melting capacity of 15 tons per hour, and other equipment includes Hydroblast wet process and wheelabrator dry process cleaning plants.

Russia—A Challenge

(Continued from page 1271)

manufacture of many engineering products, including machine tools, heavy commercial vehicles, and electrical equipment, and it appears that these products are at least competitive in cost with those made in this country. In view of the intensive research that is being pursued with regard to the means of production generally, and automation equipment and processes in particular, moreover, it is likely that the cost of many engineering products will be substantially reduced in the future.

As a manufacturing and exporting nation, we cannot afford to ignore the significance of this potential challenge from Russia, and within the next few years must take the necessary measures to meet it. We should provide every encouragement to ensure that the most promising young men and women in the country are attracted to the engineering and allied professions, and, at the same time, should intensify our efforts to improve facilities for technological and scientific education, in order that the recruits to our industries, and—even more important—our research establishments, may be adequately trained. In addition, by research and development, we must not only improve existing products and introduce new designs, but ensure that the most effective production techniques and equipment are employed for their manufacture.

Personal

MR. JOHN DODD, 58 Avon Crescent, Stratford-on-Avon, has been appointed Midlands technical representative for The Sheffield Twist Drill & Steel Co., Ltd., for the demonstration and sale of the Dormer drill sharpening machine.

MAJOR-GENERAL E. P. READMAN, C.B.E., T.D., who recently retired from English Steel Corporation, Ltd., has joined the boards of Darwins Group, Ltd., and Andrews Toledo, Ltd., also of The Sheffield Forge & Rolling Mills Co., Ltd., and the other subsidiary companies of the Group.

MR. GEORGE P. TINKER (chairman), MR. J. C. HOWARD (managing director), MR. F. S. LEIGH (assistant managing director), MR. D. L. CAMPBELL, MR. J. H. CROSSLEY, MR. P. F. HANCOCK, MR. J. A. MONKS, and MR. T. G. TANNER, comprise the board of the newly formed company Birlec-Efco (Melting), Ltd. The secretary of the company is MR. J. C. MANTELL, and the offices are at Westgate, Aldridge, Staffs.



Mr. George P. Tinker



Mr. W. J. Cleverly

MR. W. J. CLEVERLY has been appointed sales manager of the Bonded Abrasives Division of The Carborundum Co., Ltd., Trafford Park, Manchester, 17, in succession to Mr. F. W. Noble who has held the position for the past 10 years. Mr. Cleverly joined the company in 1939, and returned to them in 1946, after service in the R.A.F. He spent two years under training and in 1948 he was appointed sales representative for abrasive products in the Lancashire area. Subsequently, in 1952, he was transferred to the London and Home Counties area, where he spent several years representing the Bonded Abrasive Products Division.

MR. B. E. RICHMOND has relinquished his position as general factory manager of Tecalemit, Ltd., Plymouth, Devon, to enable him to concentrate his activities as managing director of Foamite, Ltd., a member company of the Tecalemit group. He has been succeeded by Mr. J. E. DRINKWATER, who was previously chief production engineer, and, latterly, deputy general factory manager. MR. H. E. JACKSON, B.Eng., has been appointed chief engineer.

Gauge and Tool Makers

A luncheon for representatives of members of the Gauge and Tool Makers' Association, Standbrook House, 2-5 Old Bond Street, W.1, was held at the Savoy Hotel, London, on November 27, and was followed by the 16th annual general meeting. In an address at the luncheon, Mr. F. W. Halliwell, C.B.E., M.I.Mech.E., M.I.Prod.E., first made reference to the prevailing trade conditions, and mentioned that he saw little evidence of early improvement. He urged members to work together within the Association to help one another as much as they could, provided that they did not "cut across free and honest competition." There was much that the Association could do to help members, and he advised them to seek such assistance.

Mr. Halliwell then went on to announce that he had decided to resign from the presidency of the Association to make way for a younger man. He had held this office for a long time, and had previously been chairman. Now, he and the other office bearers had persuaded Sir Stanley Harley, B.Sc., M.I.Mech.E., M.I.Prod.E., the deputy president, to accept the presidency. This recommendation had already been approved by the Council, who would ratify it at the first meeting of the new session, next month. Throughout his long period of office, he had received the support and assistance of a most enthusiastic body of founder-members and others who had since joined, and he asked them to extend the same support and assistance to the new president and the other officers.

He was proud, he continued, of the growth of the Association and of his connection with it. They had built an industry from a collection of firms, and the importance of that industry was now recognized, not only in Government circles but in the wider field of the national economy as a whole.

Mr. Halliwell then presented G.T.M.A. certificates to the following successful applicants: (Craftsmanship)—E. H. Brooks (Gay's [Hampton], Ltd.); J. H. Keetch (Belsize Engineering Co., Ltd.); T. S. Froggatt and E. H. Eames (B.S.A. Tools, Ltd.); C. I. Rockey, M. W. Unett, W. M. Upton, and G. W. Ward



Sir Stanley Harley

(Coventry Gauge & Tool Co., Ltd.). (Gauge and Tool Design and Draughtsmanship)—F. E. Needham (Coventry Gauge and Tool Co., Ltd.).

Mr. L. Van Moppes, chairman of the Association, proposed the health of Mr. Halliwell, the retiring president, and of Sir Stanley Harley, the president-elect.

In a short speech, Sir Stanley Harley then paid tribute to the work that Mr. Halliwell had done for the Association during a period of 16 or 17 years. He thanked the members for the way in which they had received the suggestion that he should succeed Mr. Halliwell as president, and expressed the hope that when the time came for him to retire it would be found that the incoming president had as high a regard for the outgoing president as he personally had for Mr. Halliwell.

Books Received

DIE TRAGFAHIGKEIT DER ZAHNRADER. By A. K. Thomas, Carl Hanser Verlag, Kolbergerstrasse, 22, München 27. 182 pp. [Price 14-80 D.M.]

Concerned with "the load-carrying capacity of toothed gears," this book is divided into four sections. The first is devoted to spur and helical gears, the second to straight and curved tooth bevel gears, the third to worm gears, and the fourth to spiral gears. Tooth and bearing loading aspects are considered, and numerous worked-out examples are included.

AIDS TO WORKSHOP PRACTICE. By C. T. Bower, A.M.I.Prod.E. Odhams Press, Ltd., Long Acre, London, W.C.2. 192 pp. [Price 18s. 0d. net.]

A collection of hints, tips and practical ideas is presented in this book and there are descriptions of various devices that have proved of practical assistance in the working of metals and other materials. These devices facilitate assembly, drilling, sawing, lathe-work, painting, sanding, tapping, and other workshop operations. They are fully illustrated by means of clear diagrams and photographs.

PRODUCTION PLANNING AND INVENTORY CONTROL. By J. F. Magee, McGraw-Hill Publishing Co., Ltd., 95 Farringdon Street, London, E.C.4. 333 pp. [Price 58s. 0d. net.]

There is no doubt that efficient and systematic stores control and material purchasing are essential for competitive production. Without them, real production planning becomes impossible. The author of this book has analysed all the various aspects of planning and stores control. Starting with the objective problems and systems of inventory control, he discusses the functions of the various stock points, the cost factors, and the method of determining the size of a manufactured or purchased lot. Next, the influence of uncertainty, forecasting, control of production levels, and the scheduling of production are considered. Finally, various problems of distribution, and the design of the production-control system are discussed. Appendixes occupying some 30 pages give the derivations of economical order-quantity formulae, rules for production control, and the techniques of seasonal planning.

Coming Events

INSTITUTION OF ELECTRICAL ENGINEERS. *East Midland Centre.* December 12, at 7.15 p.m., at the Technical College, The Newarke, Leicester; paper on "The National-Elliott 405 Computer and Its Application to Production Procedures," by H. A. Mathews.

INSTITUTION OF PRODUCTION ENGINEERS. *Sheffield Section.* December 8, at 7.15 p.m., at the Grand Hotel, Sheffield; lecture on "Argon Arc Welding of Corrosion and Heat Resisting Steels," by Dr. J. A. McWilliam. *Leeds Section.* December 8, at 7 p.m., at the Hotel Metropole, Leeds; lecture on "A Modern Foundry for the Manufacture of Small Steel Castings by New Moulding Techniques," by J. H. Osborn. *London Graduate Section.* December 9, at 7.15 p.m., at the Institution, 10 Chesterfield Street, W.1; lecture on "Investment Castings by Centrifugal Methods," by I. L. Gwynn. *Luton Section.* December 9, at 7.30 p.m., in the Pink Room, W. H. Allen Sons & Co., Ltd., Bedford; lecture on "Nuclear Power and Its Effects on the Production Engineer," by I. Munro, B.Sc. *South Essex Section.* December 10, at 7.30 p.m., at the Social Centre of the Hoffmann Manufacturing Co., Ltd., New Street, Chelmsford; lecture on "Ergonomics in Industry," by Dr. W. F. Floyd. *Midlands Region.* December 10, at 7 p.m., at the Wolverhampton and Staffordshire College of Technology, Wulfruna Street, Wolverhampton; lecture on "Reduction in Costs through the Use of Transfer Presses," by L. Schuler. *Doncaster Section.* December 9, at 7 p.m. in the Technical College Hall, Doncaster; lecture on "Manufacture of Ball and Roller Bearings." *Halifax and Huddersfield Section.* December 9, at 7.30 p.m., at the Percival Whitley Technical College, Francis Street, Halifax; lecture on "Current Experimental Work with Sintered Oxide as a Cutting Tool," by R. N. Cook. *Northern Ireland Section.* December 11, at 7.30 p.m., at the Kensington Hotel, College Square East, Belfast; lecture on "The Background to Incentives and Industrial Motivation," by E. W. Hughes, M.A., B.Sc. *Liverpool Section.* December 10, at 7.30 p.m., at the Liverpool Technical Libraries, William Brown Street, Liverpool, 3; lecture on "Materials Handling—A Challenge to British Industries," by A. G. Hayek. *Southampton Section.* December 10, at 7.30 p.m., in the Ballroom, King's Arms Hotel, Christchurch; lecture on "The Electronic Control of Machine Tools for Aircraft Production," by H. Ogden.

INSTITUTION OF MECHANICAL ENGINEERS. *Southern Graduates' Section.* December 10, at 3.30 p.m., in Cockcroft Hall, Harwell; paper on "High-speed Photography as an Aid to Engineers," by A. Payne. *North Eastern A.D. Centre.* December 17, at 7.30 p.m., in the New Lecture Theatre, The University, Leeds; paper on "Air Suspension for Road Vehicles," by J. H. Sainsbury.

THE INSTITUTE OF METAL FINISHING. *London Branch.* December 15, at 6.15 p.m., at the Northampton College of Advanced Technology, St. John Street, E.C.1; paper on "Trends in Polishing," by J. P. Dewar.

MANCHESTER ASSOCIATION OF ENGINEERS. December 9, at 6.45 p.m., at the Engineers' Club, Albert Square, Manchester, 2; lecture on "Application of Hydraulics

in Industry," by J. R. Fawcett, B.Sc. Joint meeting with the Incorporated Plant Engineers (Manchester Branch).

INSTITUTION OF ENGINEERING DESIGNERS. *North East Branch.* December 8, at 7.15 p.m., in the Northern Architectural Association Hall, 6 Higham Place, Newcastle-upon-Tyne, 1; paper on "Hydraulic Machinery," by D. C. Jeffrey and E. Rutherford.

INCORPORATED PLANT ENGINEERS. *Glasgow Branch.* December 11, at 7.15 p.m., at the Scottish Building Centre, 425-427 Sauchiehall Street, Glasgow; paper on "Can Formal Management Techniques Benefit the Work of the Plant Engineer?" by F. R. Curry.

Scrap Metals

↑LONDON.—Prices per ton for non-ferrous scrap metals free from iron are as follows:—clean copper wire, untinned and free from lead and solder, £185; clean heavy copper, untinned and free from lead and solder, £175; copper wire, No. 2, £172; clean light copper, £162; braziers copper, £142; gunmetal, £146; brass, mixed, £102; lead, net, £59; zinc, £35; cast aluminium, £96; old rolled aluminium, £114; battery lead, £31; unsweated brass radiators, £92; hollow pewter, £505; black pewter, £375.

MIDLANDS.—Although trading, in general, is still restricted, there are signs of some improvement in the disposal of scrap. No. 4 bundles are moving steadily and occasional permit loading labels are issued for heavy steel to specifications No. 1 and 2. Heavy shovelling scrap (No. 3) cannot be placed locally, and large tonnages are being held by merchants. Various export orders are being executed, and although prices f.o.r. are not very attractive, it has been possible to reduce stocks from overburdened yards.

Light steel scrap is in demand for pressing, but, so far, no interest is being shown in light iron scrap. Chipped steel turnings are being consigned to blast furnaces in the Sheffield area, but supply still far exceeds demand and it is necessary for Midland merchants to stock the surplus material. The market for borings is spasmodic, but, fortunately, as one outlet closes another opens and stocking of such scrap has so far been avoided.

Prices of the lighter grades of cast iron have improved, and trading in all grades is keener.

More outlets for short steel are needed if all the material forthcoming is to be cleared, but limited tonnages are being placed at various prices.

Disposal of compressed destructor bundles is difficult and prices have eased considerably.

Current maximum control prices, delivered consumers' works, are now: *Heavy steel No. 1, 217s. 6d.; *heavy steel No. 2, 196s.; *heavy steel No. 4, 207s. 6d.; *heavy steel No. 5, 195s. 6d.; light iron No. 8, 149s.; short turnings No. 9 (free from alloy), 167s. 3d.; light steel No. 11, 164s. 3d.; bushy turnings, 117s.; short alloy turnings, 160s. 9d.; short steel No. 2, 233s. 3d.; machinery cast, 233s.

Prices may be increased up to 2s. 6d. per ton according to quantities tendered over a given period.

* For use by Round Oak Steelworks, Brierley Hill, increase by 1s. 6d. per ton.

† George Cohen, Sons & Co., Ltd., 600 Commercial Road, E.14.

‡ Subject to market fluctuations.

British Machine Tools for Leipzig

Several leading British machine tool firms will exhibit, next March, in the machine tool section of the Leipzig Spring Fair, on a collective stand which is being organized by The Machine Tool Trades Association, Brettenham House, Lancaster Place, London, W.C.2. It is pointed out that this will be the first large-scale promotional effort of the United Kingdom machine tool industry behind the Iron Curtain.

Industrial Notes

DUNLOP FOOTWEAR, LTD., Speke, Liverpool, are now marketing Safety-master boots with steel toe caps tested to B.S. Specification A.1.

THE SOCIETY OF ENGINEERS will move to Abbey House, Victoria Street, Westminster, London, S.W.1, on December 15. The telephone number (Abbey 7244) will not be changed.

THE BRITISH THOMSON-HOUSTON CO., LTD., inform us that their London district office is now at 33 Grosvenor Place, S.W.1 (telephone number, Belgravia 7011). The British Thomson-Houston Export Co. is also located at this address.

THE TIN RESEARCH INSTITUTE, Fraser Road, Greenford, Middlesex.—The Autumn, 1958, issue of *Tin and Its Uses* includes articles on: tin-nickel plating for watch parts and drawing instruments; improving the finish of tinned wares; continuous casting of solder; and the tinning of wire for soldering.

THE PHYSICAL SOCIETY EXHIBITION in 1959 will be held, from January 19 to 22, at the Royal Horticultural Society's Old and New Halls, Westminster, London, S.W.1. Full particulars can be obtained from the Exhibition Secretary, 1 Lowther Gardens, Prince Consort Road, London, S.W.7.

BIRLEC, LTD., Erdington, Birmingham, 24, recently despatched a consignment of heat treatment equipment to Machinimport, Moscow. This equipment included a standard 24-in. mesh belt conveyor furnace for heat treating steel components, a horizontal batch furnace for tool-room heat treatment, and a generator for maintaining protective atmosphere within the conveyor furnace.

THE ENGINEERING, MARINE, WELDING, AND NUCLEAR ENERGY EXHIBITION will be held next year at Olympia, London, from April 16 to 30. It will occupy three halls and there will be more than 500 exhibitors with total stand space exceeding 250,000 sq. ft. Full particulars can be obtained from the organizers, F. W. Bridges & Sons, Ltd., Grand Buildings, Trafalgar Square, London, W.C.2.

THOS. C. WILD (MACHINERY), LTD., Vulcan Works, Coleridge Road, Sheffield, 9, are at present holding an exhibition of machine tools. Machines which are being demonstrated include the latest Cawi twist drill point grinder, Harrison 8- and 5½-in. centre copy-turning lathes, Graham & Normanton heavy-duty lathes, Mitchell centre lathes, Invicta-Hydetsco opsided planers, Ajax radial drilling machines, and Victoria milling machines.

THE WHITEHILL ENGINEERING CO., LTD., have recently moved from their Hillington factories to a factory on Craigton Industrial Estate, Glasgow, previously occupied by Rolls-Royce, Ltd. The managing director of the company, Mr. A. J. C. H. Weissenbruch, and the recently-appointed general manager, Mr. J. Rodger, who was previously superintendent mechanical engineer with Massey Ferguson, Ltd., have made arrangements to ensure a substantial increase in the output of press tools, jigs, fixtures and special-purpose machines. To this end, new machine tools of larger capacity have been installed, and particular attention has been paid to inspection equipment. We are informed that since the activities were transferred to the Craigton factory, an increased demand has already been experienced, both in the design and production departments.

Corrections

In the advertisement for Incandescent Heat Co., Ltd., Cornwall Road, Birmingham, 40, which appears on page 12 of this issue of MACHINERY, wrong wording has inadvertently been included and does not relate to the illustration. This advertisement, in its correct form, will be published next week.

In MACHINERY, 93/1266—26/11/58 it was inadvertently stated that Morrison, Marshall & Hill, Ltd., were the principals of Rushworth & Co. (Sowerby Bridge), Ltd. We express our apologies for this error. It is, of course, Rushworth & Co. (Sowerby Bridge), Ltd., who are the principals.

The Price of a Subscription to MACHINERY is 52 Shillings per annum, post free, to any part of the world.

Subscribers are not bound for any definite period of subscription. We send MACHINERY, post free, each week until told to stop. Subscribers can pay yearly, half-yearly, or quarterly, pro rata. (Cash with order)

To MACHINERY, National House, 21 West Street, Brighton 1.

Please send me/us MACHINERY every week until I/we tell you to stop, for which I/we enclose remittance of 52 Shillings per annum or pro rata

Name

Address

.....

* Position

* Firm

* For our mailing records only.

3/12/58

BRITISH MACHINE TOOL Exports of New Machine Tools

Countries	Vertical Boring Machines		Other Boring Machines		Drilling Machines		Grinding, Lapping and Honing Machines		Automatic Lathes		Capstan and Turret Lathes		Other Lathes		Screwing Machines	
	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £
<i>Commonwealth</i>																
South Africa	—	—	11 (1)	308	112 (34)	2,560	942 (48)	27,900	53 (1)	2,444	—	—	503 (23)	13,501	15 (1)	580
India	222 (1)	6,750	78 (2)	5,649	567 (16)	22,487	1,605 (28)	56,779	—	—	863 (19)	41,358	487 (12)	15,447	26 (1)	3,270
Pakistan	—	—	—	—	20 (4)	390	34 (28)	2,033	—	—	—	—	89 (1)	2,099	—	—
Australia	1,552 (1)	30,739	245 (2)	9,996	410 (13)	8,760	254 (40)	13,788	377 (2)	14,687	277 (12)	9,789	906 (76)	31,795	29 (4)	989
New Zealand	—	—	—	—	15 (10)	478	40 (9)	710	—	—	—	—	312 (10)	7,277	—	—
Canada	—	—	—	—	70 (9)	1,716	292 (19)	13,944	—	—	85 (2)	3,685	608 (27)	21,157	—	—
Miscellaneous	220 (1)	3,000	190 (3)	3,436	162 (61)	4,324	226 (36)	10,320	—	—	198 (2)	8,156	559 (23)	14,777	19 (2)	829
<i>Foreign</i>																
Soviet Union	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Sweden	250 (1)	4,980	—	—	83 (1)	1,186	52 (2)	5,135	—	—	190 (13)	6,658	—	—	—	—
Norway	—	—	—	—	—	—	—	—	—	—	—	—	27 (8)	1,109	—	—
Denmark	—	—	—	—	38 (1)	815	—	—	—	—	69 (2)	3,383	23 (2)	792	—	—
Western Germany	—	—	—	—	4 (1)	235	1 (1)	34	—	—	—	—	15 (1)	1,336	—	—
Netherlands	—	—	260 (1)	7,130	301 (8)	121	4,523 (5)	184 (2)	5,647	—	—	—	142 (3)	4,329	—	—
Belgium	—	—	—	—	8 (12)	316	6 (2)	263	—	—	187 (2)	7,958	6 (1)	193	—	—
France	—	—	88 (1)	6,198	32 (2)	1,107	52 (2)	4,280	914 (9)	43,224	—	—	56 (21)	2,531	—	—
Switzerland	—	—	—	—	54 (2)	1,307	2 (1)	70	—	—	—	—	—	—	—	—
Spain	—	—	—	—	140 (6)	7,279	387 (8)	17,709	167 (1)	9,617	—	—	—	—	—	—
Italy	593 (1)	16,700	—	—	—	—	415 (11)	24,156	796 (4)	33,057	—	—	—	—	20 (3)	1,730
U.S. America	166 (1)	3,986	—	—	308 (3)	6,414	138 (9)	6,877	75 (2)	2,026	—	—	658 (17)	21,506	—	—
Miscellaneous	—	—	5 (3)	480	452 (59)	10,541	548 (24)	31,182	437 (4)	25,348	482 (12)	32,530	725 (62)	28,369	15 (1)	330
Total	3,003 (6)	66,155	877 (13)	33,197	2,486 (242)	70,216	5,115 (245)	219,703	3,003 (25)	136,050	2,351 (64)	113,517	5,116 (287)	166,218	124 (12)	7,728
<i>Amendments to previous accounts</i>																
Commonwealth	—	—	—	—	+7 (-30)	+250	+528 (+2)	+14,650	—	—	—	—	+126 (-6)	+3,158	—	—
Foreign	—	—	—	—	+41 (+8)	+255	+1 (+1)	+542	-185 (-1)	-4,195	+5 (-)	+250	+16 (+2)	+105	—	—

Total exports of reconditioned machine tools: Quantity: No., 166; weight, 11,049 cwt.; value, £67,622

Total exports of imported machine tools: Quantity: weight, 776 cwt.; value, £36,996.

Imports of New Machine Tools

Country of Origin	Boring Machines		Drilling Machines		Gear-cutting Machines		Grinding, Lapping and Honing Machines		Automatic Lathes	
	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £	Quantity, Cwt. and No.	Value £
Western Germany	201 (2)	10,181	—	—	74 (3)	9,604	680 (27)	42,799	1,709 (15)	74,578
Belgium	66 (2)	4,434	—	—	—	—	—	—	—	—
France	—	—	—	—	—	—	71 (2)	4,300	146 (2)	8,093
Switzerland	267 (4)	21,245	1 (1)	180	22 (3)	4,146	175 (7)	16,885	841 (19)	54,428
U.S. America	—	—	30 (6)	3,691	277 (1)	20,389	705 (6)	64,448	59 (1)	4,930
Miscellaneous	1,505 (4)	27,147	220 (7)	2,548	—	—	533 (18)	30,223	252 (6)	7,337
Total	2,039 (12)	63,007	251 (14)	6,419	373 (7)	34,139	2,164 (60)	158,655	3,007 (43)	149,366
<i>Amendments to previous accounts</i>										
Western Germany	—	-69	—	—	—	-16	—	—	—	—
Switzerland	—	—	—	—	—	—	—	—	—	—
U.S. America	—	—	—	—	—	—	—	-38	—	—
Miscellaneous	—	—	—	—	—	—	-1 (-2)	-152	—	—

Total imports of reconditioned machine tools: Quantity: No. 18; weight, 1,105 cwt.; value, £29,358.

Machine Tool Share Market

Stock markets, which had been very firm and active under the influence of a reduction in Bank Rate from $4\frac{1}{2}$ to 4 per cent, became depressed following a sharp setback in prices on Wall Street, and the period under review closed on a subdued note, with declines in many sections.

In the gilt-edged section, after some strength had been displayed, a reactionary tendency developed, but the tone hardened again towards the finish.

Early cheerfulness in commercial and industrial share markets was followed by more subdued conditions, and most price changes were to lower levels, on balance.

Among machine tool issues Butler Machine Tool advanced 2s. to 10s.; Coventry Gauge & Tool, 1s. to 18s.; Clarkson Engineers, 3d. to 15s. 6d.; Greenwood & Batley, 2s. 6d. to 55s.; Kayser Ellison, 6d. to 47s.; Sheffield Twist Drill, 6d. to 14s.; Kitchen & Wade, 2s. to 11s. 3d.; F. Pratt, 1s. to 23s. 9d.; and Thos. W. Ward, 1s. 1½d. to 81s. 10½d. On the other hand, Arnott & Harrison lost 6d. at 15s.; Asquith Machine Tool, 6d. at 23s. 9d.; Broom & Wade, 6d. at 11s. 6d.; Churchill Machine Tool, 6d. at 17s. 9d.; British Oxygen, 3s. at 42s.; Chas. Churchill, 1½d. at 6s. 7½d.; Geo. Cohen, 3d. at 10s. 3d.; B. Elliott, 3d. at 2s. 9d.; Newall Engineering, 3d. at 4s. 6d.; and Craven Bros. (Manchester), 4½d. at 8s.

BUTLER MACHINE TOOL CO., LTD. Dividend $17\frac{1}{2}$ per cent for the year ended September 30, last.

CHARLES CHURCHILL & CO., LTD. Interim dividend $7\frac{1}{2}$ per cent (sale).

JOHN HARPER & CO., LTD. Interim dividend 10 per cent (same).

JOHN HOLROYD & CO., LTD. Dividend 15 per cent for the year to September 30, last (same).

KENDALL & GENT, LTD. Final dividend 10 per cent, plus a bonus of 5 per cent, making, with the interim, a total distribution of 20 per cent (same).

SHEFFIELD TWIST DRILL & STEEL CO., LTD. Interim dividend 6½ per cent.

THE MANCHESTER COLLEGE OF SCIENCE AND TECHNOLOGY, Manchester, 1, will hold a course of eight lectures on the "Presentation of Technical Information" on Tuesdays and Wednesdays (7.0 to 9.0 p.m.), starting on February 17. Application forms can be obtained from The Registrar, at the above address. There will also be a course of six lectures on "Circuit Elements and Their Use in Electrical Measurements" on Wednesdays (7.0 to 9.0 p.m.), starting on January 14.

COMPANY		Denom.	Middle Price	COMPANY		Denom.	Middle Price	
Abwood Machine Tools, Ltd.	Ord.	1/-	9d.	Harper (John) & Co., Ltd.	Ord.	5/-	16/6	
Armstrongs, Stevens & Son, Ltd.	Ord.	5/-	8/9	"	4½% Red.	£1	13/-	
Allen (Edgar) & Co., Ltd.	Ord.	£1	38/-	"	Cum. Prf.			
"	5% Prf.	£1	15/6*	Herbert (Alfred), Ltd.	Ord.	£1	37/6	
Arnott & Harrison, Ltd.	Ord.	4/-	15/-	Holroyd (John) & Co. Ltd.	"A" Ord.	5/-	13/6xd	
Asquith Machine Tool Corp., Ltd.	Ord.	5/-	23/9	"	"B" Ord.	5/-	13/6xd	
"	6% Cum. Prf.	£1	18/6xd	Jones (A. A.) & Shipman, Ltd.	Ord.	5/-	21/-	
Birmingham Small Arms Co., Ltd.	Ord.	£1	35/-xd	"	7% Cum. Prf.	5/-	5/-	
"	5% Cum.	£1	15/6	Kaysers, Ellison & Co., Ltd.	Ord.	£1	47/-	
"	"A" Prf.	£1	15/6	"	6% Cum. Prf.	£1	18/3	
"	6% Cum.	£1	18/-	Kendall & Gent, Ltd.	Ord.	5/-	7/-	
"	"B" Prf.	£1	88½	Kerry's (Gt. Britain), Ltd.	Ord.	5/-	6/10½	
"	4% 1st Mort.	Stk.	88½	Kitchen & Wade, Ltd.	Ord.	4/-	11/3	
British Oxygen Co., Ltd.	Ord.	£1	42/-	Martin Bros. (Machinery), Ltd.	Ord.	2/-	1/6	
"	6½% Cum. Prf.	£1	21/9xd	Massey, B. & S., Ltd.	Ord.	5/-	9/9	
Brooke Tool Manufacturing Co., Ltd.	Ord.	5/-	4/-	Modern Engineering Machine Tools Ltd.	Ord.	5/-	10/9	
Broom & Wade, Ltd.	Ord.	5/-	11/6	Newall Engineering Co., Ltd.	Ord.	2/-	4/6	
"	6% Cum. Prf.	£1	17/9	Newman Industries, Ltd.	Ord.	2/-	2/9	
Brown (David) Corporation Ltd.	5½% Cum. Prf.	£1	15/6xd	"	6% Prf. Ord.	5/-	5/6	
Buck & Hickman, Ltd.	6% Cum. Prf.	£1	17/9	Noble & Lund, Ltd.	Ord.	2/-	3/9	
Butler Machine Tools Co., Ltd.	Ord.	5/-	10/-	Osborn (Samuel) & Co., Ltd.	Ord.	5/-	20/-xd	
C.V.A. Jigs, Moulds & Tools, Ltd.	5% Cum. Prf.	£1	13/9	"	5½% Cum. Prf.	£1	26/-	
"	3½% Red.	£1	11/3	Pratt (F.) & Co., Ltd.	Ord.	5/-	23/9	
Churchill (Charles) & Co., Ltd.	Cum. Prf.			Scottish Machine Tool Corporation, Ltd.	Ord.	4/-	5/3xd	
"	Ord.	2/-	6/7½	Shardlow (Ambrose) & Co., Ltd.	Ord.	£1	44/6	
Churchill Machine Tool Co., Ltd.	6% Cum. Prf.	£1	26/4½	"	Ord.	5/-	14/6	
"	Ord.	5/-	17/9	Shaw (John) & Sons, Wolverhampton, Ltd.	Ord.	4/-	14/-xd	
"	6% Cum. Prf.	£1	18/3	Sheffield Twist Drill & Steel Co., Ltd.	Ord.	5% Cum. Prf.	£1	15/-
Clarkson (Engrs.), Ltd.	Ord.	5/-	15/6	"	"B" Ord.	5/-	7/6	
Cohen (George), Son & Co., Ltd.	Ord.	5/-	10/3	Stedall & Co., Ltd.	"			
"	4½% Cum. Prf.	£1	14/6	"	voting Ord.	10/-	22/6	
Coventry Gauge & Tool Co., Ltd.	Ord.	10/-	18/-	"	Ord.	5/-	7/6	
"	5% Cum.	£1	16/3	"	4½% Deb.	Stk.	82/-	
"	Red. Prf.			"	1961-1977			
Coventry Machine Tool Works, Ltd.	Ord.	4/-	8/6	Wadkin, Ltd.	Ord.	10/-	18/9	
Craven Bros. (Manchester), Ltd.	Ord.	5/-	8/-	Ward (Thos. W.), Ltd.	Ord.	£1	81/10½	
Elliott (B.) & Co., Ltd.	Ord.	1/-	2/9	"	5% Cum.	£1	16/6	
"	4½% Red.	£1	13/9	"	1st Prf.			
"	Cum. Prf.			"	5% Cum.	£1	24/-	
Expert Tool & Case Hardening Co., Ltd.	Ord.	2/-	1/3	"	2nd Prf.			
Firth Brown Tools, Ltd.	4% Cum. Prf.	£1	12/6	Willson Lathes, Ltd.	Ord.	1/-	2/4½	
Greenwood & Batley, Ltd.	Ord.	£1	55/-					


The Middle Prices given in the list are in several cases nominal prices only and not actual dealing prices. Every effort is made to ensure accuracy, but no liability can be accepted for any error.

* Sheffield price. † Birmingham price.



Have Ransome and Marles been associated with any of the big developments in British industry?

We don't hit the headlines — but we often help to make headline news possible. Since the war we have carried out research into design, materials, lubrication and production for a number of important projects. One of



these is nuclear power generation. From the early days of Calder Hall our technicians have been tackling fresh problems as new and more powerful reactors are designed.

Are there any other interesting projects?

Yes, several. Britain has been achieving a world-wide success with her aircraft engines. Two notable users of **RAM** Bearings are Armstrong-Siddeley Motors and Bristol Aero Engines. The Proteus engines of the latest Bristol Britannia are of course fitted with **RAM** Bearings.

Then again "automation" is a popular word these days. We at **RAM** are becoming increasingly "automatic" in many of our processes in shops and offices. We also supply the bearings for the latest electronic machines. Our customers include Powers Samas, Elliott Brothers, IBM and British Tabulating Machines — just another example of the role played by **RAM** in all fields of industrial development.



RANSOME & MARLES BEARING CO LTD • NEWARK-ON-TRENT • ENGLAND

TELEPHONE • NEWARK 456 AND TELEX 37-306

When answering advertisements kindly mention MACHINERY.

M

**Direct constant & immediate
readings accurate to .00001**

MAGNA-GAGE **ELECTRONIC** **COMPARATOR**



A multi-purpose instrument, which can be used as very high precision laboratory equipment, and yet is capable of providing these same exacting conditions in production. It provides for very fast routine inspection and lends itself to multiple and continuous gauging, automatic sorting, remote control and inspection, and machine control.

For very fast routine or repetition inspection by non-technicians, a colour light signalling system is incorporated to supplant the scale readings.

The standard equipment for routine inspection

Magnification: 400 and 4000 approximately.
Ranges: .005-.005 in. Each division .0001 in. .0005-.0005 in. Each division .0001 in. .12-.12 mm. Each division .005 mm. .012-.012 mm. Each division .0005 mm. **Accuracy:** .0001 in. (.0025 mm.) on coarse ranges. .00001 in. (.00025 mm.) on fine ranges. **Consistency of reading:** $\pm .000001$ in. ($\pm .000025$ mm.) with standard probe. $\pm .000002$ in. ($\pm .00005$ mm.) with extended probe. **Temperature coefficient of probe:** Zero shift lies within

$\pm .0000005$ in./deg. F. ($\pm .00002$ mm./deg. C.). **Operating pressure:** Varies from 1-2 oz. (28-56 gm.). **Zero drift of amplifier:** After 2 minutes' warm-up, .00002 in. (.0005 mm.). After 10 minutes' warm-up, .00001 in. (.00025 mm.). **Zero stability with mains change:** Undetectable for voltage changes of $\pm 15\%$ and frequency changes 40-60 c/s. **Reading stability with mains change:** No change for frequency 40-60 c/s. $\pm 1\%$ of reading for $\pm 15\%$ voltage change. **Electrical outputs:** Current: ± 0.5 mA. full-scale on

any range. Maximum load 4700 ohms. Voltage: ± 2.5 volts (approximately) full-scale on any range. Output resistance 4700 ohms. **Mains supply:** 100-115, 200-250 volts, single-phase, 40-60 c/s. **Power consumption:** 20 watts. **Probe dimensions and weight:** Diameter: .875 \pm .0005 in. (22.22 \pm .01 mm.). Overall length: 3.5 in. (9 cm.). Weight with cable and plug: 4 oz. (112 gm.). **Amplifier dimensions and weight:** Size: 8 x 8 x 8 in. (20 x 20 x 20 cm.) approximately. Weight: 8 $\frac{1}{2}$ lb. (4 Kg.).

SOUTHERN INSTRUMENTS

AN ADVERTISEMENT OF THE OSCILLOGRAPH GROUP OF SOUTHERN INSTRUMENTS LIMITED CAMBERLEY SURREY TELEPHONE: CAMBERLEY 3401

F558 36 0

When answering advertisements kindly mention MACHINERY.


STANDARD MOTOR CO. LTD.

USE WAKEFIELD-DICK


ILOQUENCH OILS

Wakefield-Dick pioneer research into oils used to enhance the mechanical properties of steels. The Standard Motor Company knows from experience that the stability and efficiency of the Wakefield-Dick range of 'Iloquench' Quenching and Tempering oils make them an essential part of heat treatment processing.

'ILOQUENCH' in use at the heat treatment plant of Standard's Banner Lane factory—one of the most modern in the country.




**WAKEFIELD-DICK
INDUSTRIAL OILS
LIMITED**



67 GROSVENOR STREET, LONDON, W.1. A MEMBER OF THE WORLD-WIDE WAKEFIELD CASTROL ORGANISATION

When answering advertisements kindly mention MACHINERY.

Automation at Vauxhall Motors



As in the many other fields of industrial production where continuous processes are called for **VICKERS-DETROIT** Oil Hydraulics are specified by the largest organisations to reduce cost, improve uniformity and provide flexibility—advantages which are at the service of every industrialist, whatever the size of plant.

*At Vauxhall's spectacular new plant automation is brought to the highest pitch of efficiency yet achieved. Pictured is the Asquith 18-station Drilling Transfer Machine used for machining all Vauxhall Victor, Velox and Cresta cylinder heads. With a total of 273 spindles it absorbs 269 H.P., cycling at 70 pieces/hr. performing all drilling, reaming, countersinking, boring and tapping operations. The sequence of all the fixtures, transfer bar, tilting and turning stations is actuated by **VICKERS-DETROIT** Oil Hydraulic Equipment.*

For further details please write for publication 1/39




by **STEIN ATKINSON VICKERS HYDRAULICS LIMITED**

S.A.V. HYDRAULICS

197 KNIGHTSBRIDGE, LONDON, S.W.7

WHAT'S NEW IN SLIDING BED LATHES?



For the answer to that, ask STANLEY. STANLEY have recently re-designed their 10½ inch Sliding Bed Lathe to incorporate several improvements.

The new Stanley is heavier—has greater horse-power—a wider bed—totally enclosed, built-in electrics. It can be supplied with a back turning rest to turn large diameters the full length of the open gap.

The Stanley Sliding Bed Lathe is really two lathes in one. It can be used as a standard centre lathe and also for large diameter, large width jobs which would otherwise call for a special machine.

Stanley lathes have been serving satisfied users all over the world for more than twenty years. The new model is designed and built to carry on this fine tradition.

All you want to know about the improved Stanley Sliding Bed Lathe is contained in a new catalogue—sent on request.

HIGHLY SATISFIED USERS OF STANLEY LATHES

include: *Mullard Ltd. Bryant Symons & Co. Ltd.*
Laurence, Scott & Electromotors Ltd. Rosser & Russell Ltd.
Prince of Wales Dry Dock Co. (Swansea) Ltd. Hobbs Transmission Ltd.

Stanley

THE STANLEY MACHINE TOOL CO. LTD.

NEW BANK · HALIFAX · YORKSHIRE

Telephone: Halifax 67233 Telegrams: "Makers" Halifax

When answering advertisements kindly mention MACHINERY.



Specialists

in the manufacture of

JIGS · PRESS TOOLS · MOULDS & DIES · GAUGES · MULTIPLE

DRILLING HEADS · **MODEL MARK** METAL MARKING EQUIPMENT

and all forms of tooling for high production.

Illustrated brochure on application.

AXMINSTER DEVON ENGLAND

Phone Axminster 3114/5

NOW is the time
to purchase your
ROYAL 10" stroke
shaping machine

from:—


THE REALM ENGINEERING WORKS LIMITED
267 WHITEHORSE LANE . SOUTH NORWOOD . LONDON, S.E.25
TELEPHONE: LIVINGSTONE 1087/8,9

When answering advertisements kindly mention MACHINERY.

Useful little book

... for the steel buyer,
the tool room manager,
the production engineer —
in fact anyone who has
to use or order tool and
high speed steels.
"Sanderson Steels"
describes our standard
range and illustrates
typical applications.

Write for a copy




SANDERSON SHOCK RESISTANT

GRADE	TYPE	FEATURES	USES	TEMPERATURE	STRENGTH	WEAR	TOOTH	TOOTH	TOOTH
SA 100	Tool Steels	Extremely tough and strong with low wear.	Used in dies, punches, and other tools where shock resistance is required.	1000-1200 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.
SA 100 S	Tool Steels	Heavy duty tool steel with high shock resistance.	Used in dies, punches, and other tools where shock resistance is required.	1000-1200 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.
SA 100 S	Tool Steels	Heavy duty tool steel with high shock resistance.	Used in dies, punches, and other tools where shock resistance is required.	1000-1200 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.
SA 100 S	Tool Steels	Heavy duty tool steel with high shock resistance.	Used in dies, punches, and other tools where shock resistance is required.	1000-1200 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.
SA 100 S	Tool Steels	Heavy duty tool steel with high shock resistance.	Used in dies, punches, and other tools where shock resistance is required.	1000-1200 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.	100-120 C.

SANDERSON BROTHERS AND NEWBOULD LIMITED • P.O. Box 6 • Newhall Rd • Sheffield 9 • Est. 1776
Makers of tool steels • saws • files • machine knives • and high speed cutting tools

When answering advertisements kindly mention **MACHINERY**.

QUALITY CONTROL of pressure die castings



BS 1004

Maintaining the correct chemical analysis of die casting alloys, particularly with regard to impurity limits, is of paramount importance in the production of high quality die castings. Our Laboratory is equipped with one of the few *direct reading spectrographs* in use in this country.

As a result the requirements of the B.S.I. Certification Scheme for zinc alloy die castings are far exceeded. Every melt is analysed and the holding furnace of every machine is checked for impurities at least once per shift, enabling any variance from specification to be quickly identified.

With the utmost confidence, we can therefore claim to supply castings of the highest quality. *Quotations, without obligation, from drawings, specifications or samples.*

**PRESSURE DIE CASTINGS in
ZINC, ALUMINIUM AND SOFT ALLOYS**

SPARKLETS LIMITED

DIE CASTING DIVISION
TOTTENHAM, LONDON, N.17

now
on the press
MACHINERY'S
ANNUAL
Buyers' Guide
1959
EDITION

the
standard
reference
book
for
buyers
of all
plant
equipment
and
materials
for
engineering
shops

1000 pages giving the
names, products and
trade names of over
4000 firms

***order your
copy now***

Available JANUARY 1959

**TO MACHINERY (Book Department)
National House, West St. Brighton 1**

Please send a copy of MACHINERY'S
ANNUAL BUYERS GUIDE (30th edition)
on publication. Price 12/6 post free


NAME _____

SIGNATURE _____

ADDRESS _____

DATE _____

When answering advertisements kindly mention MACHINERY.



moving only

in the best

circles—

The

QUALCUT

twist drill

*the polished drill
with the polished performance—*

look for the



QUALCUT TOOLS LIMITED

Worksop Road, Sheffield 9,

Telegrams and cables: "Qualcut" Sheffield 9. Telephone 4102314

When answering advertisements kindly mention MACHINERY.

Something New in Bending Rolls

The Genelin

HYDRAULIC


—for faster production

- * EASY ACCESSIBILITY
- * INFINITELY VARIABLE SPEED FROM 0 TO 100ft. per min. INSTANTLY REVERSIBLE
- * ALL-STEEL CONSTRUCTION

Up to the minute in design and well ahead in performance, the GENELIN with its hydraulic drive means faster, smoother and more accurate bending on all work within its capacity. Ease of control and setting have received special attention and it should be noted that the drive, infinitely variable, from 0 to 100 ft. per min., in both directions, is instantly reversible.

CAPACITY


MILD STEEL PLATE 39in. x $\frac{1}{2}$ in.
36in. x $\frac{1}{2}$ in.
12in. x $\frac{1}{2}$ in.



Sole Agents:

JOHN S. YOUNG & CO. LTD.

MARYVILLE AVENUE, GIFFNOCK, GLASGOW Phone: GIFFNOCK 1101 (6 lines) Grams: "STEDMACS", GIFFNOCK, GLASGOW



Photos by permission of Siemens Edison Swan Ltd.

a MILLION parts between regrinds!

Illustration shows our type of split die progression tool.

By form grinding our punches and dies, it is possible to produce parts in greater quantities than by normal manufacture.

For instance, the die shown produces 1,000,000 switch contacts in hard nickel between regrinds.

May we quote on your next job?

TRU TOOLS
TRUE TO FORM TRUE TO SIZE

J. P. SANDERS & CO. (TRU TOOLS) LIMITED
CAMPBELL RD., CROYDON, SURREY
TELEPHONE: THORNTON HEATH 5118

Electrical Aids in Industry


Resistance Heating - 1

In this form of heating, the heat is produced by passing an electric current through a high resistance conductor which is termed the "heating element".

The heat is transferred from the heating element to the work by convection, radiation or conduction or by a combination of any, or all, of these. When it is a question of radiation or convection, the element can be a bare wire or strip of suitable material, provided it is adequately supported on electrical insulation capable of withstanding the temperature.



When there is to be contact between the work and the element, heat being transferred to the work by conduction, the wire or strip must be surrounded by suitable insulating material and enclosed in a protective sheath.



In the majority of cases, the wire or strip forming the heating element is made of a nickel-chromium alloy which has a high electrical resistance and can be safely used in air at temperatures of up to 1050°C., or in a suitable atmosphere, of up to 1150°C. Other element materials are available for use at higher temperatures.

Electric resistance heating may profitably be put to many diverse uses; two of these are described briefly below, others will be listed in a subsequent data sheet.


Furnace Heating

Electric resistance furnaces can be divided into two main categories, batch type and continuous. In most cases, the heating elements are of nickel-chromium alloy, for furnace temperatures up to around 1050°C., but higher temperatures, up to nearly 3000°C., can be obtained by using other metals or alloys, or in some cases non-metallic elements. A protective atmosphere is desirable to prolong the life of some of these higher-temperature elements. For all temperatures, electric resistance furnaces can be constructed so that the heating process takes place in a controlled atmosphere if this is dictated by the composition or heat requirements of the work charge. In some furnaces, fans are used to circulate the air or special atmosphere over the charge, thereby giving increased heating rates



and a uniform temperature over the whole charge.


Automatic temperature control and programme control of the heating process are readily effected.



Electric furnaces are extensively used in industry, for example in the general heat treatment of metals, in the glass and ceramics industries, for brazing and sintering, and for many other applications requiring temperatures above 500°C.

Oven Heating

There are two basic forms of heat transfer used in electric resistance ovens; convection and radiation. The latter is dealt with in a separate data sheet under the heading "Infra-Red Heating".



Convection ovens may again be of the batch or continuous type. In either case, the charge is heated mainly by the movement of hot air, which is sometimes assisted, as in furnaces, by fans to give a rapid and uniform temperature rise. Ovens are normally designed for temperatures of up to about 500°C., and the heating elements are invariably of nickel-chromium or nickel-chromium-iron alloy.

Ventilation, when required, can be provided and regulated entirely to suit the heating process. Temperatures and times are readily controlled. A vacuum can be maintained in suitably designed ovens to assist in the extraction of moisture and solvent.



Convection ovens are extensively used for drying, baking and stoving operations, and for a host of other processes requiring a low or medium temperature.

For further information, get in touch with your Electricity Board or write direct to the Electrical Development Association, 2 Savoy Hill, W.C.2.

Excellent reference books on electricity and productivity (8/6 each, or 9/- post free) are available—"Induction and Dielectric Heating" is an example; "Resistance Heating" is another.

E.D.A. also have available on free loan a series of films on the industrial use of electricity. Ask for a catalogue.

6780/4




HACKSAWING MACHINES

THOUSANDS OF ENGINEERS
CANNOT BE WRONG WHEN THEY
SPECIFY 'RAPIDOR' HACKSAWING
EQUIPMENT

USE **Rapidor**

HIGH SPEED STEEL
HACKSAW BLADES



Full particulars from:—

EDWARD G HERBERT LTD LEVENSHULME : MANCHESTER 19 : ENGLAND

Taylor

AIR CLUTCHES


(Patented)

WITH COMBINED AUTOMATIC BRAKE

*— FOR SMOOTH, POSITIVE,
CUSHIONED POWER*

These clutches not only ensure full power with smooth, shock-free engagement at higher speeds, but also contribute to faster production and better all round performance on all types of Presses, Forging Machines, Press Brakes, Shears, etc. Synchronised, powerful, quick acting braking ensures positive safe stop, which means quick and accurate control with increased safety for operators and tool setters.

A standard range of sizes is available and details will be sent on request.



TAYLOR INDUSTRIAL CLUTCHES TROWS UPPER WORKS, CASTLETON, LANCs.

When answering advertisements kindly mention MACHINERY.


SUPER HIGH SPEED DRILLING **DEMANDS** **CORONA**

**SINGLE OR MULTIPLE SPINDLE
MODELS TO SUIT EVERY NEED**

- ▶ **ADJUSTABLE HEADS**
- ▶ **$\frac{5}{16}$ in. CAPACITY DRILL CHUCK**
- ▶ **8 SPEEDS THROUGH PICK-OFF GEARS**




MODEL 15 HF
BENCH MACHINE UP TO SIX SPINDLES



MODEL 15 HFHD
DOUBLE END WITH ADJUSTABLE HEADS
CAN BE SUPPLIED WITH COUPLED FEED
ALSO AVAILABLE WITH SINGLE HEAD

MODEL 15 HA
COLUMN MACHINE
WITH ADJUSTABLE TABLE
UP TO SIX SPINDLES




FREDK POLLARD & CO LTD
CORONA WORKS, LEICESTER, ENGLAND
TELEPHONE: LEICESTER 67534 (5 lines)

London Office: COASTAL CHAMBERS, 15 ELIZABETH ST., BUCKINGHAM PALACE RD., S.W.1 TEL: SLOANE
Scottish Representatives: WALTER S. LANG & CO., 48 OSWALD STREET GLASGOW C.1. TEL: CENTRAL 2539

Crushed swarf— is saleable

CONTRARIWISE, nobody wants the other stuff. It is indeed something of a menace, costly in labour and space. But put your bushy-turnings through a B.J-D Swarf Breaker and out come short lengths that take up much less room and can easily be shovelled—and sold. Many firms who produce fairly considerable quantities of swarf now use a B.J-D Swarf Breaker to good effect.



swarf breaker

and mechanical feeder

BRITISH JEFFREY DIAMOND LTD., CRUSHER & INDUSTRIAL DIVISION, 15-17 CAXTON STREET, LONDON, S.W.1
FW5077

BLANKS WITHOUT DIES

If you need small*
quantities of blanks, pierced or
otherwise, in metals or non-metals,
use the.

CROSLAND BLANK & PIERCE SERVICE

which offers you prompt delivery
of well finished blanks produced by
its unique and surprisingly inexpensive
tooling and production technique.
Forget about dies and simply send
your drawings and specifications to . . .

William Crosland Ltd.

BREDBURY, Nr. STOCKPORT, CHESHIRE. Phone: Woodley 2621 (3 lines)

* as small as
you like!

ESTIMATES SENT BY RETURN

When answering advertisements kindly mention MACHINERY.

In stock now


VERTICAL SPINDLE SURFACE GRINDER

A machine specially built for rough or precision grinding of continuous and interrupted plane surfaces. For hollow grinding the head can be tilted out of its horizontal position. During grinding, the entire working width of the table can be covered simultaneously by a segmental grinding wheel.

Type BPV 300/1500
£1,935*

	BPV300		BPV700	
	1000*	1500*	2000	3000*
	(inches)	(inches)	(inches)	(inches)
Working surface of table	11½ x 39½	11½ x 59	23½ x 78½	23½ x 118
Maximum width, ground	11½	11½	23½	23½
Longitudinal travel of table	54½	80½	95	154
Main Spindle drive, h.p.	20	20	30	30

* From stock, subject to prior sale.



Versatile and compact

CENTRELESS GRINDER TYPE BBZ60

For the high precision grinding of plain cylindrical, shouldered and tapered parts, as well as parts of more intricate shape.

Soft or hardened steel can be handled and with a suitable grinding wheel practically all other materials, including brass, copper, aluminium, glass and plastics.

The machine can be operated by unskilled labour.

Price, £1,250 from stock



Sole Selling Agents U.K.



NEWMAN INDUSTRIES LIMITED

Machine Tool Division

YATE • BRISTOL • ENGLAND


Telephone: CHIPPING SODBURY 3311

Telegrams: "DYNAMO YATE"

When answering advertisements kindly mention MACHINERY.

Fabricated from 'DOUBLE BOND'

M.O.S. Spec. DTD. 900 4572



Photograph reproduced by courtesy of Handley Page (Reading) Ltd.

'DOUBLE BOND' is a chemically-setting metallic plastic available either as a Putty or a Cream. It has a wide range of production and trade applications. 'DOUBLE BOND' can be used both for making objects in its own right and for sealing, joining, filling seams, channels, rivet and bolt dimples, etc.

The illustration shows an assembly and drilling fixture made from 'DOUBLE BOND' Putty Grade by Handley Page (Reading) Ltd. It is used in aircraft assembly where extreme stability and accuracy are called for and demonstrates the excellent forming characteristics and inherent strength of the product. This example, measuring 3ft. in diameter, is the first and smallest of a series, others 72in. in diameter have now been constructed with Double Bond.

Sole Manufacturers:

THE KENILWORTH MANUFACTURING CO. LTD

West Drayton, Middlesex. Tel: West Drayton 3731 PBX

FRACTIONAL HORSE-POWER MOTORS

From 1/2000 to 1 Horse Power. Synchronous. Commutator. Asynchronous Induction. Utterly reliable. Built with the skill and experience distinguishing all Klaxon output.

GEARED UNITS

Over 50 Standard Types. Output torques from Zero to 2500 lbs. ins. Other types and Performances for special needs.

WARNING SIGNALS

For industry and transport. Buxton certified mine signal equipment. Audible signals for factories, railway yards, power stations, transport, etc. Heavy duty Screen Wipers, and Direction Indicator Flasher Units.

KLAXON Ltd. Manufacturing Electrical Engineers
Estab. 1909


49 Upper Brook St., London, W.1 Tel: Mayfair 9020
WORKS—BIRMINGHAM Tel: Acocks Green 1654

KLAXON

every time!

When answering advertisements kindly mention MACHINERY.

BTR
VIBRO-INSULATORS
did this for us



What can they do for you?

Here on an upper floor, is an Internal Mixer—some 16 tons of machinery that, in producing rubber mixtures for high quality industrial products, transmits a ceaseless stream of vibrations to the floor and foundations. Few foundations could withstand such shocks without special reinforcement—much less upper floors. But mounting the Mixer on BTR Vibro-Insulators has enabled BTR works engineers to site it on an elevated platform which, as the photograph shows, is not unduly thick. The Vibro-Insulators absorb the shocks so effectively that the operator on the mill below can be quite unaware that the Mixer is even working.

If you have machinery whose vibration is possibly damaging foundations or building structures or impairing health and efficiency with excessive noise, ask BTR engineers about the advantages of mounting on BTR Vibro-Insulators.

BTR Industries Ltd

BRITISH THERMOPLASTICS & RUBBER MANUFACTURERS

HERGA HOUSE, VINCENT SQUARE, LONDON S.W.1

TELEPHONE: VICTORIA 3848



D2675

When answering advertisements kindly mention MACHINERY.

N

for Die Springs of quality

*made from High Grade Swedish Steel
carefully heat treated in order to ensure that
springs of the highest quality are supplied for
high duty purposes*

*All springs have been shot peened for maximum
fatigue and tested by scrapping solid to
perform the duties set out in this advertisement*

*To prevent rusting the springs are finished
by an approved Phosphate Process*

28 sizes always in stock

price list on application **phone or write (dept. S.M.O.)**

THE DART SPRING CO LTD WEST BROMWICH

telephone: WESt Bromwich 1791 P.B.X. (7 lines)

telegrams: Dart, West Bromwich



the New DUNBAR & COOK Collet Chuck

Designed for use with "Ward" 2A, 3A, or "Herbert" 2D and 4 Senior Capstans and Air Operated Lathes, this over size collet chuck enables second operation work up to four inches diameter to be accommodated but retains all the benefits of a ball chuck.

DUNBAR & COOK LTD • NEW JOHN STREET • BIRMINGHAM 6

'Phone: ASTon Cross 2571/2/3

Grams: "CUBAR" Birmingham

SPECIALISTS IN THE MANUFACTURE OF

**SPECIAL PURPOSE
MACHINES
JIGS AND FIXTURES**

When answering advertisements kindly mention MACHINERY.

$$6 \times 4 = 24$$

TYPES
OF FEED


SPEED
RANGES

POSSIBLE
COMBINATIONS

that's
the
beauty
of the

A & S


MODEL 'I'
HORIZONTAL MILLER




6 With automatic cycle.




1 Hand Feed—lever, screw, lever.




2 Hand Feed—lever, lever, lever.



3 Hand Feed—Screw, screw, screw.



4 Multi-form—semi-automatic cycle.



5 Normal automatic feed.

WHY PAY FOR 'SPECIAL' FEATURES YOU MAY NEVER USE ?

When you equip with A. & S. Model 'I' Millers you choose from 4 ranges of speeds and 6 different feed arrangements the best combination* for a particular job. Both hand-feed and automatic types can, however, be supplied with special attachments for special operations. No other small milling machine offers similar versatility or higher production capacity for so wide a range of work.

TABLE 26" x 7"
LONGITUDINAL TRAVERSE = 10"
VERTICAL TRAVERSE = 10"
TRANSVERSE TRAVERSE = 5½"-6"

*With the A. & S. Model 'I' brochure in front of you, you would know exactly what we mean.

Built up to a standard—not down to a price

Write for illustrated leaflet.

ADCOCK & SHIPLEY LTD.

P.O. Box 22, Ash Street, Leicester. Telephone: Leicester 24154-6
Telegrams & Cables: Adcock, Leicester.

Is this your blind spot?


Companies taking pride in their high rate of productivity on the factory floor are sometimes blind to the opportunities for increased productivity in the drawing office.

The Simplon "Modular Line" units, two of which are illustrated here, are specially designed as complete individual work stations, with the drafting board as the hub of the draughtsmen's activity. Thus all unnecessary movement is eliminated and, since countless efficient room layouts are possible, all available space is utilised to the best advantage.

Full details of the Simplon units and the Simplon Consulting and Advisory Service will be sent on request.



SIDE or BACK
REFERENCE UNITS



CANTILEVER
DRAFTING UNIT

SIMPLON

DARGUE BROS. LTD.

NEW SIMPLON WORKS
HALIFAX, YORKSHIRE

Telephones: Halifax 3218-9

Flash weld your Band Saws

Automatically


ON THE

STRYCO BAND SAW WELDER

Heavy duty, for production or repair work. Motor driven cycle flash-welds all band saws from the heaviest to the lightest—quickly, simply, and in perfect alignment.

MF.1—4 kVA. 1" capacity. MF.2—6 kVA. 1½" capacity

MF.3—8 kVA. 2" capacity



SOLE U.K. DISTRIBUTORS:



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14


Telephone WESTERN 9877 (8 lines)

Telegrams ACCURATOOL HAMMER LONDON

Write for the
fully illustrated
folder

ARNO VERTICAL MILLER

3 L DIAL TYPE



**SLASHES PRODUCTION COSTS!
REDUCES OPERATOR FATIGUE!**

NOTE THESE FEATURES.

- ★ Dial change speeds and feeds.
- ★ Three-way power traverses.
- ★ Spindle stop, feeds and rapid traverses by single lever.
- ★ Backlash eliminator.
- ★ Hardened and ground gears.
- ★ Swivelling and sliding head.
- ★ Centralised controls.
- ★ Table 60" x 12"
- ★ H.P. 9½.
- ★ Schlesinger limits.

AND THE PRICE?

—£2,100

EX-LONDON WORKS

Also:

Nos. 1, 2, 3L, 3H Vertical Millers.

Nos. 0, 2, 3 Universals.

No. 5 Facing & Boring Miller.

For further details of ARNO Millers, write, phone or call—

**HELMET ROW, OLD STREET, LONDON, E.C.1.
TELEPHONE : CLE : 6481.**

PIDGEN BROS
LIMITED

ALL GEAR WHEELS supplied complete or cut from customers' own blanks.

EXTERNAL AND INTERNAL SPURS, HELICAL AND WORM GEARS up to 27 ft. outside diameter, 48 in. face width, 1 D.P.


DOUBLE HELICAL GEARS up to 54 in. dia. 10 in. face width, 2 D.P.

STRAIGHT BEVEL GEARS up to 24 in. dia., 2 3/4 D.P., 9 module.

SPIRAL AND "SPIROID" BEVEL GEARS up to 24 in. diameter, 2 D.P., 12 1/2 module.

PRECISION GROUND WORMS up to 10 in. diameter and 12 in. thread length.

SPUR TOOTH GRINDING up to 42 in. diameter, 2 D.P.



CRAVEN

GEARS

CRAVEN BROTHERS (MANCHESTER) LTD. VAUXHALL WORKS, REDDISH, STOCKPORT
TELEPHONE: STOCKPORT 4624

SPECIALISTS in used and reconditioned machine tools

USED MACHINE TOOLS FOR IMMEDIATE DELIVERY ★

ACME-GRIDLEY 1/2 in., 1 in., 2 in., 2 1/2 in., Six-Spindle Bar Automatics.

ACME-GRIDLEY 6 in. Six-Spindle Chucking Automatics.

B.S.A. ACME-GRIDLEY 1/2 in. Six-Spindle Bar Automatics.

B.S.A. ACME-GRIDLEY 5 1/2 in. Six-Spindle Chucking Automatic.

B.S.A. 168AL Single-Spindle Automatic Screw Machines.

B.S.A. 5 in. and 9 in. Single-Spindle Chucking Automatics.

B.S.A. Multi-Tool Lathes, 6 in. x 12, 20 and 28 in.

B.S.A. No. 7 and **No. 8** Centreless Grinding Machines.

B.S.A. 50H Honing Machine.

B.S.A. LANDIS 6 in. x 30 in. Type C Plain Grinders.

B.S.A. POTTER & JOHNSTON 5D Automatic Turret Lathes.

AMERICAN Broaching Machine 10/48.

ASQUITH Two-Spindle Profiling Machine.

BRADFORD Lathe.

HERBERT Vertical Millers 10V, 18V, and 46V.

HOLROYD Two-Spindle Profiling Machines.

HULLER No. 5 Tapping Machines.

INDEX "52" Single-Spindle Automatics.

LANDIS 10 x 24 Universal Grinder.

POTTER & JOHNSTON 5D Automatic Turret Lathe.

WARD 2A Capstan Lathes.

WARD OE Capstan Lathes.

★ Offered subject to prior sale.
All machines motorised suitable for 400-440 volts, 3 phase, 50 cycle supply.


We offer good prices for your surplus plant. Send us details—we will inspect immediately and make a firm offer. Write, wire or phone . . .

BGMACHINERY
(B.S.A. TOOLS GROUP) LTD.
MONTGOMERY STREET
BIRMINGHAM, II.
Phone: VICTORIA 2351-9 Grams: "REBUILT"




DEEP THROAT

SAW/FILER



Similar in design and specification to the MIDSAW 'Standard' Saw/Filer this latest addition to the MIDSAW range of High-Speed cutting machines provides greatly increased horizontal capacity. It possesses all the well known and well tried features incorporated in the rest of our Saw/Filers, of which the patented Variable Speed Drive is outstanding.



We will be pleased to send YOU a copy of the illustrated folder giving full details of the MIDSAW "Deep Throat" SAW/FILER

— *the machine to give you
EXTRA capacity and production*

THE MIDLAND SAW & TOOL COMPANY LIMITED

MIDSAW WORKS — POPE STREET — BIRMINGHAM 1
Telephone: CENTRAL 4245/6/7 Telegrams: MIDSAW, BIRMINGHAM
LONDON (AND EXPORT) OFFICE: 44/45 TOWER HILL, LONDON E.C.3.
Telephone: ROYAL 1461-4 Cables: MORIMIL, LONDON
Telegrams: MORIMIL, FEN, LONDON



When answering advertisements kindly mention MACHINERY.

CUT THE COST OF PRESS TOOLS!



NORTON STANDARD PRESS-SHOP EQUIPMENT

including

NORTON LONG LIFE DIE SPRINGS

Made from high grade flat section spring steel with round edges in 28 stock sizes.

NORTON PRESS TOOL RUBBER BUFFERS


In best quality medium hard grey buffer rubber stocked in over 30 sizes.

Full Specification sheets on request

Tel: Central 4325 (5 lines) Grams: Nortonco B'ham

T. NORTON & CO LTD · CARVER ST · B'HAM 1

Manufacturers of NORTON Hand, Foot, Arbor & Air presses & Press shop equipment



SERVICE AND SERVICEABILITY

have made Mills world-wide reputation

'Oilauc' 60-ton Vertical Forging Press

Fabricated steel construction. Stroke fully adjustable over whole ram travel.

Hand lever operation—ram returns automatically when released.


Non-Rotating Ram.

Unloading and Retaining Valve—allows ram to be held under pressure without overheating the oil.

Removable footstock.

Additional features such as an ejector and variations of standard dimensions are available.

From 15-tons to 500-tons capacity.



'Oilauc' 60-ton Vertical Open Gap Press

Fabricated Steel Construction.

Hand and foot control.

15" Ram stroke (adjustable) with power return.

Advance speed 200" per minute.

Return speed 240" per minute.

Power speed 22" per minute.

Machine illustrated has 5'-6" long table.

Other sizes available.

Standard extras

Straightening Equipment and sensitive control.

Pressure trip for automatic ram return.

Pressure sustaining valve.

Special features available

Ejector or dashpot.

Electrical control for—automatic cycling remote operation timed pressure dwell.

From 8-tons to 300-tons capacity.



Sole Agents:

**Alfred Herbert Ltd.
COVENTRY.**



OILAULIC PRODUCTS

John Mills & Co. (Llanidloes) Ltd.
Railway Foundry, Llanidloes, Montgomeryshire.

When answering advertisements kindly mention MACHINERY.



ROLLS-ROYCE

use the best—
and the fastest
method of milling
LIGHT ALLOYS



Wadkin Vertical Milling Machine L.H.1. with cutting speeds up to 18,000 r.p.m. face milling a steering box. Photographs by courtesy of Rolls-Royce Ltd., Crewe.

***This steering box
is face machined
in 20 seconds!***

Rolls-Royce Ltd., like many other famous firms, appreciate the benefits of using a machine specially designed for milling Non-ferrous metals. Their Wadkin Vertical Milling Machine L.H. face mills their light alloy components, such as the steering box shown above, in a fraction of the time taken by any other method. And it does so with the accuracy and finish associated with Rolls-Royce standards. The Wadkin type L.H. consists of one basic machine of plain, robust and inexpensive design, with three alternative head arrangements. Each head has cutting speeds far higher than orthodox millers, permitting feeds as high as 84" per minute. Leaflet No. 811, giving full details will be sent on request.

Tel: Leicester 68151

Wadkin Ltd., Green Lane Works, Leicester

Wadkin

Tel: MAYfair 7048


London Office: 62-64 Brook Street, W.1

When answering advertisements kindly mention MACHINERY.

Hold it!


With

CROWN



SPECIAL TYPES
MADE TO ORDER

MAGNETIC CHUCKS



**STANDARD RECTANGULAR AND
ROTATING-TILTING MODELS . . .**
(as illustrated)

Wound for 110v. D.C. or 220v. D.C.
SIZES 12" x 8" up to 72" x 18"

British Made by
WINDLEY BROS. Ltd.
CROWN WORKS : CHELMSFORD
Phone: Chelmsford 2224

CUT YOUR SAWING COSTS

SUPER SPEED

HIGH SPEED STEEL

SLITTING SAWS



**FOR SUPREME PERFORMANCE
UNDER ALL CONDITIONS**


Accurately milled teeth, controlled heat treatment, perfect concentricity and precision grinding—these are the characteristics of **SUPER-SPEED** "High Speed Steel Metal Slitting Saws. Trouble free cutting—long life no matter the job.

All standard sizes from 2½" to 12" dia.

Technical advice freely available.

Also: "Super-Speed" Screw Slitting Cutters,
"Super-Speed" & "Speed" Hacksaw Blades,
"Speed" Metal Cutting Bandsaws, etc., etc.

SLACK, SELLARS & CO., LTD.
MOWBRAY STREET · SHEFFIELD 3 · ENGLAND
THE METAL SAW SPECIALISTS



When answering advertisements kindly mention **MACHINERY**.

*An engine
for the
first steamship*



When, in 1789, the world's first practical steamship had her trials on the Forth and Clyde Canal, the results were most satisfactory. Built under the supervision of William Symington—"the father of marine

engineering"—the vessel was powered by engines built by Carron Company, and these were an unqualified success. Then, as now, it paid men with ideas to get in touch with Carron Company.



1958 - *engineering for all industries!*

Although Carron Company to-day is a highly technical, efficient organisation, the old pride in craftsmanship, which has been the basis of its success, is more than ever in evidence. This is why the top men in all branches of industry—shipbuilding, marine and general engineering, catering, public works, heating and lighting and Government Departments—discuss their problems with Carron Company's advisory service. They unfailingly gain benefit from this—and so will you!




CARRON COMPANY • CARRON • FALKIRK • STIRLINGSHIRE

Showrooms and Sub-Offices: 15 Upper Thames Street, London, E.C.4. 22-26 Redcross Street, Liverpool, 1.
125 Buchanan Street, Glasgow, C.I. Sub-Office: 33 Bath Lane, Newcastle upon Tyne.

25A

When answering advertisements kindly mention MACHINERY.

NO MACHINING NEEDED WITH SINTERINGS!



Think of the savings you would make if you could eliminate machining! Impossible, you might think? No, not a bit of it. For so great are the advances made in recent years in powder metallurgy that it is now possible to produce a vast range of pieces in their finished state!

Already many manufacturers dealing in quantity production are taking advantage of these techniques. And at Sintered Products Limited, still further applications are being found daily to help industry achieve a faster, more economic production of parts. Perhaps they could help you?



**Sintered Simon says
Save on SINTERED**

Our Representative will gladly call to discuss your particular problems. Or write for the DURASINT booklet giving you full details to:


Sintered Products Limited

(One of the Sheepbridge Engineering Group)

Hamilton Road, Sutton-in-Ashfield, Notts.

Phone: Sutton-in-Ashfield 590 Grams: Sintered, Sutton-in-Ashfield

ALLIANCE (7)



Catalogue sent on request

Precision bench surface grinding machine

LIP

Developed for the watch clock instrument and allied industries

Capacity : LENGTH 202 mm
BREADTH 108 mm
HEIGHT 125 mm

Surface of magnetic chuck :
105 x 152 mm.

Accessories available

Stand
Dust extractor
Dressing diamond with holder universal vice

LIP INDUSTRY



BESANÇON : 7, rue des Chalets. Tél. 59-31

Agents for Great Britain : TORNOS SALES Co.
E.M. Vaughan Ltd
Broadgate House
COVENTRY

When answering advertisements kindly mention **MACHINERY**.

PNEUTOMATION

*a power for production
that's yours to command*


What you need in your works is this
pocket-sized elephant —

PNEUTOMATION! You'll find
PNEUTOMATION has all the
power of a pachyderm, plus
compactness. You get the
same tireless energy,
accurately applied to the
right place at the right time,
under perfect control.

PNEUTOMATION is tailor-
made to work with the minimum
of elbow room and the wide
range of standard equipment fits
any job from bell-ringing to jig-
boring. Simple design, careful
workmanship and completely non-
corrodible materials cut replacement
and maintenance costs,
make Lang PNEUTOMATION a
really long-lasting, trouble-free system.

Pneutomatic never forgets to operate

The 'Pneulang' basic cylinder unit, just one of
the 264 cylinders available 'off-the-shelf'.
The range of PNEUTOMATION equipment also
includes many types of manual and automatic
valves, lubricators, air flow regulators,
pipes and fittings, etc.



PNEUTOMATION
energy under control



Plan with

LANG PNEUMATIC LTD

VICTORY WORKS BIRMINGHAM ROAD WOLVERHAMPTON Tel. 25221 2 3

Associated with Desoutter Brothers (Holdings) Ltd.

P.1651

When answering advertisements kindly mention MACHINERY.

'EDIBRAC' CARBIDE TIPPED TOOLS

We are pleased to announce that we have been appointed **SOLE AGENTS** in London, Southern and Eastern Counties for 'EDIBRAC' Carbide Tipped Lathe Tools and Tips, Twist Drills, Lathe Centres, Reamers, Milling Cutters, etc.



Special Tools to customers drawings

Ask for Catalogue

GEORGE HATCH LTD.

3 QUEENHITHE,
UPPER THAMES STREET, E.C.4

Telephone: CENTRAL 7751



1400
1600

Milled complete
in one hour -

on the NEW
AHCOL ROTAMILL

SEMI-AUTOMATIC
ROTARY MILLING
MACHINE

With continuous cycle and automatic work clamping the $\frac{3}{8}$ " x $\frac{3}{8}$ " slots and end faces in these brass components were gang milled at 1,400 and 1,600 pieces per hour—typical Rotamill production times.

CAPACITIES	ROTAMILL	AHCOL	AHCOL SENIOR
Work drum dia.: ..	12" ..	12" ..	24" (twin heads)
Cutter dia.: ..	6" ..	4" ..	8"
Cutter width ganged: ..	6" ..	4" ..	8"
Motor: ..	5 h.p. ..	1 h.p. ..	6½ h.p. (two)




DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14

Telephone: WESTERN 8077 (8 lines)

Telegrams: ACCURATOOL HAMMER LONDON



Write for the illustrated catalogues, or send us drawings or samples, and ask for our proposals.

When answering advertisements kindly mention **MACHINERY**.

**Look first to
BROOKHIRST**

24 HOUR

DESPATCH


AUTOMATIC STRAIGHT-ON STARTERS

STOCK-CONTROLLED STARTERS

A.C. STATOR-MOTOR STARTERS

FOR QUICK DELIVERY—24 hours despatch of popular items—you can't beat Brookhirst! Full technical information and prices of the widest and most adaptable range of standard control equipment ever offered are given in Catalogue 32. Write now for your copy, and also for a copy of Short Delivery List.

(Right) Type SC-618 small horse-power A.C. automatic straight-on starter with block type contactor and combined overload and single phase protection.




BROOKHIRST

SPECIALISTS IN MOTOR CONTROL

BROOKHIRST SWITCHGEAR LIMITED . NORTHGATE WORKS . CHESTER

A METAL INDUSTRIES GROUP COMPANY



COVERS and PACKINGS FOR MODERN INDUSTRY



FORTOX FLEXIBLE

COVERS protect machinery and exclude dirt. Made in neoprene nylon proofed leather or coated fabrics to suit all conditions. New type of construction gives expansion to contraction ratio of 10-1. Single items supplied to special requirements without tool charge.

FORTOX SEALS AND PACKINGS are manufactured to high standards of accuracy ensuring positive sealing and trouble free life. A range of polyester rubbers, silicone leathers and synthetics is available for extreme conditions. Single items supplied promptly.

Write to-day for full details of our work.

A.I.D. approved.



Henry Beakbane (Fortox) Limited

HEAD OFFICE AND TANNERY


THE TANNERY-STOURPORT ON SEVERN-WORCS

TELEPHONE STOURPORT 2017

LONDON WORKS

68-70 LANT ST, BOROUGH S.E.1

TELEPHONE HOP 0458



MULTIPLE DRILL HEADS

★ **COMPACT IN DESIGN**
★ **FIXED OR ADJUSTABLE
CENTRE DISTANCES**

Hey Multiple Spindle Drill Heads convert Standard Drilling and Boring Machines to High Production Machines permitting drilling of all holes in a component simultaneously, with production rates equal to those obtainable on expensive special purpose machines.

Compact design reduces to a minimum, distance from drill head to machine spindle, whilst careful selection of material ensures an extremely efficient light weight head.

Heads are available with any number of spindles, covering a wide range of sizes

**MAXIMUM PRODUCTION ON DRILLING, REAMING,
TAPPING AND SPOT
FACING OPERATIONS**

HEY

ENGINEERING CO. LTD.
COVENTRY PHONE: COVENTRY 88641

We also manufacture Rotary
Cams and Profile Milling
Machines, Short Thread Milling
Machines, Gear Tooth Rounding
Machines, Tapping Machines,
End Facing and Centring
Machines, Special Machine
Tools for High Production.

The Muscle that hustles Production!

Now those costly 'manhandling gaps' in the production lines can be filled—with hydraulically powered muscle. Bicep Lifters boost production by completing the chain of mechanical handling:

'Biceps' mean smoother, quicker ...

Positioning of materials
Feeding work to and from machines
Loading and unloading trucks
Stacking and loading heavy goods
(especially heavy sheet materials)



- **ABSOLUTELY STABLE:** unaffected by uneven loading
- **ENORMOUSLY STRONG.** A wide range of sizes and capacities up to 10 tons
- **PLATFORM CAN BE RAISED,** lowered or stopped at any level automatically or by hand
- **CAN BE EQUIPPED WITH ROLLERS,** automatic feeding gear, wheels and steering for mobility



bicep

REGD.

HYDRAULIC LIFTERS

Write now for leaflet MM7 to:
ACCESS EQUIPMENT LIMITED

Maylands Ave · Hemel Hempstead · Herts
Tel: Boxmoor 5781 Cables: Accesquip Hemel-Hempstead




When answering advertisements kindly mention MACHINERY.

The SOMMERFIELD LIQUID BLASTER AND HONER

For

FINER FINISHES • MOULD CLEANING
ELECTRICAL CONTACTS • STENCILLING
HONING AND IMPARTING MATT OR
POLISHED FINISHES TO ALL METAL
SURFACES

FOR MEDIUM FINISHES ASK FOR OUR
L.D. RANGE OF SHOT BLAST AND
FOR HEAVY DUTY GET PARTICULARS
OF OUR BOMBARDIER CENTRIFUGAL
SHOTTING MACHINES.



Tel: Gulliver 3443


H. G. SOMMERFIELD LTD
DEPT 'E' CAMDEN RD LONDON N.W.1

INTRODUCING *The* **S & B** ROTARY COLD TAGGING MACHINE

Backed by 30 years' experience in building
rotary swagers, the makers have designed
this new machine especially for cold tagging
steel and non-ferrous tube or bar.
Four dies are mounted in a fixed head and do
not rotate. THERE IS NO POSSIBILITY OF
THE DIES REVOLVING THE TUBE risking
injury to the operator. Advantages are a
uniform strong tag, no heating and furnace
costs, higher production.

OUTPUT UP TO
200 PER HOUR
ON 2in. TUBE.

A short 16 mm.
film describing
this machine is
available on
application.



**STEVENS AND
BULLIVANT Ltd**

WESTERN ROAD




BIRMINGHAM 12

ENGLAND

When answering advertisements kindly mention MACHINERY.




**Do you
use drop forgings
like these?**



Whether you want a long run or drop forgings in small quantities, do as some of the greatest users of drop forgings — come to Doncasters. Drop forgings that are as good as skilled labour and first class materials and plant can make them are a Daniel Doncaster hall-mark. Discuss your requirements with us.

DONCASTERS



1778

DANIEL DONCASTER & SONS LIMITED • SHEFFIELD
FORGINGS • DROP FORGINGS • TOOL STEELS • HARDENED STEEL ROLLS

When answering advertisements kindly mention MACHINERY.

Speetog-Elect

REGD. TRADE MARK

SELF-LOCKING Plier Clamp

The First Tool in the World to Combine Secure Locking with Parallel Jaw opening.

BRITISH PATENTS 576142, 731731 also Foreign Patents



Setting the jaws to required distance with adjusting screw

- Jaws open to $\frac{1}{2}$ " always parallel
- Ratio of gripping pressure to hand pressure about 150 to 1
- Can be used as fixture or as hand tool
- Simple to use yet so sure in its action



Presetting to required pressure with same adjusting screw

TIME FOR SETTING & CLAMPING 10 SECONDS! DO YOU KNOW OF ANYTHING FASTER?



A squeeze of the hand and the job is held fast with any pressure required from a few ounces to several hundred pounds

Speed Tools Ltd


VEREKER HOUSE, GRESSE ST., LONDON. W.1. Museum 1039/1099

NRP


M.P.J. DIAL SNAP GAUGES

MODEL 'D'


SPECIAL ANVILS




Anvils for measurement of a shoulder diameter in a recess.




Anvils for measurement of a shoulder diameter.




Anvils for checking dimensions of a gear.



Anvils for measurement of a groove.



Anvils for measuring a root dimension of a rotor blade.



Standard Model

The illustrations show special anvils fitted by us to suit particular requirements.

Range of Models—

Smallest—0-in.
Largest—38in. to 40in.
Graduations—0.0005in., 0.0001in.,
0.01 mm or 0.002 mm.

Member of the Gauge & Toolmakers' Association

M.P.J. GAUGE & TOOL CO. LTD · ERDINGTON · BIRMINGHAM 24



a fine cut



Of course, it's Savile Row for a fine cut. But in your line of country, Jessop-Saville tools give the best cut of all. Jessop-Saville "off the peg" high speed steel butt-welded tools are always available in 55 standard shapes and 15 shank sizes. The High Speed Steel Tips—electrically butt-welded to good quality carbon steel shanks—have exceptional wear and abrasion resisting qualities and consequently longer service between re-grinds. Please send for a copy of our Monthly Stock List.

JESSOP-SAVILLE

ARKWELD AND TRIUMPHWELD
high speed steel butt-welded tools

WM JESSOP & SONS LTD

BRIGHTSIDE WORKS SHEFFIELD




J J SAVILLE & CO LTD

TRIUMPH WORKS SHEFFIELD

ENQUIRIES TO: SMALL TOOL WORKS · PORTLAND STREET · SHEFFIELD 6

KLÖCKNER MOELLER

Switchgear . . .



... in the Steel Company of Wales

In September, 1954, a Klöckner Moeller contactor was installed in the Cold Reduction plant of the Steel Company of Wales' Trostre works.

Now, some three years later, the contacts have 1.3 mm. and 1.1 mm. of wear remaining. The expected life of these contacts is a further six years.

In addition, during the entire working life of this equipment it has not been necessary to carry out any maintenance or repair.

KLÖCKNER MOELLER ENGLAND LIMITED



LONDON 7 Charterhouse Buildings,
Goswell Road, E.C.1 CLERKENWELL 0778


MANCHESTER Prince's Buildings, Block C,
28 Oxford Street, Manchester 1. Central 0274

BIRMINGHAM Guildhall Buildings, Navigation Street,
Birmingham 2. Midland 2891

GATESHEAD-ON-TYNE 451, Durham Road, Low Fell,
Gateshead-on-Tyne 9. Tel.: 75517



GRINDERS



PRICE:

10in. 3ph £47.10.0

12in. 3ph £75.0.0

14in. 3ph £95.0.0

FOR DETAILS OF OUR COMPLETE
RANGE. WRITE

R.J.H.
THE R.J.H. TOOL & EQUIPMENT CO., LTD.,
HECKMONDWIKE. TEL: HECKMONDWIKE 490

When answering advertisements kindly mention MACHINERY.

AFTER **125** **YEARS**



ALL METALWORKING TRADES
still demand
COATED ABRASIVES
by

OAKEY

IN ROLLS · BELTS · DISCS & SHEETS

ESTABLISHED

1833

John Oakey & Sons Ltd · Wellington Mills · London · S.E.1




OA2BA

When answering advertisements kindly mention MACHINERY.

SUMMIT


TRADE MARK



HOBS

Made in

**SUPER
HIGH SPEED STEEL**
either ground form or
Machine Relieved



**JOSEPH THOMPSON
(SHEFFIELD) LTD.**

Townhead St., Engineering Works, Sheffield, 1, England
Telephone: 24120 (3 lines) Grams: "Summit, Sheffield"

SEGIC TAPPING MACHINES

Controlled
Pitch
Ex Stock

0 BA — 12 BA in Steel
£127

Other sizes and hydraulic
up to 1½ in.



**TRUE FORM
IRRESPECTIVE OF OPERATOR'S SKILL**

Distributors and Stockists for the United Kingdom



**MORTIMER
ENGINEERING CO.**
PO BOX 1705 - 5 GUILDFORD - GU1 1TD




204-206 ACTON LANE, HARLESDEAN, LONDON, N.W.10 Tel: ELGar 3834

CONTINUOUS FILING

*speeds
production*

Size of table 20 in. by 20 in.
Depth of throat 18 in.
Cutting speed 5 steps
Range 9 to 44 m/min
Smallest hole for introducing
the file chain ¼ in.
Power required approximately
0.75 H.P. 220/380 Volts
Table inclinable 20° forward
15° back
Three widths and sections of band-
file may be used ¼ in., ⅜ in., ½ in.
rough medium or fine cut



The new
GROB

(MODEL F.A.B. 18)

BAND FILING MACHINE

FISHER DEANE ENGINEERING CO LTD

19 HOWARD CLOSE - HAMPTON - MIDDXX Tel: MOLesey 2612

When answering advertisements kindly mention MACHINERY.

LUMSDEN

MODEL 96 LM

SURFACE GRINDERS

Top rates of production are linked with a high order of accuracy when 12 cast steel gear housings for the Jones KL66 crane pass under an 18-piece segmental wheel on this model 96 LM Heavy Duty Surface Grinder. The large diameter table revolves at 8 R.P.M. $\frac{1}{16}$ in. of metal is removed and the components are sized to ± 0.002 in. Whilst the Lumsden model 96LM is designed to tackle just such a job as this, in the most rapid, precise and economical manner possible, a complete range exists, from which to choose a machine ideally suited to your own grinding requirements.

*Close Limits
and High Output
on
Differential Housings
for JONES' CRANES*



Manufacturers :

LUMSDEN MACHINE CO. LTD. GATESHEAD

Sole Distributing Agents :

ALFRED HERBERT LTD., COVENTRY


When answering advertisements kindly mention MACHINERY.

GRANVILLE*High Speed*
BANDSAW

- ✱ POSITIVE CONTROLLED HYDRAULIC FEED
GIVES SUPER FAST CUTTING ON BARS
TUBES, ANGLES AND SECTIONS
- ✱ NO WASTE: CUT ONLY 0.05 in. WIDE
- ✱ ACCURATE: TO WITHIN ± 0.005 in. on 4 in. BAR

Specially designed for production cutting-off, the GRANVILLE will handle bars, tubes, angles and even sections as large as 13 in. x 6 in. at super-fast speeds. Ample power, positively controlled hydraulic down-feed. A precision setting device for fine adjustment of vice angle within 15 mins. of a degree is available.

Write now for full details.



Full particulars from: **F. COALS LIMITED**

WOODFORD AVE., WOODFORD GREEN, ESSEX.
PHONE WANSTEAD 7766/7767/7768

**TYPE 9H**

★ DEMONSTRATION
WITHOUT
OBLIGATION



DUFF NORTON
LIFTING JACKS

STOCKS

All sizes of Duff Norton Jacks
are available from CP branch
office stocks at:


LONDON
BELFAST
BIRMINGHAM
BRIDGEND
DUBLIN
GLASGOW
LEEDS
MANCHESTER
NEWCASTLE
and from CP distributors
in all main centres.

The finest jack in the world!

CONSOLIDATED PNEUMATIC TOOL CO. LTD. DAWES RD. LONDON, S.W.6
CP 169

SCHMIDT Automatic
SAW SHARPENER for

Slitting Saws,
Hacksaw and
Bandsaw Blades



accuracy with
automatic
sharpening

Grinds Slitting Saws up to
1 1/2 in. dia. Hacksaw blades
up to 2 1/2 in. x 28 in. and Band-
saw blades 1 1/2 in. wide.

An accurate retoothing device
is fitted.

Exclusive distributors in the
United Kingdom

**IMMEDIATE
DELIVERY**


Send for Comprehensive
Illustrated Brochure

ELGAR




*Machine Tool
Company Limited*

172-178, VICTORIA ROAD, ACTON, LONDON, W.3
Phone: ACOrn 5555 (7 lines) Grams: ELGATool, LONDON W.3
Midlands Showroom: 1075 Kingsbury Road, Birmingham 24
NRP

PRESS BRAKES



200 ton
12'-0" wide Press Brake




WE ALSO MAKE

- Open-fronted Presses
- Double sided Presses
- Single and Double Crank Presses
- Power Screw Presses
- Minting machinery
- Cartridge machinery
- Double Action type Drawing Presses



TAYLOR & CHALLEN LTD BIRMINGHAM 19

When answering advertisements kindly mention MACHINERY.



foot lever PRESSES

Specially designed for high output with unskilled labour. Foot operation leaves operator's hands free for manipulation of the workpiece. Supplied for bench or stand mounting.
PROMPT DELIVERY.
Ask for details.

ASK FOR CATALOGUES OF COMPLETE RANGE OF DIAL GAUGES, PRESSES AND DRILLING MACHINES
GENEROUS TERMS TO MERCHANTS

MANUFACTURED SOLELY BY

ENGINEERING PRODUCTS LIMITED

GLENBROOK WORKS, LITTLERS-CLOSE,
MERTON ABBEY, LONDON, S.W.19

Telephone: LIBERTY 1085 & 1086

BIRD'S

SPURS, HELICALS AND BEVELS

Quick delivery for cutting only customers' blanks.

**W. H. BIRD
& SONS, LTD.**

St. Philips,
Bristol, 2
Phone: 77033
Grams: OISEAU
BRISTOL




GEARS

Bristol

**INSTANT, EASY
CUTTING-OFF**

**WITH
Ballinger**

WET-TYPE ABRASIVE WHEEL CUTTING-OFF MACHINES



ILLUSTRATING TYPE 'A' FULLY AUTOMATIC SINGLE BAR HYDRAULICALLY OPERATED MODEL.
CAPACITY 3 in. SOLID BAR WITH 16 in. WHEEL.

This wet-type machine can be supplied with fully automatic single or triple bar stock feeds. Long wheel life. Clean, cool, fast cutting. Fitted with Eccentric Wheelhead for cutting difficult alloys. Full range of models available. Ask for details.

L. J. H. BALLINGER LTD.

WOODCHESTER, STROUD, GLOUCESTERSHIRE

Phone: AMBERLEY 2186/7

When answering advertisements kindly mention MACHINERY.



Planning a New Factory?

Reorganising Production?

Moving Plant?

***Consult WARDS
F.P.I. Department...***

... a service which ensures speedy and efficient Industrial "housemoving" with minimum loss of production. No transfer of machinery or factory re-organisation is so small that it does not demand planned attention; no jobs are too big or too small to be outside the scope of this department's activities.

Write for the leaflet:—"Factory Planning and Installation".

THOS. W. WARD LTD

FACTORY PLANNING AND INSTALLATION DEPARTMENT

ALBION WORKS • SHEFFIELD

Phone: 26311 (Ext. 281) Grams: "Forward, Sheffield"

LONDON OFFICE: BRETTENHAM HOUSE LANCASTER PLACE STRAND W.C.2. PHONE: TEM. 1515

F.P.I. 25

When answering advertisements kindly mention MACHINERY.

THE FASE MANUFACTURING CO. LTD

35/51 HANGER LANE, EALING, LONDON, W.5

Telephone: PERivale 4760/9825

- ★ FOR ROD, TUBE, BAR & SHEET STORAGE
- ★ SHELVING, BINS, WORKSHOP TRAY & PANS
- ★ WORKSHOP BENCHES & BENCH TRESTLES
- ★ FABRICATION OF STEEL ANGLE FLAT & CHANNEL
- ★ STEEL PARTITIONING ★ SLOTTED STEEL

If you've a storage problem

FASE CAN HELP YOU SOLVE IT

IF IT'S IN STEEL—WE MAKE IT!

Send us your requirements

MARLOW

**Mk. IV VERTICAL
MILLING MACHINE**

- ▶ SWIVELLING AND DOWN FEED HEAD
- ▶ LARGE CAPACITY
- ▶ TABLE 28" × 8"
- ▶ 6 SPEEDS 85 to 1450 r.p.m.
- ▶ SPINDLE TO TABLE 20"
- ▶ HEIGHT 80"

MARLOW Models

MK IV (Illustr.) £285

MK I 22" × 6" £198


MK II 28" × 6" £210

MK III 28" × 8" £225

VICTA ENGINEERING CO

Offices:
Thicket Corner, Maidenhead
Tel 59 and at: Eagle Works,
Chester Rd. Borcham Wood,
Herts.

Tel: Elstree 3146



TOOLING SERVICE

★
Designers & Manufacturers of
JIGS · FIXTURES
PRESS TOOLS
GAUGES · MOULDS
and
**SPECIAL PURPOSE
MACHINES**

★
**RATCLIFFE
TOOL Co. Ltd.**

GORST ROAD, LONDON, N.W.10.

Telephone: ELGar 6693


and at
COED COCH RD., OLD COLWYN, N. WALES

Tel: COLWYN BAY 55288

A.I.D.
Approved

A.R.B.
Approved

When answering advertisements kindly mention MACHINERY.




why pick on us?

We're just the type for Imperial Typewriters.

They picked on us to cast the aluminium side plates for their new typewriter because they knew we'd do it quickly, cheaply and well. Imperial Typewriters are just the type for us.

They wanted quantity production of the type of casting for which we are well equipped. If that's the type of job you want done — pick on us.



the whole in one


BRITISH DIE CASTING AND ENGINEERING CO. LTD.

EDWARD ROAD · NEW BARNET · HERTS · TEL : BARNET 9211
ALSO AT WEST CHIRTON TRADING ESTATE · NORTH SHIELDS
NORTHUMBERLAND · NORTH SHIELDS 2100



CRC 37

When answering advertisements kindly mention MACHINERY.



**Quality
turned
parts**

- ★ All Materials— Stainless & High Tensile Steel, Nylon, Tufnol, etc.
- ★ Small Gears— spur, Sprockets, Ratchets, Bevels, etc.
- ★ Grinding, Heat Treatment, Plating.
- ★ 50-5000 Quantities a speciality
- ★ All enquiries promptly handled
- ★ A.I.D. approved, On M.O.S. Lists.

S.M.E.C. LIMITED 
 STEYNING • SUSSEX • ENGLAND Phone STEYNING 2228


*your problems are
our business -*

**PRESS
TOOLS**

JIGS

FIXTURES

**SHEET METAL
ENGINEERING CO. LTD.**
 BRIDGE STREET, MORLEY Nr. LEEDS
 TELEPHONE: MORLEY 1065-67 ALSO AT SHIPLEY, YORKS.




REMEMBER!

TAL

for

**PRESSURE
DIECASTINGS**

**ZINC B.S. 1004 OR ALUMIN
LARGE OR SMALL**



Enquiries to

T.A.L. DEVELOPMENTS LTD.

BROADWATER WORKS, GARMAN ROAD, TOTTENHAM, N.17
 TELEPHONE: TOTTENHAM 2732/3

COXETER

Revolving Centres




- Models for Bar or Tubular work
- Standard sizes, morse taper and parallel shanks
- Best Cast Steel construction hardened and ground
- Heavy duty bearings
- Especially suitable for heavy cutting with tipped tools
- Special sizes quoted for
- Quick deliveries

IMPROVED TYPES
 Price list on application

REVOLVING CENTRES LTD.
 40-41 PARK END STREET, OXFORD
 Phone: OXFORD 2275/6 Grams: COXETERS, OXFORD

When answering advertisements kindly mention MACHINERY.



JONES - SHIPMAN

model **540** surface grinder
6" x 18" capacity

With a world-wide reputation

This unique machine has all the essential qualities for high class surface grinding.

It is without doubt the best known machine of its kind in the world, thousands are in use giving first class performance and trouble free service.

Full details are given in Brochure 183Z available on request.

A. A. JONES & SHIPMAN LTD.

Narborough Road South, Leicester.

Tel. 823222.

Telegrams: "Chuck" Leicester.

London Office: Murray House, 5 Vandon Street, Buckingham Gate, S.W.1. Tel: Abbey 5908/9

When answering advertisements kindly mention MACHINERY.

SPEED OUTPUT - CUT COSTS WITH



FRANBER - RHODIUS

FLEXIBLE BONDED

GRINDING DISCS

The new Flexible Bonded grinding - wheels by Franber-Rhodium are unequalled for fast cool grinding and cutting. Being highly flexible, they are virtually unbreakable, and, therefore, safe in use.

DISINTEGRATION OR FRACTURE—WITH THE ATTENDANT DANGER TO OPERATORS AND ADJACENT WORKPEOPLE—IS ALMOST IMPOSSIBLE WITH FRANBER - RHODIUS GRINDING WHEELS



There are FR depressed-centre grinding discs and cutting-off wheels specifically designed for all ferrous and non-ferrous metals.

FRANCIS W. BIRKETT & SONS LTD., CLECKHEATON, YORKSHIRE. Tel: 961 2/3.

SCREWTINIZE

**YOUR
PRODUCT**



Collars, distance pieces, rollers etc. hardened and ground on all faces, with honed bores if required. Catalogue of Standard Collars with pleasure.

PREMIER

SCREW & REPETITION CO. LIMITED.
WOODGATE, LEICESTER. TELEPHONE: 25691 5 lines



**OF EVERY TYPE
IN ALL MATERIALS**

quotations by return—consult

SPINNING & SHEET METAL (GUILDFORD) LTD
12 North Place, Guildford, Surrey


TELEPHONE: GUILDFORD 62420

When answering advertisements kindly mention MACHINERY.

Swinging to Clayton



One of two Clayton wall cranes especially designed to fit into a handling scheme used in the turbine assembly bay of British Thomson-Houston Ltd. Two overhead electric travelling cranes of 75 and 150 tons capacity, on gantries one above the other, take care of the heavy lifts involved in turbo construction and the two travelling wall cranes are provided for general assembly work on the turbo alternators.



In addition to the above equipment over 100 Clayton Electric Hoists have now been supplied. 80 of 2 tons capacity are fitted on radial jib cranes and most of these have the Clayton micro speed units for precision handling.

CLAYTON

CRANES

AND ELECTRIC HOISTS

MAY WE SEND YOU CATALOGUES?

THE CLAYTON CRANE & HOIST CO. LTD.

(DEPT. 16) IRWELL CHAMBERS EAST · UNION ST · LIVERPOOL

Telephone: CENtral 1141 (4 lines) Telegrams: Claymag, Liverpool

London Office:

12 Duke Street, St. James's, S.W.1. Telephone: Whitehall 6988

When answering advertisements kindly mention MACHINERY.

DURABLE

Collapsible THREADING TAPS


Stationary and Rotating Types

- Also: Adjustable Taps
- Adjustable Cutter Heads
- Centre Setting Gauges
- Special Tools, Jigs, Fixtures, Etc.

DURABLE TOOLS LTD.

81-89, AVENUE PARK STREET, GLASGOW, N.W.

Telephone: Maryhill 2344
Telegrams: Durable, Glasgow



**JIG BORING ON
No. 4G "SIP" JIG BORER**

Fit the thread to the job!

Makes soft threads hard
Gives new threads for old

Made in high carbon
steel for use in
aluminium and
magnesium
also in stainless
and bronze for
other applications



Details and samples on request—
CROSS MANUFACTURING CO. (1933)
Ltd.

BATH, SOMERSET. Tel. Combe
Down 2355-8
Grams: Circle BATH

SPECIALISTS IN THE MANUFACTURE
OF JET ENGINE LABY-
RINTHS, CIRCLIPS, SPRING
WASHERS, SPRINGS, ETC.

CROSS
THE BRITISH
WIRE THREAD
INSERTS

CUT COSTS IN KEYWAYS



KEYWAY BROACHES

Cut perfect taper or parallel Keyways with any type of hand press, without skilled labour or elaborate set up. No. 1 set for $\frac{1}{8}$ "- $\frac{1}{4}$ " with guide diameters $\frac{1}{8}$ "- $\frac{1}{4}$ ". No. 2 Set for $\frac{1}{8}$ "- $\frac{1}{4}$ " with guide diameters $\frac{1}{8}$ "- $\frac{1}{4}$ ". Broaches and guides are interchangeable for non-standard Keyways.

W. H. MARLEY & CO. LIMITED

NEW SOUTHGATE WORKS, 105 HIGH RD., LONDON, N.11

TELEPHONE: ENTEnterprise 5234, 5578

When answering advertisements kindly mention MACHINERY.

Yate Company announces new projects

MACHINE TOOL STOCK ROOM FOR LONDON

Continental and English machines on show

Newman Industries Limited of Yate, Bristol, have announced the opening of a new London stockroom. Situated in Monkton Street, Kennington, the building is within easy reach of Kennington and Lambeth North underground stations.

Eventually Newman will have on display at this stockroom a representative range of all the new machine tools for which they hold selling rights in the U.K. Already on show are an MVE Centre Lathe, TOS Vertical Spindle Surface Grinder and Centreless Grinder, a TECHNOIMPEX Milling Machine, a PFEIFER Horizontal Borer and HEID Copying Lathe, Planer Drive and Clutches. It is hoped that a ROCCO Horizontal Boring Machine from Italy will shortly be on show.

Anyone requiring fuller information or wishing to view these machines should contact Newman at their London Office. Telephone Sloane 8206.

Quarter of a million miles by car

This year technical representatives of the Newman Machine Tool Division have travelled nearly a quarter of a million miles buying and selling new and secondhand machine tools. This figure excludes air and rail travel and journeys abroad to the various continental manufacturers for whom Newman are sole agents. It is expected that the present boom in production will mean a bigger mileage than ever in 1959.

Complete Rebuilding Service

There is still some capacity for rebuilding at Yate where over 40,000 square feet of floor space is set aside for this purpose. Machines are rebuilt to Schiesinger limits and guaranteed for six months. Typical detailed planning sheets showing how each rebuild is planned down to the last nut and bolt may be obtained on application to the Newman Head Office at Yate.

BETTER INFORMATION SERVICE

In the belief that engineers today have a morning mail overloaded with often quite irrelevant material, Newman Industries have adopted a system which will reduce this irritation.

The Company has sent out a prepaid postcard to a large number of Machine Tool buyers, listing 25 classifications of new and secondhand machinery and asking that the recipient should tick only those classifications in

which he may be interested. The information gathered will enable Newman to circularise details of tools and services more quickly and selectively than was before possible.

Companies who have not received a card and wish to be placed on the mailing list are invited to write to Newman Industries Limited, Yate, Bristol now.

Newman

FOR
MACHINE
TOOLS

ROCCO FOR NEWMAN

The Italian machine tool manufacturers ROCCO have given sole selling rights in this country to Newman Industries Limited.

It was announced from the Machine Tool Division that the ROCCO Horizontal Boring and Milling Machine, a big success at this year's Milan Fair, should prove just as popular in Britain.

STOP PRESS

MITCHELLS of Keighley have appointed Newman one of their U.K. Distributors for their range of centre lathes.

The first ROCCO machine to be imported, Type AL76 (3in. Spindle) sells at £5,250 inclusive of import duty. The machine has, as standard equipment an 18in. facing head; universal milling attachment and arbor support (which can be used for vertical milling); high precision scales; adjustable verniers; dial indicators for vertical and horizontal traverses and screwcutting. Many other attachments are available as extras. The machine has an indexing table of 48in. by 36in. and spindle speeds up to 1,500 r.p.m.

When answering advertisements kindly mention MACHINERY.

Follow the example of
LEADING MANUFACTURERS

We **Guyson**



We specialise in the manufacture of light sandblast cabinets designed to work where your production can be most conveniently served—right on the job. Your choice may be selected from Bench or Floor Models, small or larger, tailor-made for every industrial requirement in the Laboratory, Tool-room, Production Bay or Repair Depot. There's an excellent return on your investment when using Guyson Shotblast Equipment. Please write for Bulletin 275 fully describing the Guyson Range.

Light Industrial SHOTBLAST EQUIPMENT

* REMOVES

RUST AND SCALE

* CLEANS

CASTINGS OF EVERY
KIND

* MATT FINISHES

COMPONENTS IN
METAL, PLASTIC AND
GLASS

Guyson Regd

INDUSTRIAL EQUIPMENT LIMITED

NORTH AVENUE • OTLEY • YORKS Tel: 2456 • Grams 'GUYSON' OTLEY

**WHO SAID
REPETITION GREY
IRON CASTINGS?**

**From
1 oz to 1 cwt**

When the call is for Grey Iron Castings, Henley Foundries can answer it . . . Swiftly, Economically

- Good Machining Properties • High Dimensional Accuracy
- First-Class Finish and Appearance • Repetition Work a Speciality

HENLEY FOUNDRIES

All enquiries to: HENLEY FOUNDRIES LTD., BANNER'S LANE, CRADLEY, CRADLEY HEATH, STAFFS. PHONE: CRADLEY HEATH 66901

The equivalent of

NEW LEAD SCREWS FOR OLD

Pitch correction of any lead screw, traverse screw, etc., under 3in. diameter to within Schlesinger limits. Maximum delivery 7 days. Certified accuracy graph provided.

PRICES FROM 5 GNS. TO 12 GNS.

**HALIFAX RACK & SCREW CUTTING
COMPANY LIMITED**

Coronation Works • Ovenden • HALIFAX. Tel. 62078/9

maximum air flow—
lowest air drop—
positive air seal—
one hand operating—

$\frac{1}{8}$ " $\frac{1}{4}$ " sizes b.s.p. male and female connections

B&W **INSTANTAIR** couplings

write for leaflet to:


B.E.N. PATENTS LTD. (Division of Broom & Wade Ltd.)
C.F303 DEPT. C.I., HIGH WYCOMBE, BUCKS



He's right, of course!

Spectra-Blue Spectra-Orange
Spectra-Red Spectra-Brown
Spectra-Pink Spectra-Green
Spectra-Grey Spectra-Magenta
Spectra-Yellow Spectra-Seagreen
Spectra-Violet
Spectra-White Spectra-Black

What our Buyer says about those Storekeepers who can't keep their stock in simple fashion is not for publication. But then, he's proved how easy it is to use a colour system for checking stocks, marking tools and generally speeding work in the stores. With SPECTRA-COLOR he has the simple answer to all his identification problems. Just think of the combinations you get from thirteen colours—and two grades (Standard for all bright metals, Opaque for black metals and unmachined castings). What he likes is the permanence of SPECTRA-COLOR. Brushed or sprayed on, it will not chip, peel, crack or smudge and is unaffected by oil, water or petrol. The time he saves, and the space he uses to far greater advantage, is amazing. Of course, he's right! Why not send for samples and see for yourself—then pass it to the Works Manager, he'll be every bit as interested.



SPECTRA-COLOR

... comes in pints, quarts, half gallons and gallons

SPECTRA CHEMICALS LIMITED

Spectra Works, High Street, Caterham, Surrey. Tel. Caterham 3182, 2293, Grams. Spectra Caterham

When answering advertisements kindly mention MACHINERY.

*I'M STRETCHLESS— FLEXIBLE—
RESISTANT TO OIL, WATER & SOLVENTS*

I'M **HEVAFLEX**

*THE ENDLESS WOVEN
NYLON & NEOPRENE BELT*


- ★ EXTREMELY FLEXIBLE
THICKNESS ONLY ONE MILLIMETRE
- ★ RUNS UP TO 10,000 F.P.M.
- ★ HIGH TENSILE STRENGTH FOR
MAXIMUM POWER OUTPUT
- ★ 5 TO 6 TIMES LONGER LIFE
THAN CONVENTIONAL BELTS
- ★ LENGTHS FROM 10ins. TO 150ins.
IN ANY WIDTH UP TO 12ins.



F. U. (LONDON) LTD.

MAGNA ROAD
WIGSTON, LEICESTER. Telephone. WIGSTON 3519

SUSSEX



SERVICE IN PRECISION RUBBER MOULDINGS



Moulded components in Natural, and all types of Oil
Heat and Chemical Resistant Synthetic Rubbers. Backed
by modern Laboratories, and 50 years of progressive
research and manufacture, it is best made in rubber
it will be better made by "Sussex."

SOLE EXPORTERS: COLLETT & CO. LTD. LONDON, N.W.11

*now
on the press*
MACHINERY'S
ANNUAL
Buyers' Guide
1959
EDITION

*the
standard
reference
book
for
buyers
of all
plant
equipment
and
materials
for
engineering
shops*

1000 pages giving the
names, products and
trade names of over
4000 firms

**order your
copy now**

Available JANUARY 1959

**TO MACHINERY (Book Department)
National House, West St. Brighton 1**

Please send a copy of MACHINERY'S
ANNUAL BUYERS GUIDE (30th edition)
on publication. Price 12/6 post free

NAME

SIGNATURE

ADDRESS

DATE.....

When answering advertisements kindly mention MACHINERY

could you use the skill of 100

Rotheroe & Mitchell Ltd., have expert facilities for the development, design, tooling and testing of all types of equipment, including electronic apparatus.

If you are having difficulty in meeting delivery promises, why not take advantage of our service, after all sub-contracting has been our business for 21 years.

Write or telephone for further details today.

engineers?


There is no reason why you shouldn't. That is the experience and skill you have at your service when you contact Rotheroe & Mitchell Ltd., and that is a very sound move if you are concerned with the making of precision components from bar or castings, or the manufacture and assembly of complete equipments in the Instrument and Electro-Mechanical field.

ROTHEROE & MITCHELL LTD

Electrical and Mechanical
Instrument Makers


Aintree Road, Perivale, Middlesex Tel: PERivale 2238-9

IF YOU MAKE THESE



With these products, when rivets need to be headed close up against an angle or shoulder and when tight or loose heads are needed, the T.T. Rotary Vibrating Rivetting Hammers should be your choice. The range copes with rivets from under $\frac{1}{8}$ in. to $\frac{3}{4}$ in. diam. in mild steel. Send us a sample of your product for completion. Snaps, anvils, tables and fixtures to suit requirements can be supplied.

YOU NEED THIS



TURNER

MACHINE TOOLS LTD
62-68 PRINCIP ST BIRMINGHAM 4

Tel: Aston Cross 2244.

Illustrated
R.H. 38 M.D. Standard
Machine ($\frac{3}{4}$ in. capacity).

NYLON

Always in Stock

NYLON

*In Rod
Tube, Sheet
or
Tape Form*


NYLON

Also manufacturers of
**GEARS, BUSHES, BEARINGS
AND ROLLERS IN NYLON**

Gears cut in all materials from one off to a production run; Blanks supplied in Texolex, Nylon and non-ferrous metals; Gears cut from customer's own material; Reduction Gear Boxes from 5-1 to 80-1.

BRITISH RAWHIDE BELTING CO. LTD.
246 GT. PORTLAND ST., LONDON, W.1

Telephone: EUSton 6404
and at 15, Paradise St., Liverpool, 1.



ARBOGA

VERTICAL MILLING MACHINE

MODEL EM 825

Fills an outstanding requirement for small work.

- Table, 17½ in. by 9½ in. or 22 in. by 9½ in.
- Longitudinal traverse, 11 in. or 15½ in.
- Eight speeds, 100 to 2,900 r.p.m.
- Table to Spindle 20 in.
- Swivelling head, Rigid Column, Cast-iron base, No. 3 Morse Taper, 1 in. bore.
- Price: £265, 17½ in. table. £277 10s., 22 in. table.

DISTRIBUTORS AND STOCKISTS FOR THE UNITED KINGDOM.




MORTIMER
ENGINEERING CO. LTD.
POORHETTERS - SQUITTENMAN & CO. LTD.



Showroom & Sales: 204-206 Acton Lane, Harlesden, N.W.10. Tel. ELG 3834

RAYNER POWER DRIVES



½ H.P. 400 to 2,000 r.p.m. infinitely variable



Infinitely Variable 3 H.P. 18 to 94 r.p.m.

**COMPACT PURPOSE-MADE
POWER DRIVES ARE OUR BUSINESS**

PETER RAYNER LTD RAYNER

121 WHITEHALL RD · LEEDS 12 TELEPHONE: LEEDS 33864

We can send this to you NOW!..


MYFORD SUPER 7 Lathes

Full details from

F. W. KUBACH LTD. (Dept. F)

12 Sylvan Road, London, S.E.19

Telephone: LIVINGSTONE 331112



Maher...

a name to remember when disposing of your surplus stocks of
HIGH SPEED & ALLOY STEEL BARS

ALSO
**TUNGSTEN MOLYBDENUM
NICKEL TITANIUM**

**COBALT
SCRAPS & RESIDUES**

HIGHER PRICES FROM THE SPECIALISTS

J. W. MAHER & SON LTD.

Scrap Department, Edward Street, Sheffield 3, England
Phone: Sheffield 27976 Cables: Jomab, Sheffield

When answering advertisements kindly mention MACHINERY.

The Easiest way to read

**Nine thousand
Nine hundred
and Ninety-nine**

Figures speak clearer than words and, with ENM Counters, very much more accurately. ENM Counters are available for almost every trade and purpose — all built with the inherent fine precision of the instrument maker.

★ Please write for full particulars



BRITAIN'S LARGEST MAKERS OF
COUNTING AND NUMBERING MACHINES

ENGLISH NUMBERING MACHINES LTD

Dept. 9A Queensway Enfield Middlesex

Telephone: HOWard 2611 (5 lines) Telegrams: Numgravco, Enfield




UNIVERSAL JOINTS

Manufactured in a range of 14 sizes to suit shafts from $\frac{1}{4}$ in. - 2 $\frac{1}{2}$ in.



W TYPE DOUBLE


Prices and technical data on application.
On Admiralty, War Office and Air Ministry Lists.



B TYPE SINGLE

THE MOTOR GEAR & ENGINEERING CO. LTD.

ESSEX & CORONA WORKS • CHADWELL HEATH • ESSEX • Phone: SEVEN KINGS 3456-7745 (10 Lines)



A.B.C. 4-WAY TOOLPOST ACCURATELY INDEXING

Supplied to suit any make or size of lathe.
Can be locked in any position regardless of Index.

Sole Manufacturers: **A. B. CREED LTD.**
Little Ilford Lane, London, E.12. Tel: Ilford 0455


London Stockists: Acbars Ltd · Buck & Hickman Ltd · Buck & Ryan Ltd · George Hatch Ltd · Richard Melhuish (London Ltd)
Pander Engineering Supplies Ltd · Pidgen Bros. Ltd
A. H. Ritchie & Co.

SPEEDET **Radius Truing Dresser**

This attachment will produce convex and concave radii up to 3.5in. or (metric equivalent) and will be found to be indispensable where accurate work is required.

British Patent
No. 491589

Full technical details and price list on request.



Tel.: CENTRAL
2807/8/9.
Telegrams:
"MAN-
BOARD"
BIRMING-
HAM.
Telex: 33,380
R.G.B. TOOLS
B'HAM.

R.G. BOARDMAN (TOOLS) LTD.

44, SUMMER ROW, BIRMINGHAM 3.

These PARALLEL ACTION Pliers are FIRM FAVOURITES with all TRADESMEN

END CUTTING
NIPPER
No. 301



FLAT NOSE
PLIER
No. 406



SIDE CUTTING
PLIER
No. 405



CLAMPING
PLIER
No. 479



SNIPER NOSE
PLIER
No. 433



MAUN INDUSTRIES LIMITED MANSFIELD, NOTTS.

STEEL FABRICATION SPECIALISTS

—GUILLOTINING—ROLLING—
—PROFILING—WELDING—
—MACHINING—

C.F. IDE
ENGINEERING LTD.

EMPIRE WORKS, 163 CLARENCE STREET,
KINGSTON-ON-THAMES

Telephone: KINGSTON 6820

Jefco *Face Screen*

REGISTERED DESIGN
751914

PERFECT PROTECTION WHEN GRINDING OR
MACHINING, COMFORTABLE TO WEAR.
STANDS CLEAR OF THE FACE
ADJUSTABLE TO ANY ANGLE.


Obtainable from all Engineers Merchants
or direct from:—

J. & E. FERRIS LTD.

33 MUSEUM ST., LONDON, W.C.1.
Telephone: Museum 2876

Also Jefco face screen for Motor Cyclists
Non-Splinter front easily renewable





As simple as ABC!

You will find it well worthwhile to study the David Brown Radicon Worm Reducers for yourself. Our catalogue No. 387-96 contains fullest information on these

"go-anywhere, do-anything" reduction units, including ratings, mounting positions, efficiency, etc.

Why not send for a copy to-day? Bear in mind, too, that advice from David Brown, the gear experts, is always readily available to you.

RADICON



WORM REDUCERS

1½ 15 2¼


40 alternative mounting positions

64 ratios 5:1 to 3600:1

Highest Value at competitive prices



Also available
as motorised units



THE


DAVID BROWN

CORPORATION (SALES) LIMITED

LONDON GEAR DIVISION Stonebridge Park Works Nth Circular Road London NW10 Elgar 6824

BRITISH
MADE

Calibrated
dial and
lead screw



'CENTEC' 2

Universal Precision Milling Machines with

① ② ③ Possibilities of table movement

ALL GEARED 6 spindle speeds

① 4 Power feeds


② Capstan handle
rack and pinion

With big advantage of fast table approach by Capstan Handle followed by automatic feed on cut and fast return by Capstan Handle.

Index table
Dividing head
Quick-action
swivel vice
Rotary table

Table
working surface
2A—16in. x 4½in.
2B—25in. x 5in.

Long
Traverse
8in.
13in.



Vertical swivelling head for MILLING
and DRILLING at all angles.

CENTEC MACHINE TOOLS LTD

Hemel Hempstead, Herts.

Telephone: Boxmoor 584-5-6

Cut SET-UP COSTS!




ALL SIZES
DELIVERED
EX-STOCK

Change to ROCKWELL HELICAL CLAMPS

BRITISH PATENT

Why waste time building up rickety, makeshift clamps with anything that's handy? Get on the phone today and ask for full information about Rockwell Helical Clamps. These ingenious clamps have been designed for simple quick and positive mounting, with negligible clamp projection over work piece. Each clamp is a complete unit, with no parts to lose.



• WRITE OR PHONE FOR LEAFLET GIVING PRICES
SIZES AND FULL TECHNICAL DETAILS
-TODAY!

WELSH HARP, EDGWARE ROAD,
LONDON, N.W.2. GLADSTONE 0033

ROCKWELL
MACHINE TOOL CO. LTD.

Also at Birmingham—Springfield 1134/5. Stockport—Stockport 5241
Glasgow—Merrylee 2822

SC 5

"COVENTRY"

WET TOOL GRINDER

Specially designed for tungsten carbide tools, one wheel for roughing and one for finishing. Large diameter ball-bearing spindle. Sturdy construction throughout, with self-contained motor drive as shown. Write for full details.

CENTAUR TOOL WORKS
EYRE ST., SPRINGHILL BIRMINGHAM
Phone EDGBASTON 1118/9. GOWAN CAPSTAN BIRMINGHAM



A.I.D.
D.I. Arm
A.R.B.
Approved

PRECISION Engineers

Capstan auto and centre lathe turning
Horizontal and vertical milling
Drilling and tapping

Centreless surface and internal grinding
Case-hardening and stove enamelling

Own Design and Drawing Office,
Toolroom and Experimental Department

**Machining specialists in stainless and
various high tensile steels**

SCREW MACHINE PRODUCTS LTD

Woolburn Green · Near High Wycombe · Bucks
Telephone : BOURNE END 111




ELECTRIC FORK LIFT TRUCK

LOAD RATING
1500 lbs.
at 15 inch centres

- Lifts to 9 feet
- Turns in own length
- Heavier mast assembly

Model
E 650
Mk III



ELECTRIC
BATTERY
OPERATED

This "WRIGLEY" Fork Lift Truck incorporates many new and improved features, ensuring far greater efficiency and trouble-free operation. Excellent manoeuvrability in premises with limited space, narrow gangways and passages or through doorways with low headroom.

SEND FOR ILLUSTRATED LEAFLETS

WESSEX INDUSTRIES (Poole) LTD
WEST STREET POOLE DORSET

TEL: POOLE 2000

When answering advertisements kindly mention MACHINERY.

CLASSIFIED ADVERTISEMENTS

RATES : PLAIN ADVERTISEMENTS Except " Situations Wanted " (ALL TYPE) : 2/2 per line. MINIMUM 8/8 (4 lines) OR £1 8s. 2d. per inch (13 lines per inch). Box Nos. 1/3 extra per insertion. SITUATIONS WANTED : 1/8 per line. MINIMUM 6/8 plus 1/3 Box No. SPECIAL DISPLAY TYPE (with or without Blocks) : ☆ p. £1 10s.; † p. £3; ‡ p. £6 or £2 per inch (min. 3in.). Series rates on request.

CONTRACT WORK

DESIGNS

PRECISION PRODUCTS
(ROMFORD) LTD.

TOOL DESIGNERS
AND MANUFACTURERS

For all your needs

JIGS - FIXTURES
GAUGES - PRESS TOOLS
FORM TOOLS AND
SPECIAL MACHINES

Viking Works, London Rd.,
Romford, Essex. Tel : Romford 61921

ESTD 1889

R-STEPHENS & SON LTD

PRESS TOOLS - JIGS
FIXTURES - MOULDS
GAUGES - DESIGNS


115 CHURCH ROAD
UPPER NORWOOD
LONDON S.E.18

PHONE
LIVINGSTONE
2265-6

EXTRA LARGE TOOLS?

I'm sure we can help. Don't forget we specialise in DESIGN and MANUFACTURE of tools of all kinds.

VERO PRECISION ENGINEERING LIMITED
Regents Park, Southampton
Tel : 71061-4



PRESS TOOLS
LAMINATIONS-COMBINATION-PROGRESSION, ETC.

JIGS-FIXTURES-PROTOTYPE and PRE-PRODUCTION MACHINING

Designing-Short Order Work-Sub Assemblies Completely Toolled

JIG BORING AND PRECISION GRINDING LANDEN (ENGINEERS) LTD.

1a, Aubert Park, Highbury, London, N.5
Phone : CANbury 1075



INFINITE CAPACITY FOR ABSORPTION

'ABBEY' CAN HANDLE ALL YOUR DESIGNING PROBLEMS

We can absorb your overload with our rapid and competitive design and manufacturing services. We specialise in transfer and special purpose machines, auto tooling, jigs and fixtures, press tools, plant layout and factory services.

Members of the Federation of Engineering and Design Consultants

THE ABBEY TOOL CO. LTD.

CHURCH HILL COLESHILL BIRMINGHAM TEL : COLESHILL 3276
109 FISHERGATE PRESTON LANCs TEL : PRESTON 2309

Presswork Up to 50 Tons, In-
cluding deep-drawing. Long or short runs. Customers' tools and materials acceptable. Tooling and designing.—BIRCH & JACQUES (TOOLMAKERS), LTD., Hershams Trading Estate, Walton-on-Thames. Tel.: W-on-T 5379.

Presswork Up to 40 Tons, Circu-
lar and surface grinding on latest J. & S. machines. Tools designed and made for the trade or your article produced throughout in our works. A.I.D. approved. Enquiries welcomed.—WEMBLEY TOOL CO., LTD., 2, Bridge Road, Willesden, N.W.10. WIL. 6667/8.


ENGINEERING BUYERS NEED MACHINERY'S ANNUAL BUYERS' GUIDE

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

C.B. POWELL LTD ESTD 1945
PHONE: 71144

DESIGNERS OF
ENGINEERING
PRODUCTION
EQUIPMENT



SPECIAL M/C'S
FIXTURES
JIGS & TOOLS
GAUGES

1 ST. JOSEPHS CLOSE
HOVE • SUSSEX



DESIGN & PLANNING

PRESS TOOLS
JIGS & FIXTURES
SPECIAL PURPOSE M/C'S
DIECASTING MOULDS
PLASTIC MOULDS
PIPING, DUCTING, ETC

W.R. SOUTHWELL (DESIGNS) LTD
30 ST. DUNSTONS HILL, CHEAM
SURREY • Phone: FAIRLANDS 3617 E 7548


Export Enquiries Invited

TOOL DESIGNERS & MANUFACTURERS

JIGS FIXTURES
PRESS TOOLS
SPECIAL MACHINES
JIG BORING
AND PROTOTYPE WORK

**WILLIAM ATKINS
(COVENTRY) LTD.**

Specialists in
Turbine Blade
Tooling
Layout
and Lofting



203/269
Foleshill Road
Coventry
Tel: Coventry 62568

•••GEARS•••

GEARS We are Specialists

Experienced Gear cutters at your service
No need to let a gear problem stamp you
Expert knowledge at hand
Rapid delivery from customers' own blanks
All gears cut, or made complete to your requirements
Trust your gear-cutting to us (over 30 years experience)
Every satisfaction assured
Do send your enquiries, large or small, prompt attention given

F. M. ILLICH (GEARS) LTD.
4A JAMESTOWN ROAD, LONDON, N.W.1

Tel: Gulliver 5046

SPIRALS • SPURS WORMS & WHEELS • BEVELS • SPROCKETS
CAPACITY LIST ON APPLICATION



When answering advertisements kindly mention MACHINERY.

CAPACITY AVAILABLE FOR DESIGN AND MANUFACTURE OF SPECIAL PURPOSE MACHINES

ALSO
MACHINING CAPACITY ON
CENTRE LATHES, CAPSTANS,
GRINDING, DRILLING & MILLING
MACHINES.

MOORE & ELLIS
(LONDON) 1946 LTD.
61, UNION STREET, BOROUGHS, S.E.1
TELEPHONE: HOP 2504

Spur Gear and Sprocket Cutting

from blanks supplied or machine complete.

Phone: EUSTON 1354.
TURNER BROS.,
10, Pratt Mews, Camden Town, N.W.1.

Gear Cutting, Auto Turret, Capstan
and Centre Lathe Turning, Milling,
Planing, Hardening and Grinding,
Profile Cutting and Welding.

**SMITH & NETHERWOOD,
LTD.**
Tanyard Road, Quarmby,
HUDDERSFIELD.
Phone: MILNSBRIDGE 1865.


IMMEDIATE CAPACITY AVAILABLE

- GEAR CUTTING to 24in.
- THREAD MILLING 6in. by 48in.
- PLANING 6ft. by 2ft. 6in.
- BROACHING

MAURALL ENG. CO.
38-40, Upper Clanton Road, E.S.
Telephone: AMHERST 6163.

Gear Cutting Super Accurate.

Spurs and Spirals to Admiralty class one
specification. Prototype quantities. Very quick
delivery.—NEWPORT ENGINEERING CO.
PANY LTD., Noddy Works, Julian Road
Birling, W.S. Phone: BAILING 3924.



GEARS—PRECISION AND INSTRUMENT MACHINE CUT

Max. capacity 12 D.P. 8-in. dia.
Blanks turned and cut.
SETON CREACHE ENGINEERING LTD.,
TRADING ESTATE, PARK ROYAL ROAD, N.W.10
A.I.D. Phone: ELGAR 3356/7 A.R.B.

Complete production of
GEARS

SPURS · SPIRALS · BEVELS
WORMS · WHEELS · RACKS
SPROCKETS & CLUTCHES

Extra rapid delivery
from Customers own Blanks

A.I.D.
APPROVED

COMPLETE
GEARED
ASSEMBLIES

THE DAVALL GEAR COMPANY LTD.
GEARWORKS · HIGH STREET · POTTERS BAR · MIDDLESEX
Telephone POTTERS BAR 2382-3

SMALL GEARS

ALL TYPES OF SMALL GEARS
UP TO 8in. DIA. 10 to 64 D.P.
ESTABLISHED IN 1880

G. W. EVERY & SONS, LTD.
49, THORNHILL RD., LONDON, N.1. Phone: NORTH 1827

GENERAL ENG'G. •• SERVICES ••

Immediate Capacity Available,
castings, non-ferrous, die, shell moulded,
sand, etc. Also machining and stove-enamel-
ling.—MILLS ENGINEERING PRODUCTS,
LTD., Barnet. Phone: Barnet 6744.

Luton Engineering Pattern Co.
are prepared to undertake the manufacture
of all classes of wood and metal patterns and
accuracy and prompt delivery guaranteed.—
Send your enquiries to 80A, Princes Street,
Luton. Phone 961.

Centre Lathe Turning Up to
74in. centres by 48in. b.c. Tool, Prototype
and small batch work. Modern plant. A.I.D.
approved.—WARD ELECTRIC CO. (NOR-
WOOD), LTD., 44, Chapel Road, W. Norwood,
S.E.27. GIPSY Hill 1620

**FOR
PRECISION MACHINING
FABRICATION PIPEWORK ETC.
WELDING ARGON ARC & GAS
TOOLS, JIGS & FIXTURES
FITTING & ASSEMBLY**

**TRY
PIPEWORK & ENGINEERING LTD.
STANLEY ST. SOUTH, BRISTOL 3.**

**Induction hardening
and brazing, etc. We collect
and deliver**

**Shot blasting.
PRECISION HEATING LTD.**
142A Canbury Park Road, Kingston-on-Thames
Surrey. Phone: KINGSTON 1468

**Thames Valley Pattern Works
LTD.**
ELMTREE ROAD, TEDDINGTON
Phone MOL 698 MOL 6097
**ENGINEERS' PATTERNS
MODEL MAKING
INSTRUMENT CASES
PERSPEX MODELS & MOULDS**

Barrel Finishing. Specialists in
Barrel Finishing. Compounds and media
supplied. Contract work undertaken.—Send
samples to GRANATT CHEMICAL & ENGI-
NEERING CO., Austin Road, Battersea,
S.W.11 MACaulay 7729.

PROTOTYPE & PRODUCTION
ELECTRONIC WIRING, COIL WINDING,
INSTRUMENTATION & TESTING
SETON CREAGHE ENGINEERING LTD.,
G. W. Trading Estate, Park Royal Road,
N.W.10.
A.I.D. ELGAR 3356-7 A.R.B.

Ceramic Grinding Undertaken,
both internal and cylindrical.—BOX
2725, MACHINERY, Clifton House, Euston Road,
N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

P.V.C. Plastic welding

*to the trade for industrial packing and protection.
Cases, Covering, Stationery, etc.
Long and short runs.*

COLARET

Old Station House, 277a, Finchley Road, N.W.3
Phone: HAMpstead 8029

CROYDON TOOL**AND CASE HARDENING SPECIALISTS****EXPERTS IN ALL HEAT TREATMENT OF METALS**

CYANIDE HARDENING · ANNEALING · SHOT BLASTING

KEEN PRICES · WE COLLECT AND DELIVER

UNION ROAD, WEST CROYDON. PHONE: THORNTON HEATH 5222

IMMEDIATE CAPACITY AVAILABLE

Capstan Work up to 1 1/2 in. Bar
and 6 in. Chucking
Milling, Drilling, Grinding
Boring and Assembly Work
Jigs & Fixtures
Also Hardening for the Trade

A.I.D. and A.R.B. approved

B. TOONE
(NOTTINGHAM) LTD
NEWDIGATE ST.
NOTTINGHAM
Tel.: 76661-2-3

STAINLESS STEEL SPECIALISTS

Fabrication, welding and X-ray
inspection, pressings and machined
parts.

THE TAYLOR RUSTLESS
FITTINGS COMPANY, LIMITED,
Ring Road,
Lower Wortley,
Leeds, 12.

A. I. D. ——— **THE** ——— ELGar 5057/8
HEAT TREATMENT
PEOPLE OF LONDON

G.R.M. Heat Treatments Ltd., Coronation Rd., Park Royal, N.W.10

RESEARCH

ENGINEERS LTD.

for PROTOTYPES**DESIGN & CONSTRUCTION OF SPECIAL MACHINERY**

ALSO CONTRACT WORK, MEDIUM AND SMALL PRECISION
MACHINING, GEAR CUTTING AND COMPLETE ASSEMBLIES

NORTHAMPTON GROVE, CANONBURY, LONDON, N.1

Telephone: CANONBURY 4244 (4 lines).

Telegrams: WILMAKET, NORDO, LONDON.

When answering advertisements kindly mention MACHINERY.

REPAIRS

By

WELDING

BROKEN MACHINE TOOL PARTS
& DAMAGED PLANT IN ALLOY STEELS,
CAST IRON & NON-FERROUS METALS
SPECIALLY REPAIRED BY WELDING

ESTABLISHED OVER 40 YEARS

THE BLAKER MOTOR WELDING CO. LTD.*Welding Engineers*

BUKES RD., PARK ROYAL, LONDON W.8

Phone: ACORN 4811. Grams: Blakerweld. Edue: London

DAVIES-CHARLTON (U.K.) LTD.

STATION SAWMILLS, BARNOLDSWICK, VIA
COLNE, LANCs. TEL. BARNOLDSWICK 3310
A.I.D. APPROVED

Are specialists in component
production for the Aero-jet
engine industry, and can offer
capacity on

THREAD GRINDING
THREAD ROLLING

Capstan, Auto and Centre Lathe
turning. External, Internal
Centreless and surface grinding.
Horizontal, vertical and profile
milling. Drilling, Tapping and
Honing.

**QUOTATIONS FOR LARGE OR SMALL
QUANTITIES**

IDEAL**HARDENING CO., LTD.**

DAVIS ROAD, CHEBBINGTON, SURREY

**HEAT TREATMENT
SPECIALISTS
HARDENING OF
EVERY DESCRIPTION
AND SANDBLASTING**

Tel.: ELMBRIDGE 6556-6567

WOOD & METAL

PATTERNS

HAND MACHINE OR SHELL MouldING
Keen Quotations Good Delivery

B. LEVY & Co. (Patterns) Ltd.
1-5 OSBERT ST., LONDON, S.W.1

Telephone: VICtoria 1073 & 7496

Classified Advertisements (CONTRACT WORK, contd.)

INCREASE YOUR CUTTER LIFE UP TO 400%

LET

CARBIDE IMPREGNATION LTD.

(DORSPA LTD.)

IMPREGNATE YOUR CUTTERS, FORM TOOL, REAMERS, ETC.*As recommended and carried out by us for leading aircraft and motor firms*MANUFACTURERS OF SPECIAL
CUTTERS AND FORM TOOLS
TRADE ENQUIRIES INVITED**235, LONDON ROAD, HEMEL HEMPSTEAD**

Tel: BOXMOOR 450

HERTFORDSHIRE**ABBEY HEAT TREATMENTS LTD.**
PLAZA WORKS, HIGH STREET, MERTON, S.W.19
FOR ALL TYPES OF HEAT TREATMENT.
WE COLLECT - WE DELIVER
TELEPHONE: CHerrywood 2291**•• MACHINING ••****AUTO TURNED PARTS**FINE TOLERANCES, MAX. DIA. 1½ in.
INDEX SS & GRIDLEY MULTI AUTOS
THREAD CHASING MANUFACT'RS
ROLLER BOX TOOL HOLDERS**BENTON ENGINEERING CO. LTD.**Tonbridge Road, Harold Hill, Essex
Ingrebourne 43844/5**Thread Milling for the Trade**
up to 6 in. O.D. and 5 in. I.D. Any thread,
any quantity. Keen prices for long runs.
Satisfaction guaranteed.**UNICORN PRODUCTS, LTD.**
119-121, Stanstead Road, Forest Hill, London,
S.E.20. Telephone: Forest Hill 7688 (3 lines).**1½ in. Bar, 4 in. Chucking
AUTO CAPACITY****ECONOMIC PRICES from 500 UP**
made possible by**THE HYDRO COPYING TAREX**
HUNTLEY & SPARKS, LTD., Wandale Road,
London, S.W.19, A.I.D., A.R.B. L18 2446

George Mills (Engineers) Ltd.
119-121, Stanstead Road, Forest Hill, London, S.E.20

Forgings
IN IRON & STEEL
UP TO 11 CWTs.

“AWKWARD”
MACHINING AND GRINDING
WELDING, FABRICATING
PROFILE FLAME CUTTING
AND GENERAL PRESSWORK

A.I.D. APPROVED
SPECIAL PURPOSE MACHINES
REPAIRS & SALVAGE
BY METAL DEPOSITION IN
STELLITE, CHROME, NICKEL ETC.

A.R.B. APPROVED

▶ We are equipped to provide a first-class machine shop capacityPLANING 12 FEET • HORIZONTAL BORING • VERTICAL BORING • RADIAL DRILLING
CENTRE LATHES • COMBINATION TURRET LATHES • HORIZONTAL MILLING
VERTICAL MILLING • GRINDING • DRILLING • WELDING • PROFILING • HONING**D. A. GUNN ENGINEERING LTD**

32 PARK ROAD NORTH • LONDON • W.3 Tel.: ACOrn 4841/4

SEND
US
YOUR
ENQUIRIES*When answering advertisements kindly mention MACHINERY.*

Classified Advertisements (CONTRACT WORK, contd.)

PRECISION TURNED PARTSA.I.D., A.R.B., C.I.A. & I.F.V. APPROVED
AUTO AND CAPSTAN QUANTITIES

Send your specification to:

AYLESBURY TURNED PARTS

(True Screws) Limited

Britannia St., Aylesbury, Bucks.

Tel: Aylesbury 2424 (3 lines)

Automatic Work Up to 1 1/2 in.Immediate capacity available—
TRUE ENGINEERS, LTD.
Wharf Lane, Bourne End, Bucks. 'Phone 1316.**Automatic and Capstan**Capacity Available up to 2 1/2 in. dia.—
WILLIS ENGINEERING, 65A, High Street,
Hampton Hill, Middlesex. Molesey 4273.**Automatic Turned Parts, Press**Work, Press Tool Making, Capstan and
Centre Lathes, Milling, Drilling, Thread Milling.
Capacity available—PARKER ENGINEERING
(KINGSTON), LTD., 200-202, Cambridge
Road, Kingston-on-Thames. KIN. 5501.**Planing Capacity, Heavy or Light**Turning up to 5 ft. diameter.
Special machines to customers' design.
F. ATKINSON & SONS, London, LTD.,
65, King's Cross Road, W.C.1. Terminus 4050.**Immediate Capacity Turning,**capstans, milling, drilling, die and tool
making.—MILLS ENGINEERING PRO-
DUCTS, LTD., Barnet. Tel.: BARNET 6744.**Metal Spinnings. Immediate**capacity for metal spinnings and sheet
metal work. A.I.D. approved.—HIGHBURY
METAL SPINNING CO. (1955), LTD., 30,
Highbury Place, N.5. CANonbury 2906.**Horizontal Production Milling**for the trade. Slots, flats, squares, etc.,
of all descriptions milled on latest plant. Keen
prices for long runs, satisfaction guaranteed.—
UNICORN PRODUCTS, LTD., 110-131, Stan-
stead Road, Forest Hill, London, S.E.23.
Telephone: Forest Hill 7688 (3 lines).**Capstan and Turret Lathe**Capacity available up to 4 1/2 in. diameter
bar and 2 1/2 in. diameter chucking. Castings and
Forgings a speciality. Milling, drilling and
centre lathe turning. High class work with
prompt delivery. Enquiries invited to:—

WHITWAM & ELEY,

22/24, Stafford Road, W.3. Acorn 8364.

Automatic Capacity Availableon Index single spindle autos. up to 2 1/2 in.
dia.—ARTHURS ENGINEERING, Hershams
Trading Estate, Molesey Road, Hershams,
Surrey. 'Phone: Walton-on-Thames 5119.**Capstan Capacity Immediately**available, 6 B.A.—1 1/2 in. Steel or Brass.
Large stocks of raw materials:—
SACEON, LTD.,
7, Chislewick High Road, W.4. Tel. CHISwick 3595**Capstan Capacity Immediately**available 10 B.A. to 1 1/2 in. B.M.S. Stainless
Frame, etc. All materials in stock.—CHISWICK
ENG., LTD., Pluckington Place, Southall,
Middlesex. Tel.: Southall 2247.**High Precision Grinding of**Tungsten Carbide and Steel Tools.
Accurate profile grinding and progression tools
a speciality.—S.T. LTD., 22-26, Upper Mulgrave
Road, Chesham, Surrey. 'Phone: VILlant 0074/5.**FINE LIMIT GRINDING**MILLING, TURNING, DRILLING.
Complete Service Offered.**SETON CRAIGHE ENGINEERING LTD.,**Trading Estate, Park Royal Road, N.W.10
A.I.D. ELGar 3356/7 A.R.B.

Centreless Grinding

ALL TYPES OF FORM, THROUGH AND PLUNGE

BAR GRINDING

1/2 in. to 5 in. DIA. UP TO 15 ft. LONG

IMMEDIATE CAPACITY ON CAPSTAN MILLING
CENTRE LATHES, AUTO AND ALL TYPES OF GRINDING**REDCAR ENGINEERING CO. LTD.**

MOLLY ROAD WORKS, TWICKENHAM, MIDD. Tel. POP 6157 & 7083

A.I.D. & A.R.B.
APPROVED**WE WOULD WELCOME YOUR ENQUIRIES FOR:—**

- MILLING—Horizontal & Vertical.
- BORING—Horizontal & Vertical.
- CENTRE LATHES to 38 in. Dia.
- Cylindrical Grinding to 20 in. Dia. x 84 in.
- CAPSTANS to 2 1/2 in. Dia.
- Surface Grinding to 24 in. x 8 in.
- PLANING TO 6 ft. x 3 ft. x 3 ft.
- Drilling and Thread Tapping.

A.I.D. APPROVED

BOWES ROAD ENGINEERING CO. LTD.

BOWES ROAD, NEW SOUTHGATE, N.11. 'Phone BOW 2284/5/6

E. R. LATTIMER LTDA.I.D. & A.R.B.
APPROVED

Offer Complete Service for
PRECISION PROFILE MILLING, JIG BORING
LIGHT TO MEDIUM COMPONENT MANUFACTURE,
TOOL DESIGN & MANUFACTURE,
SMALL ASSEMBLIES, DIE & MOLD MANUFACTURE,
SMALL PRESSURE DIE CASTINGS
IN HAZAR ALLOY TO B.S. 1064
SUPER PRECISION HYDRAULIC COMPONENTS AND ASSEMBLIES
FOR WHICH WE HAVE HYDRAULIC TESTING EQUIPMENT

SHAKESPEARE
STREET,
SOUTHPORT

Phone: 57696 7

AUTOPRODUCTIONS LTD.Automatics: Single Spindle
Index "18" "24" "36" "52" "B.42"
Multi Spindle: 1 in. and 1 1/2 in. WickmanCapstan
Drilling
MillingCentreless Grinding
Polygon Turning
Chemical Blacking**CAPACITY AVAILABLE**

53, Green St. Sunbury-on-Thames

Phone: 2499

PLOUGH GRINDING

24 hr. Service


High Speed Service Tool Co. Ltd.
Maple Road, Surbiton, Surrey.
Elmbridge 1135-6-7.**ROSSER & RUSSELL LTD.**Queen's Wharf, Hammersmith,
LONDON, W.6.

Telephone: RIVerside 4161.

**GENERAL ENGINEERS
AND
MANUFACTURERS OF
SPECIAL MACHINERY
TO
CUSTOMERS DESIGN**

WE MAKE TANKS, FRAMES, DUCTS, INSTRU-
MENT PANELS AND CHIMNEYS.Let us have your enquiries for welded
fabrications large or small. And we can
press 200 Tons, guillotine 1/2 in. plate,
bend and cylindrical roll.SHELMERDINE & MULLEY LTD.
EDGEWARE ROAD, CRICKLEWOOD,
N.W.2.
GLAdstone 7677-8

When answering advertisements kindly mention MACHINERY.



cam
CUTTING

PRECISION TRACK MILLING OF FACE, BOX & CYLINDRICAL CAMS UP TO 30 INCHES DIAM.

ZEPHYR Engineers Ltd TEL: EUS. 7624
24/32 EUSTON BUILDINGS, LOND. N.W.1

CAPACITY AVAILABLE

TRADE WORK DIVISION
PRECISION

MACHINING of most descriptions
GENERAL ENGINEERING
and
MANUFACTURING
A.I.D. and A.R.B. approved

S. M. STUART-TURNER & CO.
(SURREY) LTD. FAIRVIEW ROAD NORBURY
LONDON S.W.16 TEL POLLARDS 2231/2
GRAMS, "AERQUIP" STREATH LONDON

Immediate Capacity Available,
on single spindle Automatics up to 11in.—
JAN PRECISION SCREWS, 33, Woodthorpe
Road, Ashford, Middlesex. Phone: Ashford 4524.

CAMS

FOR ALL SINGLE SPINDLE AUTOS

APPROX. 48 HOURS DELIVERY

EDWARDS BROS.
51 GEORGE LANE, SOUTH WOODFORD, E.18
TELEPHONE: WENTWORTH 1248

HOLLAND & CAESAR LTD
ENGINEERING CONTRACTORS
GRINDING SPECIALISTS
ORKEY WKS, 3-5 LEIGHTON PLACE,
LONDON, N.W.5
Est. 1836 Tel: GULliver 3047 and 6444

GRINDING
IMMEDIATE CAPACITY AVAILABLE
CYLINDRICAL-INTERNAL-SURFACE
LATEST TYPE MACHINES
PLOUGH GRINDING—24 HOUR
SERVICE

also
General Machining, Fitting
and Complete Assemblies
Special Purpose Machines
Designed and Built
to Specification
We shall be pleased to
advise on your Grinding
and Machining Problems



EST 1890 **CHATER-LEA** MFG. Co. Ltd.

INVITE ENQUIRIES FOR ALL TYPES OF MACHINING, INCLUDING BROACHING, GEAR CUTTING, THREAD ROLLING, GRINDING (INTERNAL, EXTERNAL AND CENTRELESS), ALSO HEAT TREATMENT, PLATING AND FACILITIES FOR TOOLING, CUSTOMERS MATERIAL OR WE WILL SUPPLY.


NEW ICKNIELD WAY, LETCHWORTH, HERTS.

A.I.D. A.R.B. I.F.V. APPROVED TEL: LETCHWORTH 490

When answering advertisements kindly mention MACHINERY.

MACHINING CAPACITY AVAILABLE

PHONE: KIN 6112

CAPSTAN
TURNING
MILLING
DRILLINGSEND US
YOUR
ENQUIRIESTURRET LATHES
CENTRE LATHES
ALL GRINDERS
ETC.GOOD DELIVERIES — QUALITY — KEEN PRICES
W. G. MARSDEN ENG. LTD. 30 FIFE ROAD, KINGSTON, SURREY**PLOUGH GRINDING**24 hour service
Competitive prices**HandA Engineering**
35 Grant Road, Croydon
ADD 2931**MACHINING
ECLIPSE****METAL INDUSTRIES LTD.**
Sedgley Rd. West Tipton • Staffs.GENERAL ENGINEERING WORK
PRODUCTION OR PROTOTYPE
JIGS • FIXTURES • ASSEMBLY
Pressure diecasting in zinc or lead**PRECISION & GENERAL
MACHINING**including
Thread Milling • Radial Drilling
Metal SpinningA.I.D. and I.F.V. Approved. Enquiries invited.
Surplice & Tozer Eng. Co., Ltd.
Acre Works, WindsorWindsor 1657 & 1844
Member of the Metropole Group**Metal Spinnings Produced to**
your requirements. Economically. On
Time. A.I.D. approved.—**MARTIN-GOLOD,**
LTD., Maybury Gardens, N.W.10. WIL 3888.**Cylindrical and Internal Grind-**
ing, max. swing 8in., capacity available.
Close limits. Modern plant. A.I.D. approved.—
WARD ELECTRIC CO. (NORWOOD), LTD.,
44, Chapel Road, West Norwood, S.E.27.
Gipsy Hill 1020.


**AUTOMATIC
TURNED PARTS**

WEST ST. REIGATE
AMBRESSEY
ENGINEERING CO. LTD.

Free cutting mild steel rod available
in most sizes up to $\frac{1}{2}$ in. diameter.
For your orders for turned parts.
Swiss automatic production.
ROBERT PRINGLE & SONS
36-42, Clerkenwell Road, London, E.C.1
Telephone: CLERKENWELL 2341**CYLINDRICAL
GRINDING CAPACITY**External up to 12in. dia. by 36in.
Internal up to 7 $\frac{1}{2}$ in. by 8 $\frac{1}{2}$ in.**MARSDEN & SHIERS, LTD**
Davis Road, Chessington, Surrey.
A.I.D. & A.R.B. A.N.R. Approved.
Telephone: ELMbridge 5333 & 5334**Multi-spindle and Single-spindle**Auto Turning up to 2in. bar capacity
capstan turning from the bar up to 2 $\frac{1}{2}$ in. dia.
chuck work up to 14in. dia., thread miller,
milling, shaping, drilling, etc., capacity available.
Any tolerance and quantity. Satisfaction
absolutely guaranteed.—**UNICORN PRO-**
DUCTS, LTD., 119-112, Stanstead Road, Forest
Hill, S.E.26. Phone: FOREST HILL 7688 (3 lines).**Capstan Capacity Available**
 $\frac{1}{2}$ in. to 14in. Stainless, H.T., B.M.S.,
etc. No quantity too small.—**ACME WORKS,**
Pluckington Place, Southall, Middx. Tel.:
Southall 2247.**Turning, Milling, Grinding and**
Drilling Capacity available.—**POLAR-**
COLD LIMITED, Congleton, Cheshire. Tel.:
Congleton 2401.**• PRESS WORK •****PRESSWORK**PRESS TOOLS
JIGS & FIXTURES
GRAVITY DIES
ASSEMBLIESThe
**THORAN ENGINEERING
COMPANY LIMITED**
SOUTH POTTERIES ESTATE
WHITE HART LANE
TOTTENHAM N.17

TELEPHONE: BOWES PARK 8383

SUB-MINIATURE PRESSINGSand multi-stage precision press work
in all materials
PROMPT DELIVERIES**G. A. PRECISION PRODUCTS LTD**
No. 2 Factory, Darkes Lane
Potters Bar, Middlesex
Potters Bar 6895**Metal Pressings**TO ANY TOLERANCE
SHAPE OR QUANTITYSERVICE and PRECISION
at COMPETITIVE PRICES**ECONOMIC STAMPINGS LTD.**DISABLI STREET, LEICESTER • TELEPHONE 52235
BRANCH OF THE BENTLEY GROUP**Press Work Capacity Available**up to 1,500 tons. Red area 6ft. 6in. by
4ft. Enquiries welcomed.—**GULF RADIA-**
TORS, LTD., Penarth Road, Cardiff.


**PRESSWORK
PRODUCTS LTD**
*Specialists
in Accuracy*

LIGHT PRESSINGS •
DEEP DRAWING •
SPRING
PRESSINGS •

May we help you?
WRITE OR PHONE US AT

STATION WORKS
LUDLOW ROAD
MAIDENHEAD • BERKS
Phone: Maidenhead 700 (3 lines)

When answering advertisements kindly mention **MACHINERY**.



THE FIRM WITH HALF A DOZEN JIG BORERS for PRESS TOOLS etc.

HIGH SPEED SERVICE TOOL CO. LTD.
Maple Road, Surbiton, Surrey. Elmbridge 1135-6-7
STUDER PROFILE GRINDING A SPECIALITY.

Presswork, 25 Tons Maximum,
also Spotwelding capacity available.
Tools made or customers' used. Materials
supplied or accepted.—**SILENT CHANNEL
CO., LTD.,** Metal Products Division, Huntingdon.

Pressings and Stampings, Ltd.,
Eccleston Road, West Ealing, W.12.
Presswork up to 150 tons. Double action deep-
drawing guillotine 8ft. by 10 S.W.G. Spot
welding.—Assembly. Tool making and electro-
plating.—Phone: Ealing 3667-8.

WE DESIGN

AND MANUFACTURE PRESS TOOLS AND DO THE PRESS WORK

A.I.D. & A.R.B. APPROVED

NAISH BROS. & CO. LTD.
124, CHELTENHAM ROAD,
BRISTOL. Tel.: 25532-3

**Pressings in All Metals Up to
60 tons.** Press tools manufactured in our
own toolroom. Light assemblies. Domestic
Electrical and Mechanical. All finishes. A.I.D.
and A.R.B. approved. Advice and estimate
given free. Inquiries to:

METAL COMPONENTS, LTD.,
Dolphin Road, Shoreham-by-Sea, Sussex.
Phone: Shoreham-by-Sea 2224/5.

• TOOLMAKING •

PRESS TOOLS STAMPINGS

JIGS, FIXTURES,
PRESSURE DIES,
GENERAL MACHINING,
JIG BORING, PRESS WORK,
ETC.

Please send your enquiries to

THE MIDDLETON TOOL & ENG CO LTD
ALEXANDRA RD, PONDERS END, MIDDX.
TEL: 0208 40544



COVENTRY GRINDERS LTD

A.I.D., A.R.B. Approved Phone: 73344

send us your Enquiries for

FORM GRINDING GAUGES & TOOLS

The Largest
Stockist of
Precision
Ground
GAUGE PLATE
All sizes from
 $\frac{3}{4}$ in. to 18in.
wide
 $\frac{1}{2}$ in. to $1\frac{1}{4}$ in.
thick
18in. to 48in.
long

PRESS TOOLS

MITCHAM JIG & PRESS TOOL COMPANY LTD

JIG BORING ON 4G SIP JIG BORER
KELLERING · PROFILE GRINDING · DESIGN & MANUFACTURE

GAUGES · SPECIAL
PURPOSE MACHINES

BENEDICT ROAD · MITCHAM · SURREY

Tel: MITCHAM 3635

When answering advertisements kindly mention MACHINERY.



LENCHS
(BIRMINGHAM) LTD
TOOLMAKERS
Barr St., BIRMINGHAM 19.

Literature on request

Sole Manufacturers of:
OAKALOY
CARBIDE TOOLS & TIPS

PRESS TOOLS - JIGS -
FIXTURES

Tel: Northern 8421 (4 lines)

MacDowall

JIGS, FIXTURES
PRESS TOOLS &
GAUGES
PRECISION ENGINEERS
SPECIAL MACHINERY

MACDOWALL EQUIPMENT COMPANY LIMITED
NORTH STREET ROMFORD ESSEX

ROMFORD 61981



PLASTIC
MOULDS
PRESS TOOLS
JIGS
FIXTURES, ETC.

51-53
BICKERSTETH RD.
PITCHAM RD.
TOOTING,
LONDON S W 17

TELEPHONE BALHAM 1006 (2 LINES)

A.I.D. Member of the Gauge & Toolmakers Association A.R.B.

- MOULDS Compression and Injection Plastic
- MOULDS Pressure Diecasting
- MOULDS Rubber and Gravity
- JIG & FIXTURES
- PRESS TOOLS
- PRESS WORK up to 25 tons
- AUTOMATIC & CAPSTAN TURNED PARTS

TO BE PRECISE IT'S
Camdentools
21-22, HONYWOOD ROAD,
BASILDON, ESSEX.
Phone: Basildon 20506/7.

Press Tools, Press Work, Jigs,
Fixtures, Capstan and Auto. Turning
Special H.S. Cutters. Components manufactured
and assembled to specif.—L. PERSON & SON,
63, Shaftesbury Street, N.1. CLE. 7130.

Capacity Available, Press Tools,
Jigs, Fixtures, Production of Metal
Pressings, Prototypes and Jobbing. Light
Assemblies. ELLIOTT & WEST,
587, Liverpool Road, N.7. Phone: NORTH 2366.

PRECONOMY CO LTD

PRECISION

Jigs and Fixtures


MOULDS and Press tools

ECONOMY

Eastfield Side, Sutton-in-Ashfield, Notts

★ **PRESSURE**
DIE-CASTING DIES
PRESS TOOLS - JIGS - FIXTURES - GAUGES
★ **MOULDS FOR**
PLASTICS

SHINDLER ENGINEERING CO LTD
ST. CHADS PLACE, KING'S CROSS, W.C.1 TELEPHONE: TEA 4445 241



JIG BORING
ON GIP JIG BORERS
EDMONTON TOOL & ENG. CO LTD
151, WERTFORD ROAD, EDMONTON N.9
TELEPHONE: EDMONTON 4412/3
SPURS, SPIRALS, BEVELS, WORMS
& WORMWHEELS
GEAR CUTTING

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

CHIS 5842. **R. E. CARDER LTD.** CHIS 4611.
1 & 2, Chiswick Common Road, London, W.4

JIGS — TOOLS — AND PRESS TOOLS
UNIVERSAL GRINDING
—JIG BORING, GENERAL
GOOD CLASS MACHINING WORK—
DESIGN OFFICE & DEVELOPMENT WORK

JIGS
And FIXTURES
Designed & Manufactured by
DINSDALE ENGINEERING CO. LTD
LEEDS PLACE, TOLLINGTON PK. LONDON N.4

Capacity Available. Press Tools

Jigs and Fixtures. Test Rigs a speciality. Contract Jig-boring. Ring Portsmouth 23852 and our representative will visit you within 24 hours to discuss your requirements.
ALAN BRADLEY ENGINEERING CO., LTD.
South Street, Portsmouth, Hants.
A.I.D. Approved.

SPECIALITIES

WIDDOWSON'S specialise in re-building your **CINCINNATI** MILLING MACHINE

HERBERT WIDDOWSON & SONS LIMITED

CANAL STREET WORKS • NOTTINGHAM • ENGLAND TELEPHONE 51891

Capstan Users. Your Forming can be done entirely free of cost by using our new patent toolholder. Many other advantages. Cost often recovered on first job.
ETHOR SUPPLY CO.,
70, Exeter Road, Harrow, Middlesex.

Cleveland Automatics Rebuilt by experts. Replacement Parts. Manufacturers of Roller Boxes, Turret and Cross Slide Tooling.—**THE TIMS ENGINEERING CO., LTD.**, Vitcarb Works, Springfield Walk, Kilburn, N.W.6. Phone: MAIda Vale 0049.

TAPERLOCK & TRILOCK GAUGE HANDLES
Engraving Service **& BLANKS** Complying to B.S. 1044

Blanks in soft and annealed condition or in hardened state with centres lapped and taper ground to size. Handles anodised to your specific colour



BRILHART LTD • HATFIELD • DONCASTER • Tel: Stainforth 595




FOR MEASURING AND COUNTING

TRUMETER CO. LTD. MILLTOWN STREET, RADCLIFFE, LANCs.

C.W.2689

'MULTI-VIEW'
OIL LEVEL INDICATOR



SHOWS OIL LEVEL FROM BOTH HORIZONTAL AND VERTICAL POSITIONS
Six standard sizes from—
1/4" to 2" B.S.P.—Specials to order

LUBRICATION EQUIPMENT LTD.

Beech Street • Liverpool 20 • Tel: Bootle 2989

The "Coxeter" Revolving
Centre, from 76s. All sizes from stock.—
R. REVOLVING CENTRES, LTD., Oxford.




BRAND NEW BALL & ROLLER BEARINGS
OVER 5,000,000 IN STOCK IN MORE THAN 5,000 TYPES
BRITAIN'S LARGEST STOCKS
WRITE FOR STOCK LISTS
CLAUDE RYE BEARINGS 895-921 FULHAM RD., LONDON S.W.6
RENOVN 6174 (EXT. 24) TELEX 2-3453



When answering advertisements kindly mention **MACHINERY**.

Classified Advertisements (SPECIALITIES, contd.)



AN IMPROVED PLATE WORKING MACHINE

This illustration shows the improved "Nibbler" Universal Sheet Steel and Plate Working Machine.

It will perform the following operations:—

Straight Cutting.	Circle Cutting.
Beads.	Folding or Jogging.
Figure Cutting.	Planishing.
Lower Cutting.	Nibbling.
Slot Cutting.	Flanging.


Made in three sizes.

We will gladly quote you times on your own work

GEORGE H. ALEXANDER MACHINERY LTD.

82-84 Colleshill Street, Birmingham, 4, England

Albion COUNTING INSTRUMENTS



(patented design)
Send for catalogue
to Instrument Division

B. & F. CARTER & Co. LTD.
BOLTON 19 Bolton 4344 (3 lines)

**AUTOMATIC
NUMBERING
MACHINES**
for
**MARKING
ALL TYPES
OF METALS**

Phone
GERrard 5051

ARCHER ST. WORKS
ARCHER STREET
SHAFTESBURY AVE.
LONDON W.1.

A.E. GALE LTD.

**FLEXIBLE
METALLIC CONDUIT**
and solderless couplings

For protecting cables leading to:
motors, switchboards,
starters, etc.

ALL SIZES FROM
1/4 in. to 3 in.

THE DONOVAN ELECTRICAL CO. LTD.

(Wholesaling Division)

GRANVILLE STREET · BIRMINGHAM 1

**'WORTH'
PIPE UNIONS**
for Steam, Water, Oil
or Gas.
NEVER LEAK

WALTER SLINGSBY & CO. LTD.
WASK WORKS KEIGHLEY

Tungsten Carbide Tool

Manufacturers of standard and special form tools in high speed steel and tungsten carbide.

Our range includes reamers, cutters, workrest blades and wear-resistant parts.

Carbide supplied to customers' specification and express service given for emergency tooling.

DIAGRIT GRINDING CO., LTD.,

Marden, Kent.

Phone: Marden 362.

**Universal
Ball Bearing Co.**
111-115 Hammersmith
Grove, London, W.6
**FACTORS
MANUFACTURERS
AND REPAIRERS**

Phone: Rivers 3262-3-4. Grams: "Universal Bearing Hammersmith"

TIME RECORDERS—Sales—

Rental Service. Tel. HOP. 2239.

TIME RECORDER SUPPLY &

MAINTENANCE CO., LTD.,

157/159, Borough High Street, London, S.E.1.

Machine Engraved Feed Dials.

Scales, Nameplates, Labels, etc., in Metal and Plastics. Quick Delivery.—O. H. KAMPP & CO., Tanyard Works, Beaminster, Dorset Phone: Beaminster 440.

ANNOUNCEMENTS

PHOTOGRAPHY

Miles & Kaye, Ltd., 102, Southampton Row, London, W.C.1. Holborn 6558. Specialists in commercial and industrial photography for over 60 years. All branches of photographic work undertaken.

Photographs by MACHINERY

set the standard in engineering publicity. Our studio is one of the best equipped in the country. Ideal for really good photographs of tools, attachments and portable equipment. Mobile units available for taking photographs in black and white or in natural colour in your own or your customers' works. Specimens of work submitted on request.—Full particulars from the **SERVICE MANAGER, MACHINERY PUBLISHING COMPANY, LTD.,** National House, West Street, Brighton, 1.

FACTORY SPACE TO LET

Factory Space to Let Nr. Maidstone, Kent. 2,575 sq. ft. still in use as Engineering Works. Fully equipped with power supply, 400-440, 3 phase, 50 cycles. Occupation can be obtained April, 1959. 14 years' lease at rental of £12 per week.—**DIAGRIT GRINDING CO., LTD.,** Pattenden Lane, Marden, Kent. Tel.: Marden 362.

BUSINESS FOR SALE

Precision Engineering Business,

N.W. London (Private Company) for sale as going concern. Well equipped with modern machines, cars, etc. Leasehold factory, low rental. Would consider sale of part capital to engineer willing to become working director.—**BOX Z715, MACHINERY,** Clifton House, Euston Road, N.W.1.

Engineering Business, Machine

Tool and Electrical Equipment Mfg. Est. 1924. North London. Turnover £25,000. Fully equipped modern machine tools.—**BOX Z759, MACHINERY,** Clifton House, Euston Road, N.W.1.

Toolmaking and Precision En-

gineering Business for Sale. Freehold. New Workshops and Machinery. Excellent Director's House. 4 Bed, 3 Reception. Large Income. Established. Essex main road. £17,500. **BOX Z760, MACHINERY,** Clifton House, Euston Road, N.W.1.

PATENTS—TRADE MARKS

The Proprietors of Patent No.

739478 (Bahlsen) which relates to "Apparatus for Discharging Articles from a Stack," are desirous of entering into negotiations with interested parties with a view to the grant of a licence to work the invention in Great Britain.—Replies to **BOX Z765, MACHINERY,** Clifton House, Euston Road, N.W.1.

EDUCATIONAL

Works Study. Next Full Time

course (6 weeks) starts January 5. Syllabus from **SCHOOL OF TIME AND MOTION STUDY** (Founded 1951), 29, Cork Street, W.1.

PACKING AND SHIPPING

R. & J. PARK, LTD., Dominion

Works, Chislewick, England. Export packers, shippers and forwarding agents. Specialists in packing heavy machinery.

When answering advertisements kindly mention **MACHINERY.**

Classified Advertisements (ANNOUNCEMENTS, contd.)

BUSINESS OPPORTUNITIES

Sheffield Engineering Firm with comprehensive engineering plant and extensive experience in the design and production of all types of machinery, including special purpose plant, wishes to undertake the manufacture of complete or part assemblies including assembly line production. Own Drawing Office and Pattern Shop. Technical Representatives in all areas.—BOX L771, MACHINERY, Clifton House, Euston Road, N.W.1.

To Manufacturers. Prototype machine, manufacturing drawings, patterns, etc., together with orders totalling £60,000 per annum for five years, for outright sale by design and development engineer.—BOX Z767, MACHINERY, Clifton House, Euston Road, N.W.1.

MATERIALS FOR SALE

E. Stephens & Sons, Ltd., Bath Street, London, E.C.4. CLE. 1721. Tube, Rounds, Flats, Hex. Cut to size. Quick delivery.

MATERIALS WANTED

Steel, Aluminium, Brass, Sheets, and Offcuts 10 to 24in. Small or large quantities. Cash payments.—DYAS & FOWLE, 41, Loudoun Rd., N.W.8. MAIda Vale 2711, 5477

BRITAIN'S BIGGEST BUYERS

WANT
NEW BALL & ROLLER BEARINGS
OF ALL TYPES & SIZES
CLAUDE RYE BEARINGS
895-921 FULHAM RD. LONDON, S.W.6
REMOVN 6174 (EXT. 24) · TELEX 2-3453

PLANT WANTED

ACME GRIDLEY Automatic Turning Machine, capacity 2½ in., BAR, 4-spindle Model R or RA. In new condition. Box Z686, MACHINERY, Clifton House, Euston Road, N.W.1.

Wanted. Reasonably Modern machine tools and sheet metal working machinery. Best prices paid.—W. FORREST & CO., LTD., Industry Works, Sylvester Gardens, Sheffield, 1. Sheffield 23314/5.

WANTED!

USED MACHINE TOOLS

We offer generous prices for your plant or accept in part exchange for modern equipment

E.H. JONES
(MACHINE TOOLS) LTD

48, HIGH ST. EDGWARE, MIDDX
Telephone: EDGware 4488/9
BIRMINGHAM: MIDLAND 5593

Power Presses, 40 Tons, with adjustable stroke to 2in., also to 4in.—Required by SEARCHLIGHT, 159, Bello Bridge Road, Acton. Acorn 1077.

SURPLUS MACHINE TOOLS REQUIRED

OFFER YOUR MACHINES TO
J.E. RAISTRICK LTD.

POYLE TRADING ESTATE
COLNBROOK, SLOUGH,
BUCKS.

TEL: COLNBROOK 2421

3 Dimensional Diesinking Machine, Decker or Alexander.—Details and price to BOX Z357, MACHINERY, Clifton House, Euston Road, N.W.1.

CENTAUR TOOL WORKS, Birmingham, 18, pay best prices for good modern secondhand Machine Tools by first-class makers. Write or phone and our representative will call. Phone: EDGBASTON 1118 and 1119. Grams: Capetan, Birmingham.

**WANTED
MODERN MACHINE TOOLS**

We pay cash for single machines or complete plants

SEND US DETAILS
IMMEDIATE INSPECTION ARRANGED
**SOUTHERN ENGINEERING
AND MACHINERY CO.**
CONNAUGHT BUILDINGS
TANNERS BROOK, MILLBROOK
SOUTHAMPTON
Telephone: Southampton 73101/2/3

Machine Tools, Power Presses and Sheet Metal Machinery. Single machine or complete plants purchased immediate inspection.—ALBERT EDWARDS MACHINERY, LTD., 79/89, Pentonville Road, London, N.1.

**A. LAWRENCE & CO.
(MACHINE TOOLS) LTD.**

will be pleased to purchase your surplus Modern Machine Tools either on a cash or part exchange basis. Ask our representative to call and inspect.

Welsh Harp, Edgware Road,
London, N.W.2
Telephone: GLAdstone 0033

NORTON

GENEROUS PRICES
for "NEARLY NEW"
MEDIUM &
HEAVY DUTY MACHINE TOOLS
Ring: TATe Gallery 0433/4

REVERSE CHARGE
TELEPHONE CALLS
ACCEPTED!



W. NORTON (MACHINE TOOLS) LIMITED
GROSVENOR GARDENS HOUSE, GROSVENOR GARDENS,
LONDON S.W.1 Telephone: TATe Gallery 0433/4

Harry Kirk Will Purchase modern quality machine tools for cash. Whole plants or individual items. Full details to:—

HARRY KIRK ENGINEERING, LTD
Machine Tool Division,
Brandon Road Works,
Brandon Road, Coventry
Telephone: Walsgrave-on-Avon 2213/4

**Wanted
urgently**

Late Type Machine Tools
Best Prices are offered for latest types of Machine Tools. Send us details of what you have and our representative will call to inspect

J. B. MACHINE TOOL CO. LTD.
312 BRADFORD ST., BIRMINGHAM 5
Telephone: MIDland 4375

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT WANTED, contd.)

WANTED
GOOD CLASS MACHINE
tools and sheet metal
machinery.

EDWIN MILLEN

70 Clerkenwell Road, London, E.C.1
Phone: Clerkenwell 6064

WANTED GOOD
MACHINE TOOLS

Offer your Surplus Tools
to us. We pay a good price

M. WARD

(MACHINE TOOLS) LTD.
1, KILBURN HIGH ROAD,
LONDON, N.W.6

MAIDA VALE 1195-96
Telegrams: Emwarner, K.M., London
One minute from Kilburn Park Station
Bakerloo Railway

2 m.



Proprietors: Exors.
M. & H. Urquhart
MODERN MACHINE TOOLS
of all types.

GOOD PRICES. Send details to
WM. URQUHART,
1023/27, Garratt Lane, London, S.W.17
Tel: BALHAM 8551

WANTED
ALL TYPES OF MODERN
MACHINE TOOLS

Please write or phone details to:

THE MIDLAND MACHINE TOOL CO.
BRADLEY, BILSTON, STAFFS.

Tel.: Bilston 42471/4



WE ARE KEEN BUYERS
OF GOOD MODERN
MACHINE TOOLS.

INSPECTION WILL BE
ARRANGED AT ONCE.

M. C. LAYTON LTD.
96-98 VICTORIA STREET,
LONDON, S.W.1

Telephone: VICTORIA 7778/9.

kent
Give Value

WHETHER BUYING OR SELLING
USED MACHINE TOOLS

Contact:—
K.E.N.T. MACHINERY & ENG. CO.
Datchelor Place Mews, London, S.E.5.
Telephone: ROD 4149.

B.G. MACHINERY, LTD.,
Montgomery Street, Sparkbrook,
Birmingham, 11. will pay good prices for
Machine Tools of first-class make and in good
condition.—Phone: VICTORIA 2351/9.

URGENTLY REQUIRED:

TAYLOR & CHALLENGE Type H31 Open
front, Geared Power Press, fitted adj.
stroke, Inclinable Preferred.

SWEENEY & BLOCKSIDE No. 14 Open
front Geared Power Press, fitted adj.
stroke.

Excellent modern Machines required, motor-
ised 400/440 volts, 3 phase, 50 cycles.

BOX Z753, MACHINERY
Clifton House, Euston Road, N.W.1.

WANTED

HERBERT No. 3 & No. 4
AUTOS preferably with Air
Chucks.

HERBERT No. 3 N.D.
HORIZONTAL MILLER

PRATT or similar VERTICAL
AIR CHUCKS

AIR COMPRESSOR—DIRECT
DRIVE to give 220 C.F.M. @
100 p.s.i.

RADIAL DRILL—ASQUITH
O.D.I. or similar

LUMSDEN SURFACE
GRINDER 71 or 72 L.E.O.D.

CLEVELAND 2 1/2 in. SINGLE
SPINDLE BARAUTO

J. C. Bamford
(EXCAVATORS) Ltd
Lakeside Works, Rocester, Staffs.
Telephone: Rocester 371

Modern Good Class Machine

Tools and Sheet Metal Machinery required
for prompt cash.—H. BELL, MACHINE
TOOLS, LTD., Walter Street, Leeds, 4. Tel:
63-7398.

No. 3 Size Horizontal Borer.
Must be accurate machine.—BOX Z754,
MACHINERY, Clifton House, Euston Road,
N.W.1.

Gear Lead Measuring Machine;
Maag P.H. 60, Orcutt Mk. III or similar.
—BOX Z761, MACHINERY, Clifton House,
Euston Road, N.W.1.

Wanted, Motorised 30-50 Ton
Power Press Spinning Lathe with trim-
ming and wiring attachments. Details and
prices.—BOX Z766, MACHINERY, Clifton House,
Euston Road, N.W.1.

Wanted, Second Hand Centre
Lathe, approximately 6in. centre height
by 30in. to 36in. between centres. Must be
in perfect condition, motorised and adaptable
for spherical turning.—Send details of age, con-
dition and price to HARRGATE OPTICAL
CO., LTD., Grove Park Terrace, Harrogate.

Wanted. 6ft. x 1 1/2 in. Power
Guillotine. Price reasonable.—PRICHARD
LTD., Greasley Street, Bulwell, Nottingham.

Draw Benches Wanted. 10-20
tons pull: 16ft. to 26ft. draw.—Full
details of price, condition, location, to F. J.
EDWARDS LIMITED, 359, Euston Road,
London, N.W.1. Euston 4681.

PLANT FOR SALE

HENRY BUTCHER & CO.

Specialists in the

• VALUATION AND SALE OF FACTORIES, PLANT AND MACHINERY •

73 CHANCERY LANE, LONDON, W.C.2

TEL: HOLBORN 8411 (8 lines) GRAMS: PENETRANCY, HOLB., LONDON

Colchester Triumph 7 1/2 in. Gap
bed A.G.H. Lathe with coolant and equip-
ment. 400/350.—C. DUGARD, LTD., Denmark
Villas, Hove. 32471.

A Good Number of High-class
Machine Tools always in Stock.—
ELLISON, Cook Street, off Chapel Street
Salford, 3, Lancs.

Churchill Hydraulic External
Grinder, Model BY. Fitted Cam Grind-
ing attachment. Mot.—WILCOX & CO. Bar-
street, Birmingham, 19. Northern 1234.5.

When answering advertisements kindly mention **MACHINERY**.

RING BELLS for machine tools

LEEDS 63-7398

CINCINNATI No. 3 Dial Type Vertical Milling Machine. Speed Range 18-450 r.p.m.

HERBERT 47V Vertical Milling Machine. Speed Range 21-750 r.p.m.

ARCHDALE 18in. Vertical Milling Machine. Speed Range 79-2,000 r.p.m.

ARCHDALE 30in. Vertical Milling Machine. Speed Range 29-522 r.p.m.

MILWAUKEE 2H Universal Milling Machine. Speed Range 30-1,400 r.p.m. Comprehensive equipment.

BROWN & SHARPE No. 2 Universal Milling Machine. Speed Range 40-1,300 r.p.m.

PARKSON 2T Universal Milling Machine. Speed Range 8-360 r.p.m. Comprehensive equipment.

PARKSON 1NA Universal Milling Machine. Speed Range 17-450 r.p.m. Comprehensive equipment.

EDGEMOND No. 2 Plain Milling Machine. Speed Range 21-380 r.p.m.

ARCHDALE 20in. Production Milling Machine. Speed Range 30-619 r.p.m.

BROWN & SHARPE No. 10 Production Milling Machine. Speed Range 55-1,300 r.p.m.

WARD 7 Combination Turret Lathe. Taper Turning. Bar Feed and Chucking. Speed Range 37-750 r.p.m. Comprehensive equipment.

WARD 7, 3A, 2A, 1A Capstan Lathes arranged Bar Feed.

NORTON 16in. x 50in. Universal Grinding Machine. Comprehensive equipment.

CHURCHILL 12in. x 36in. Universal Grinding Machine. Comprehensive equipment.

NEWALL Type L 10in. x 36in. Plain Grinding Machine.

JONES & SHIPMAN 10in. x 27in. Plain Grinding Machine.

B.S.A. Landis Type C 6in. x 18in. Plain Grinding Machine.

CHURCHILL 24in. Ring Grinder.

CHURCHILL 42in. Ring Grinder.

SCRIVENER 2C Centreless Grinder.

HENDEY 24in. x 168in. S.S. & S.C. Lathe. Speed Range 14-560 r.p.m.

F.L.C.B. 17in. x 10ft. S.S. & S.C. Lathe. Speed Range 1.08-152 r.p.m.

OLDFIELD & SCHOFIELD 15in. x 8ft. S.S. & S.C. Lathe. Gap Bed. Speed Range 6.5-332 r.p.m.

OLDFIELD & SCHOFIELD 12in. x 7ft. S.S. & S.C. Lathe. Gap Bed. Speed Range 12-400 r.p.m.

MONARCH 16in. x 30in. Type CY S.S. & S.C. Lathe. Speed Range 14-600 r.p.m.

CINCINNATI Type LT 8in. x 5ft. S.S. & S.C. Lathe. Speed Range 16-392 r.p.m.

LANG 9in. x 5ft. 6in. S.S. & S.C. Lathe. Speed Range 8.75-240 r.p.m.

DEAN SMITH & GRACE 7in. x 3ft. 6in. S.S. & S.C. Lathe. Gap Bed. Speed Range 11-490 r.p.m.

DEAN SMITH & GRACE 7in. x 2ft. 6in. S.S. & S.C. Lathe. Gap Bed. Speed Range 11-490 r.p.m.

DENHAM 6in. x 3ft. 0in. S.S. & S.C. Lathe. Gap Bed. Speed Range 10-400 r.p.m.

KITCHEN & WADE 5ft. No. 5 M.T. Radial Drilling Machine. Speed Range 20-1,000 r.p.m.

TOWN 8ft. No. 3 M.T. Radial Drilling Machine. Speed Range 126-1,450 r.p.m.

ARCHDALE 4ft. No. 4 M.T. Radial Drilling Machine. Speed Range 80-2,000 r.p.m.

ARCHDALE 8ft. No. 2 M.T. Radial Drilling Machine. Speed Range 126-1,440 r.p.m.

ASQUITH L.D.R. 4ft. No. 2 M.T. Radial Drilling Machine. Speed Range 79-2,000 r.p.m.

CLIFTON & BAIRD Punching and Cropping Machine. Cap. 4in. x 4in. x 4in. angle.

BIGWOOD 4 Roll Bending and Straightening Machine. Cap. 4ft. x 4in.

Modern Machines—Motorised 400-440/3/50. Fully Overhauled—Six months' Guarantee.

WESTERN MACHINE TOOLS (SWANSEA) LTD.
72, MANSEL STREET, SWANSEA.
Tel.: 50061/2.

There are **HUNDREDS** of **MACHINES** to choose from at

THE F.J.E. MACHINE CENTRE

ISLINGTON PARK STREET, NEAR HIGHBURY CORNER, LONDON, N.1
(on the main A1 Road from the North)

Two Belliss & Morcom 2,500
c.f.m. Compressors, 100 lbs. w.p., 550 h.p. motors, 6,600/3/50 supply. Used 4 years only. With inter- and after-coolers, Receiver, Switch panel. Available immediately.—FRED WATKINS (ENGINEERING) LTD., Coleford, Glos. 'Phone: Coleford 2271/2/3.

Workpans, Large Quantities
Strong Gauge Workpans, size 16in. by 14in. by 5 1/4in., forged, riveted handles, approx. weight 8 lb., price 8s. 6d. each, quantities. Other sizes manufactured.—Contact J. BURTONS WORKS, Astley, Shrewsbury. Tel. Shawbury 266

Jones & Shipman 4-spindle Drill
5in. cap., separate motors. 400/3/50.—C. D'UGARD, LTD., Denmark Villas, Hove. 32471.

DEAN SMITH & GRACE 36in. Short Bed Boring and Facing Lathe, hollow spindle 4 1/4in. dia., motor-driven 400/3/50.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

A SELECTION FROM OUR STOCK OF MACHINE TOOLS

WARD 7 C.T. Lathe, comprehensive equipment.

RICHARDS No. 5 Borer, with travelling spindle.

SNOW Grinders, Horiz. spindle, OS, 72, OS, 120 and OS, 54.

HARRISON 11in. swing Copying Lathe (NEW.)

CRAVEN S2 Universal Rigidmill.

TRIUMPH 8ft. x 3in. Guillotine.

W. FORREST & CO. LTD.
INDUSTRY WORKS,
SYLVESTER GARDENS,
SHEFFIELD, 1.
'Phone: 23314/5.

100 Ton Friction Screw Press,
11in. between uprights, 5 1/4in. dia. screw. £95.—BIRCH & JACQUES, Bershaw Trading Estate, Walton-on-Thames.

NEW MACHINES EX STOCK

MITCHELL OF KEIGHLEY 10 1/2in. x 7ft. 5in. B.C. Gap Bed S.S. & S.C. Centre Lathe.

MITCHELL OF KEIGHLEY 8 1/2in. x 4ft. 3in. B.C. Gap Bed S.S. & S.C. Centre Lathe.

COLCHESTER "MASCOT" 8 1/2in. x 5ft. 6in. B.C. Gap Bed S.S. & S.C. Centre Lathe.

STANLEY 8 1/2in. x 6ft. 0in. B.C. Gap Bed S.S. & S.C. Centre Lathe. 2 speed motor.

STANLEY 7in. x 2ft. 10in. B.C. Gap Bed S.S. & S.C. Centre Lathe. 2 speed motor.

COLCHESTER "STUDENT" 6in. x 24in. Gap Bed S.S. & S.C. Centre Lathe.

VICTORIA V2 Vertical Miller, table 45in. x 11in.

MYFORD MG12 Cylindrical Grinder.

P. SIMPSON & CO. LTD.
177 RAIKES LANE, BIRSTALL,
NR. LEEDS.
Tel.: Batley 1235.

MACHINE TOOLS—The Heart of Industry

NEW

H.M.V. Model AV-75 (Swedish) 3in. Universal Horiz. Borer.

BINS & BERRY Model "TB" 12 1/2in. h.c. x 7ft. 6in. b.c. S.S. & S.C. Gap Bed Lathe.

GRANOR 11in. h.c. x 7ft. 10in. b.c. S.S. & S.C. Gap Bed Lathe.

HARRISON 8in. h.c. x 6ft. 7in. b.c. S.S. & S.C. Gap Bed Lathe.

New **STANLEY** Sliding Bed, 10in. h.c. x 5ft. b.c. S.S. & S.C. Lathe.

W.M. 7 1/2in. h.c. x 36in. b.c. S.S. & S.C. Gap Bed Lathe.

ESSEBECO Model RD25 27in. Radial Arm Drill, No. 3 M.T., power feed.

RICHMOND HB3/12 48in. Radial Arm Drill, No. 4 M.T.

RICHMOND SR2 4ft. Radial Drill, No. 3 M.T.

ABWOOD CG1 8in. Carbide Tool Grinder.

ABWOOD Model TH/2AP Vertical Surface Grinder.

BURDETT 18in. x 6in. Hydraulic Surface Grinder.

EXCEL No. 5 Tool and Cutter Grinder, cap. 10in. x 26in.

VICTORIA U2 Universal Miller.

W.M. "369" Turret Miller.

WORCESTER 6-ton Open Fronted Press.

EXCEL No. 3 Filing and Sawing Machine.

HEAP Universal 2in. Whit. Screwing Machine.

INVICTA Model 6M 24in. Shaping.

IN ADDITION TO THE ABOVE WE HAVE 380 SECONDHAND MACHINE TOOLS IN STOCK.

All machines delivered free U.K.

PRICED BROCHURE ON REQUEST

MARTIN BROS. (MACHINERY) LTD.,
EMPRESS WORKS, EMPRESS STREET
CORNBROOK, MANCHESTER, 16.
Tel.: Trafford Park 1091-2.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

FRORIEP

Heavy Duty Vertical TURNING
AND BORING MILL, max. swing
54in., with side head; 50 h.p.
main motor. Manufactured 1952

F. J. EDWARDS LTD.,
359-361 Euston Road,
London, N.W.1
EUSTON 4481 and 3771

Archdale 28in. Vertical Boring
and Drilling Machine, No. 4 M.T. Roller
bearing production table. 400/3/50.—C.
DUGARD, LTD., Denmark Villas, Hove 32471.

Brown & Sharpe Automatics—
60 High Speed with slotters. 6 High Speed,
magazine feed, No. 0 Reg. No. 2 Reg. Good
condition. Brown & Ward Mot. 4in. 4-op.
Threader.—C. L. THOMAS, LTD., 18, Park
Avenue, Solihull 1281.

Arc Welders, Oil Cooled, £25.—
RENTWELD, 94, Camden Road, N.W.1.
GUL. 6006.

Victoria Universal Milling
Machine. Table 40in. x 10in. Power Lomat
and cross. Little used, complete with dividing
head. 400/3/50 self-contained motor. Excel-
lent condition. £485. Cincinnati Horz. H.D.
with table 56in. x 15in. all geared. Power feeds
all directions. £265. 400/3/50.—BOX Z768,
MACHINERY, Clifton House, Euston Road,
N.W.1.

Several Bliss No. 19 Inclinable
Presses for sale. Some with dial feeds and
ejectors and roll feeds, others plain. Pressure
about 14 tons. Strokes vary between 4in. and
3in. Bed 17in. x 10in. Motor drive. Full
details from F. J. EDWARDS, LTD., 359,
Euston Road, London, N.W.1, or 41, Water
Street, Birmingham, 3.

Thompson Hydraulic Surface
Grinder. Type F. Cap. 18in. x 6in.
Motorised.—WILCOX & CO., Barr Street,
Birmingham, 19. Northern 1234/5.

Churchill-Redman 11NM, 11in.
A.G.H. Centre Lathe, 38in. in gap, 10ft.
B.C. M/D. 400/3/50.

CINCINNATI No. 2 Universal Milling
Machine. Table size 52 1/2in. x 12in. Speeds to
1,500 r.p.m. M/D. 400/3/50.

BROWN & SHARPE 2B Plain Horizontal
Milling Machine. Dual control type. Table
51in. x 11in. Speeds to 1,500 r.p.m. M/D.
400/3/50.

HERBERT 3A—Chucking Auto. M/D.
400/3/50.
ALBERT EDWARDS (MACHINERY), LTD.,
79/89, Pentonville Road, London, N.1. Tele-
phone: TERMINUS 0167/8/9.

500 Ton Double Action Drawing
Press, blankholder 60in. x 60in. with
self-contained Oil Pump Unit.
REED BROTHERS (ENGINEERING), LTD.,
Plant Works,
Woolwich Industrial Estate,
London, S.E.18.
Telephone: Woolwich 7611/6.

Expanding Lathe Mandrel Sets.
Range 1in. to 2in. Leconte Pattern.
List £17 5s. Ex Government Barzain. Unused.
Boxes: £6 10s. set, p.d. 3s. 6d. Also 2in. to 3in.
£5 10s. cart. 5s.—STEVENAGE TOOLS &
SWITCHES, LTD., Stevenage, Herts.

New Britain-Gridley No. 60
1in. capacity Six Spindle Bar Automatic.
Petersmann P7, 1/4in. capacity Sliding Head
Single Spindle Automatics.
Petersmann No. 2 Pinion and Gear Cutting
Machines.


Herbert No. 6 Chucking Automatic.
Coventry Gauge and Tool Gun Gauge Grinder.
Newall 6in. x 18in. Hydraulic Plain Cylind-
rical Grinder.
B.S.A. Landis 6in. x 18in. Type C Hydraulic
Plain Cylindrical Grinder.

Brown & Sharpe No. 5 3in. x 18in. Hydraulic
Plain Cylindrical Grinder.
Head No. 73 Hydraulic Centreless Internal
Grinder.

Bryant 16-28 Hydraulic Internal Grinder.
All of the above are modern machines, in
first class condition, motorised for 400 440/3/50
A.C. electric supply and are offered at genuine
bargain prices.

THE WEST MIDLAND EQUIPMENT CO.,
10, Hagley Road, Stourbridge, Worcs. Stour-
bridge 4187.

**A
HARD NUT
TO CRACK?**



REMEMBER...

WARDS might have it!

THOS. W. WARD LTD
MILBURN WORKS, SHEFFIELD

Denison Universal Tester. Ten-
sile Bending and Compression. Cap
10,000 lbs.—WILCOX & CO., Barr Street,
Birmingham 19. Northern 1234/5.

One—Kierserling Type WDS.3.
1 1/2in. dia. Centreless Bar Turning
Machine, complete with roller cutter head up
to 1 1/2in. dia. motor, starter and pump, 400-440
volts, 3 phase, 50 cycles.—BOX Z728,
MACHINERY, Clifton House, Euston Road,
N.W.1.

Taylor & Challen B3 1/2 Geared
Press, 60 tons, 3in. stroke. Fitted 9in.
double roll feed. Mot.—WILCOX & CO.,
Barr Street, Birmingham, 19. Northern
1234/5.

Brown & Sharpe Automatics:
Several No. OG, No. 2G and No. 90G.
All late serial numbers and in good condition.
Reasonable prices. M/C's complete with stock
supports, feed and speed gears.—Can be seen at
MELBOURNE ENGINEERING CO., LTD.,
Derby Road, Melbourne, Derbyshire. Phone:
Melbourne 232.

Jones & Shipman Precision
Hydraulic Surface Grinder, Model 540.
Serial No. 40853, 6in. x 18in. capacity. Com-
plete with coolant equipment. First class work-
ing condition, inspection invited. Price £475
o.n.o.—TEST EQUIPMENT, LTD., Gatwick
Road, Crawley, Sussex. Telephone: Crawley
2350.

LEONARD ROTH

ABBOT ST., KINGSLAND HIGH ST.,
DALSTON JUNCTION, LONDON, E.8.

TERMS ARRANGED.

Tel.: CLIsold 0513/4.

MATRIX Precision Cylindrical Grinder.
24in. x 8 1/2in. capacity. Internal Grinding
Attachment, 3 and 4 Jaw Chucks, Collet
Assembly, Suds Pump, etc., Motorised
400/3/50. £195.
EXCEL No. 3 Die Filer & Sawing Machine
400/3/50 £125.
6ft. x 4in. Geared Bending Rolls, £65.
HUMPHRIES 25 Ton Power Press, Adjustable
Stroke, Motorised, 400/3/50. £325.
SCHULER Type 25 Ton Power Press, Ad-
justable Stroke with 400/3/50 Motor, £175
WE HOLD BIG STOCKS OF LATHES,
SHAPERS, MILLS, DRILLS, PRESSES,
ETC. PLEASE WRITE FOR LISTS.

Oldfield & Schofield No. 1

Forcing or Straightening Press, 10 ton
cap. 15in. stroke. Mot.—WILCOX & CO.,
Barr Street, Birmingham 19. Northern 1234/5.

MILWAUKEE 2H Vertical Milling Machine,
spindle speeds 35 to 1,400 r.p.m. Table
50in. x 10in. Modern tool.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742

PLANNER 30in. by 16 1/2in. by 15in. Auto
cross and down feeds. £45.
SMALL HYDRAULIC PRESS 12in.
by 8in. by 6in., 5,000 lbs. max. £45.
24in. **WETSTONE GRINDER.** Mot. in
base. £85.
HARDINGE lin. CAPSTAN. Collet
suds and electrical equipment. £90.
WARNER & SWASEY 1 1/2in. CAP-
STAN. Feeds all ways. M/D. £85.

EDWIN MILLEN,

70, Clerkenwell Road, London, E.C.1.
Phone: CLERkenwell 6064.



JONES & SHIPMAN Model 540 Surface
Grinder.

38in. Radial Sensitive Drilling Machine,
ARCHDALE No. 3 M.T.
10 1/2in. x 6ft. Between Centres **MITCHELL**
Centre Lathe.

No. 3 **EXCEL** Filing and Sawing Machine.
14in. **BUTLER** Slotting Machine, 39in. dia-
meter table. 90 strokes per minute.
24in. x 9in. **BUYSER** High-speed Vertical
Milling Machine. Spindle speeds 265-1,860
r.p.m. As new.

27in. **WOTAN** Hydraulic Shaper. Automatic
feeds and rapid traverses to the table. Ram
speeds 16-98ft. per minute. Overhauled.
52in. x 10 1/2in. **CINCINNATI** Vertical Milling
Machine. Model 2M. Power feeds and
rapid traverses. Excellent condition.

10in. x 24in. **NEWALL** Type L.U. Universal
Grinder. Hydraulic. Complete with internal
spindle.

10in. x 24in. **CHURCHILL** Hydraulic Universal
Grinder. Complete with internal spindle.

DIMCO (Gt. Britain) LTD.,
28, WOOD LANE,
SHEPHERD'S BUSH,
LONDON, W.12.

SHEPherd's Bush 4401.

When answering advertisements kindly mention MACHINERY.

In Stock NOW

AUTOMATICS

PONGRACZ Single Spindle Automatic capacity 10 mm.
CONOMATICS 3½ in. four-spindle Bar Automatics, (Three available.)
BULLARD 8 in. six-spindle Vertical Chucking Automatic.

BORING MACHINES

RICHARDS Type PRT Horizontal Type Floor Boring Machine, 3½ in. dia. travelling spindle and 28 in. dia. facing head.
FRORIER Vertical Boring Mill, table diameter 39 in., maximum turning capacity 52 in. (1955.)
ASQUITH 7 in. Horizontal Floor Boring Machine.
BERTHIEZ Model 9340 Vertical Boring Mill, table diameter 7 ft. 10 in., maximum turning capacity 9 ft. 6 in. (1953.)
JUNGENTHAL Model KE.1200 Vertical Boring Mill, table diameter 39 in., maximum turning capacity 50 in. (1954.)
NEWALL No. 1 Jig Boring Machine.
New PFEIFER Model F.60 Horizontal Universal Boring, Facing, Milling and Drilling Machine, 2½ in. travelling spindle.
NILES Horizontal Boring Machine, 4½ in. travelling spindle, 60 in. by 48 in. table.

CAPSTAN & CENTRE LATHES

BRADFORD 8½ in. centre height by 30 in. between centres Centre Lathe.
HERBERT No. 8 Combination Turret Lathe.
HERBERT No. 12 Combination Turret Lathe with comprehensive tooling.
NILES Centre Lathes 15 in. centre height by 28 ft. between centres. (Two available.)
BETTS-BRIDGEFORD Centre Lathe, 15 in. centre height by 16 ft. between centres. (Two available.)
WARD No. 7 Combination Turret Lathe.
GISHOLT Model IL Universal Turret Lathe. (Two available.)
LIBBY Model 4A Capstan Lathe.
OLDFIELD & SCHOFIELD Surfacing and Boring Lathe, 10½ in. centre height by 33 in.

DRILLING MACHINES

KITCHEN & WADE 28V10 Single Spindle Vertical Drilling Machine, No. 4 M.T.
HETNER Radial Drilling Machine, having 10 ft. Radial Arm elevating column type.
KITCHEN & WADE 4 ft. 6 in. Radial Drilling Machine.
TOWN 30 in. Vertical Spindle, Boring, Drilling and Tapping Machine. No. 5 M.T.
ASQUITH ODI 6 ft. Radial Drilling Machine.

GEAR MACHINES

MUIR 72 in. spur and helical Gear Generating Machine.
KOLB Gear Grinding Machine.
GLEASON No. 9 Bevel Gear Completer Machine.
ORCUTT Model HM.24 Internal Spur Gear Grinding Machine.
SYKES V.10 Gear Generator.
GLEASON 3 in. Bevel Gear Generators. (Two available.)

GRINDING MACHINES

New EXCEL No. 3 Hydraulic Surface Grinding Machine.
CHURCHILL Universal Grinding Machine, 10 in. by 24 in. between centres.
B.S.A. LANDIS Type "C" Plain Hydraulic Cylindrical Grinding Machine, 6 in. by 30 in. (Two available.)

CHURCHILL Model HBY Internal Grinding Machine.
BLANCHARD No. 10 Vertical Spindle Surface Grinding Machine.

LANDIS Hydraulic Universal Grinding Machine 14 in. by 36 in. between centres.
LANDIS Type D Hydraulic Crank Pin Grinding Machine, capacity 2½ in. by 72 in.
LANDIS Type "C" Plain Hydraulic Cylindrical Grinding Machine, 10 in. by 36 in.
NORTON 10 in. by 18 in. Plain Cylindrical Grinding Machine.
ABWOOD Vertical Spindle Surface Grinding Machine, 6 in. by 18 in.
CHURCHILL Hydraulic Universal Grinding Machine, capacity 24 in. by 72 in.
New TOS Vertical Spindle Hydraulic Surface Grinding Machine, table 118 in. by 24 in.
New TOS Vertical Spindle Hydraulic Surface Grinding Machine, table 59 in. by 12 in.
New TOS Model BBZ.60 Centreless Grinding Machine, maximum capacity 2½ in. diameter.
BROWN & SHARPE No. 22, 10 in. by 36 in. Plain Hydraulic Cylindrical Grinding Machine.
MOPCO Plain Hydraulic Cylindrical Grinding Machines, 13 in. by 30 in. (Two available.)

MILLING MACHINES

MILWAUKEE No. 2H Vertical Milling Machine, table 50 in. by 10 in.
SUNDSTRAND Hydro-Screw Rigidmill Automatic Production Milling Machine, table 7 in. by 14 in., table traverse 48 in.
MILWAUKEE No. 4H Plain Horizontal Milling Machine, table 74 in. by 15½ in.
VICTOMATIC Automatic Cycle Production Milling Machine, capacity 50 in. by 10 in.
REED PRENTICE No. 5 Vertical Milling Machine, table 68 in. by 16 in.
CINCINNATI Hydromatic 3/24 Duplex Production Milling Machine. (Two available.)
REED PRENTICE No. 6 Vertical Milling Machine, table 84 in. by 20 in.
CINCINNATI 1/12 Horizontal Production Milling Machine.
CENTEC Model 3R Automatic Production Milling Machine, table 6 in. by 25 in.
CINCINNATI 2M Universal Milling Machine.
REINECKER Vertical Milling Machine, table 5 in. by 13½ in.
HERBERT No. 10 Vertical Milling Machine, table 31 in. by 9½ in.

PLANING, SLOTTING AND SHAPING MACHINES

STOCKBRIDGE 20 in. Shaping Machine.
URQUHART LINDSAY & ROBERTSON ORCHAR Spiral Drive Heavy Duty Planing Machine, capacity 16 ft. by 5 ft. by 5 ft.
STIRK HILOPLANE Planing Machine, four solenoid tool boxes, capacity 12 ft. by 4 ft. by 4 ft.

MISCELLANEOUS

BESCO Overcrank Guillotine, capacity 5 ft. by 14 gauge (Motorised 400/350 cycles.)
SHEEPBRIDGE 20 in./22 in. Hydraulic Cold Circular Sawing Machine.
BENNIE Punching, Cropping, Notching Machine, Punch 1½ in. through ½ in.
ROWLAND 16 in. Type AHC Hydraulic Abrasive Wheel Cutting-Off Machine.

RING

CHIPPING SODBURY 3311

or contact our nearest Representative

NEWMAN INDUSTRIES LIMITED

Machine Tool Division

Telephone: Chipping Sodbury 3311

YATE, BRISTOL

Telegrams: "Dynamo, Yate"

London (Sloane 8206). Birmingham (Northern 9634). Manchester (Deansgate 2837 8). Glasgow (Central 2101/2).
Newport, Mon. (Newport 64006). Leeds (Leeds 672323). Lincoln (Lincoln 22695). Wallend-on-Tyne (vVallsend 63992).

Neuman for MACHINE TOOLS

Classified Advertisements (PLANT FOR SALE, contd.)

ACBARS LIMITED

57a, HOLBORN VIADUCT,
LONDON, E.C.1.

Telephone: Central 2287. Telegrams: Acfirb. Cent. London

AVAILABLE FROM STOCK

All machines listed below are at our Works in Sutherland Walk, Walworth Road, S.E.17.

AUTOMATICS

HERBERT Auto. Junior.
HERBERT 3A Chucking Auto.
ACME-GRIDLEY, Type R, 4-spindle, 1 1/2 in. capacity.
ACME-GRIDLEY, Type R, 4-spindle, 1 1/2 in. capacity. (2 machines.)
WICKMAN 4mm. Swiss Type.
BECHLER 7mm. Swiss.
RYDERMATIC No. 12 Multi Tool Lathes

GRINDERS

CHURCHILL No. 2 Hydraulic Spineshaft Grinder.
ABWOOD Vertical Spindle Surface.
BROWN & SHARPE No. 2 Surface Grinder.
JONES & SHIPMAN Fig. 62M Plain Cyl. 8in. dia. by 10in.
LANDIS 10in. by 18in. Plain Grinder.
CHURCHILL 24in. by 10in. Universal.
JONES & SHIPMAN Fig. 138 10in. by 27in. Universal Grinder.
BRYANT 16C 16in. Internal Grinder.
SMART & BROWN Internal Grinder.
ROWLAND three wheel Carbide Tool Grinder and Capter.

CAPSTAN LATHES

HERBERT No. 0 1/2 in. collet cap. (2).
MURAD 1/2 in. Capstan Lathe.
SOUTHWARK No. 2 1 1/2 in. Capstan Lathe.
DRUMMOND Type K Capstan Lathes (2).
GISHOLT No. 4 Friction Head Capstan.
LIBBY 4R 2in. Capstan Lathe. Bar feed.
BARDONS & OLIVER No. 5 Capstan Lathe.
HERBERT No. 7 Turret Lathe.
FOSTER No. 28 Turret Lathe.

CENTRE LATHES

SOAG OXFORD 65in. Centre Lathe.
SOUTHBEND 13in. swing taper turning.
WILLSON 8 1/2 in. A.G.H. Lathe.
CARDIFF 8 1/2 in. by 48in. Lathe.

MILLERS

HERBERT No. 1 Horizontal.
VICTORIA MO Plain.
New VICTORIA U1 and U2 Universal.
ARCHDALE 20in. Horizontal Mills (3).
ARCHDALE 28in. Horizontal Mill.
RICHMOND VHM Vertical Mill.
New VICTORIA V2 Vertical.
HOLROYD T17 Thread Miller.
HELLER Automatic Thread Millers (4).

MISCELLANEOUS

TAYLOR No. 1 Cutting-off Machine for Tubes and Bars.
JONES & SHIPMAN 2-spindle Pillar Drill, with No. 3 M.T. spindle, power feed.
New ESSEX 18 Bandsaw.
New RICHMOND SR2 3ft. Radial Drill.
All Machines motorised 400/3/50 unless otherwise stated.

Willson 8 1/2 in. Gap Bed Heavy duty S.S. & S.C. Lathe. 3 1/2 in. H.M. 400/3/50.—C. DUGARD, LTD., Denmark Villas, Hove, S2471.

K·E·N·T

Lumsden No. 83 Heavy Duty Horizontal Surface Grinder. Capacity 8 1/2 in. x 24in. 31in. segmental wheel. Hydraulic. £625.
G. & L. "Gran Rapids" No. 25 Hor. Hyd. Surface Grinder. £275.
Brown & Sharpe 2a Universal High Speed Milling Machine. £625.
Van Norman 22L Duplex Hor and Vert. High Speed Milling Machine. £625.
Zbrojovka 47in. x 12in. Vert. Mill. Sliding and swivel head. Rapid. £475.
Herbert No. 1 Lever Hor. Milling Machine. £75.
Cincinnati 08 Vert. Milling Machine. £225.
Archdale 18in. High Speed Vert. Milling Machine. £375.
Fifteen Ward 2A and 3A Capstans, from £125.
Holbrook 8 1/2 S.S. & S.C. Lathe. T.T. collets. £325.
Smith & Mills 16in. Heavy Duty High Speed Shaper. £275.
Southbend 5in. S.S. & S.C. Lathe. Full equipment. As new. £150.
Lang 8 1/2 in. S.S. & S.C. Lathe. £625.
Asquith Precision Jig Boring and Drilling Machine. 3ft. 6in. x 2ft. 6in. Compound table. £350.
Bliss No. 20 Power Press, 2in. stroke. £112 10s.
Double Action Double Sided Gearing Cam Drawing Press, 10in. combined stroke, approx. 40 tons. £175.

All machines mot. 400-440/3/50.

K·E·N·T MACHINERY & ENGINEERING CO.
Datchelor Place, London, S.E.5.
Telephone: ROD 4149.

HERBERT and ARCHDALE 4-spindle Drillers pole change motors, each with 3 ungeared 1/2 in. and one geared auto. spindle.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

Richards Horizontal Borer.
16in. facing head, 40in. x 20in. fixed table and 20in. x 20in. rotating table. Vernier scales, 400/3/50.—C. DUGARD LTD., Denmark Villas, Hove. S2471.

Lorenz Gear Shaper, Model S.O.O. Capacity 7 1/2 in. P.D. x 2in. face. Motorised.—WILCOX & CO., Barr Street, Birmingham, 19. Northern 1234/5.

Milling Machine. Cincinnati
Horizontal Mill with Richmond Vertical Milling attachment. Sundry optional accessories, located outer London.—BOX Z727, MACHINERY, Clifton House, Euston Road N.W.1.



New & Used Machine Tools

COLCHESTER TRIUMPH Centre Lathe, fully equipped.
WILLSON 7 1/2 in. A.G.H. Centre Lathe.
COLCHESTER MASTER Centre Lathe.
NEWBY 14in. Stroke Shaper.
ALBA 25 Shaper, 14in. stroke.
CINCINNATI No. 2 Tool and Cutter Grinder. Mot. 400/3/50.
BROWN & SHARPE No. 13 Universal and Tool Grinder.
ELECTRISKA 1 1/2 in. cap. Geared 27in. Column Drilling Machine. (New.)
DENBIGH No. 3 M.T. Column Drill.
BLISS No. 20 Power Press, 1 1/2 in. stroke.
NORTON Hori. Spindle Surface Grinder, 36in. table with 24in. by 8in. mag. chuck.
ARCHDALE 14in. Horizontal Mill, 26in. by 8in. table, 3 available.
DENBIGH C4 Horizontal Mill with equipment.
PALLAS HO Horizontal Mill, 30 by 7 table. Motorised 400/3/50.

STRAIGHT & VINES LTD.

MINT STREET, BOROUGH,
LONDON, S.E.1.
Telephone: HOP 4364

STAINES MACHINE TOOL COMPANY

DAWSON Steam - Heated Chemical Cleaning Plant, 3ft. square, 21ft. long, complete with tanks, chain driven conveyor, reduction gear, roller conveyor, centrifugal pumps, steel framing, electrical equipment, cabinet and baskets. This plant is in excellent condition and offered £550 for early removal.

RIVERSIDE ESTATE, CAUSEWAY, STAINES

Telephone: Staines 2647

Herbert No. 13 Bar Turret
Lathe 2 1/2 in. capacity by 36in. long Atlas No. 1 Capstan Lathe, 1in. bar capacity Gisholt No. 14 simplified chucking capstan. All 400/3/50.—HICKS MACHINERY, LTD., 26, Addison Place, London, W.11. Tel.: PARK 2335.

SHEET METAL MACHINERY · MACHINE TOOLS · POWER PRESSES

A large range of all types IN STOCK—both NEW and USED. Send for particulars

F.J. Edwards Ltd

EDWARDS HOUSE
359-361 EUSTON ROAD
LONDON, N.W.1
Phones: Euston 4681 & 3771
and at **LANSDOWNE HOUSE**
41 WATER STREET
BIRMINGHAM, 3
Phone: CENTral 7606-8

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



USED LATE TYPE MACHINES

LATHES

LANG Late Type 8in. centre by 54in., in gap 28in. Norton Feed Box. Camlock Nose, heavy duty, motorised.
WILSON 7 1/2in. by 40in. gap bed, motorised.
BERRY A.G.H., 6 1/2in. centre by 32in., in gap 28in., motorised.
MITCHELL 7 1/2in. by 42in. by 25in. gap, A.G.H., motorised.
CHURCHILL CUB Lathe, 6in. by 24in., A.G.H., motorised 415/3/50.

CAPSTANS AND AUTOS

HERBERT 2D, bar feed, dead length chuck, motorised.
WICKMAN Auto, cap, 10mm., motorised.
WARD 2A, A.G.H., bar feed, motorised.
WARD No. 7 A.G.H. Bar feed, ball chuck, etc., motorised.
WARD 1A Capstans, 1in collet cap., H.S. range up to 4,130 r.p.m. Ball chuck, bar feed, mot., coolant pump, 400/440/3/50 A.C.
HERBERT 1S Capstans, 1in. collet cap. Draw-in collet and bar feed, 16 speeds 18/4,020 r.p.m. Hand feed turret and cross slide. Mot. coolant pump, 415/3/50.
HERBERT No. 0 Capstans, 1in. cap. Dead length air chucks, 12 speeds 93/6,000 r.p.m., mot., coolant pump, 415/3/50.
BOLEY & LEINEN Precision Capstan, Model S.R.26. Collet cap. 1in., mot. 415/3/50.

MILLING MACHINES

WADKIN High-speed Vert. Mill, table 12in. by 36in., mot. 415/3/50.
ARCHDALE 28in., table 49in. by 13in., mot. in base.
ARCHDALE 20in. Horizontal. Table 40in. by 10in. Dial type speed change 30 to 615 r.p.m. Dial feed. Mot. 415/3/50.
ARCHDALE 18in. High-speed Vertical WB30. Table 34in. by 10in., 6 speeds 500/2,000 r.p.m. Mot. 415/3/50.

GRINDING MACHINES

ABRASIVE Surface, No. 3, motorised, 24in. by 8in.
CHURCHILL Hyd. Vert. Surface (plough), cap. 18in. by 36in., segmental wheel 18in. dia. Humphrey mag. chuck, 12in. by 36in., mot. 415/3/50.
LANDIS Hydraulic Cylindrical Grinder, 12in. by 48in., mot., reconditioned.
NEUAL Hydraulic Cylindrical Grinder, 12in. by 24in., mot.
K.S. Internal Grinder, 1 1/2in. to 1 1/2in. dia., int. cap. Power feed to table, auto. sizing feeds, mot. 415/3/50. Late type machine, ex. con.
OLIVETTI Automatic Hydraulic Cylindrical Grinder. Type R4/1200, 14in. swing by 38in. between centres. Plunge cut. Mot. 415/3/50.

SHAPING MACHINES

ALBA 24in., motorised.
PRATT & WHITNEY Slotter, 5 1/2in. stroke, tilting ram.

PRESSES AND SHEET METAL, ETC.

RHODES Stagger Press, 25 ton, throat 24in.
OLIVER Quick Work Shear, cap. 1in., throa 30in.
RHODES Pluffed Hydraulic Guillotine, 6ft. by 14ft. Gauge. Micro stops.
THERMIC Muffle Furnace, 15in. by 24in. by 12in., gas heated pyrometer 1,000 deg. C.
T. & C. B1 and B2, motorised.
RHODES 40 ton inc., motorised.
BLISS No. 8, late type, motorised. £100.

DRILLING MACHINES

TOWN Radial 5ft. 0in., motorised.
PROGRESS Pillar 4E, motorised.

WILLIAM URQUHART

Head Office:—
 1023, Garratt Lane, London, S.W.17
 Showrooms:—
 Ace Works, Plough Lane, Tooting, S.W.17
 'Phone: WIMbledon 6341

As our stock
 changes very rapidly
 it is not possible
 to list weekly the
 machines actually available.

ELGAR

MACHINE TOOL CO. LTD.

172-178 Victoria Road, Acton, W.3.

(Opposite North Acton station.)

ACOR 5555

Over 250 new Machine
 Tools in stock.

ARCHDALE 42in. Radial Driller, 16 spindle speeds, 89 to 960 r.p.m. No. 4 Morse taper.

PARKES (MACHINE TOOLS) LTD.

WITTON ROAD, BIRMINGHAM, 6.

Tel.: EAST 1742.

50 Ton Fielding Downstroke

Hydraulic Press, 3ft. stroke.
 150 Ton Rhodes 18in. Stroke Double Sided Geared Power Press.

200 Ton Tanzye Hydraulic Straightening Press, bed 25ft. by 3ft., stroke 21in., motorised travelling table, 3 ram pump.

100 Ton Bigwood Motorised Geared Beam Bender up to 12in. by 6in.

Scriven 3-Roll Plate Bending Machine, rollers 14ft. wide, 1in. capacity.

Archdale 4ft. Radial Drilling Machine.

Herbert Filing and Sawing Machine, 15in. square, adjustable table.

Alexander 16in. Cutting-off Machine.

Herbert Hack saw, 13in. blade, belt driven.

Wicksteed Hack saw, 16in. blade, 6in. by 6in.

Rex Hack saw, 18in. blade, 8in. by 8in.

Colchester 7in. Centre Lathe, 7ft. gap bed.

Herbert Horizontal Milling Machine, 3ND table 61in. by 15in., 4 spindle speeds.

3,000 kg. Capacity Avery Hardness Testing Machines, 10in. dia. table (2).

50 Ton Inclinable Geared Open Press.

Crow Harvey Punch, Shears and Angle Cropper, 18in. blade, 27in. throat, heavy duty.

Fels Punch, Shears and Cropper, 12in. blade, shear 1in. takes 6in. by 6in. by 1in. angles.

Craig & Donald Billet Shears, 8in. blade 6in. by 1in. capacity.

Robertson Shears, 1in. capacity, 10 h.p., 28in. blade, 9in. maximum opening (2).

Robertson 7-roller Plate Flattener, 8ft. 6in. wide, approximately 1in. capacity.

Sedgewick 6ft. Folding and Bending Machine.

Landis Pipe Screwing Machine up to 12in. bore, also 2in. machine.

Berry 3-roller Plate Bender, 7ft. wide, approximately 1in. capacity.

Sweeney Fly Presses, all sizes, 20 available.

New 1-cwt. and 2-cwt. Hammers by Massey and Alldays & Onions, also 3/5 cwt. secondhand.

Oliver Planishing Hammer, 29in. gap.

E.O.T. Cranes.

60/5 ton Clyde Goliath, 40ft. span, unused.

40/5 ton Babcock Goliath, 40ft. span, unused.

40/5 ton Adamson, 42ft. 3in. span, almost new.

40 ton Clyde, 42ft. 3in. span, still packed.

30/5 ton Adamson, 42ft. 3in. span, almost new.

40 ton Vaughan, 42ft. 3in. span, almost new.

20/6 ton Vaughan, 42ft. 3in. span, cab type (6).

FRED WATKINS (ENGINEERING), LTD., Coleford, Glos. 'Phone: Coleford 2271 (3 lines).

Cashmores

Selection of Machine Tools
 from Stock or Early Delivery.

DRILLING MACHINES

JONES & SHIPMAN 15in. Two and Three Spindle Drilling Machines, No. 3 Morse Taper spindles, motorised 400/3/50 cycles.

KITCHEN & WADE 4ft. 0in. Sensitive Radial Drilling Machine, two-motor type, box bed, motorised 400/3/50 cycles.

LATHES

NILES TIMESAVER 17in. Centre Heavy Duty Lathe, 13ft. between centres, swing 26in. dia. over saddle, motorised 400/3/50 cycles.

SWIFT 15in. Centre Heavy Duty Lathe, 8ft. 0in. between centres, swing 24in. dia. over saddle, motorised 400/3/50 cycles.

FAIRBAIRN 16in. Centre Heavy Duty Lathe, 15ft. 0in. between centres, swing 23in. dia. over saddle, motorised 400/3/50 cycles.

LANG 15in. Centre Heavy Duty Lathe, 17ft. 6in. between centres, 2 saddles, swing 19in. dia. over saddles, motorised 400/3/50 cycles.

WARD No. 7 Covered Bed Capstan Lathe, arranged chuck work, motorised 400/3/50 cycles.

New MITCHELL 12 1/2in. Centre Gap Bed Lathe, admit 8ft. 9in. between centres, motorised 400/3/50 cycles.

HONING MACHINE

KITCHEN & WADE Vertical Hydraulic Honing Machine, capacity 2in. to 9in. dia. bores up to 29in. long, motorised 400/3/50 cycles.

SLOTTING MACHINES

BUTLER 14in. stroke Slotting Machine, 39in. dia. indexed rotary table, motorised 400/3/50 cycles.

MUIR 30in. Stroke Heavy Duty Slotting Machine, 50in. x 50in. tilting table, motorised 400/3/50 cycles.

BORING MACHINE

WALDRICH Heavy Duty Vertical Turret Lathe, fitted side head, maximum swing 66in. dia., motorised 400/3/50 cycles.

GRINDING MACHINES

CHURCHILL Model VXA Vertical Spindle Hydraulic Surface Grinder, table 72in. x 16 1/2in., segmental wheel 18in. dia., motorised 400/3/50 cycles.

LUMSDEN Model 911E Vertical Spindle Rotary Table Surface Grinder, 26in. dia. table, grinding wheel 18in. dia., motorised 400/3/50 cycles.

CHURCHILL Model OSB Horizontal Spindle Hydraulic Surface Grinder, 30in. x 8in. table, motorised 400/3/50 cycles.

CINCINNATI No. 2 Centreless Grinder, Filmatic bearings, motorised 400/3/50 cycles.

NORTON 12in. x 36in. Hydraulic Universal Grinder, motorised 400/3/50 cycles.

PRESSES

BLISS 400 Ton Knuckle Joint Press, stroke 2 1/2in., bed area 20in. x 20in., motorised 400/3/50 cycles.

MILLING MACHINES

ARCHDALE 30in. Vertical Dial Type Milling Machines, table 44in. x 14 1/2in., motorised 400/3/50 cycles.

BOHLE Heavy Duty Dial Type Universal Miller, table 55in. x 14in., motorised 400/3/50 cycles.

ARCHDALE 18in. Horizontal Dial Type Plain Miller, table 30in. x 10in., motorised 400/3/50 cycles.

SHAPING MACHINE

STEPTOE 24in. Heavy Duty Shaping Machine, size of table 24in. x 16in. x 18in. deep. Motorised 400/3/50 cycles.

MISCELLANEOUS

RUSSELL 24in. Hydraulic Cold Metal Sawing Machine cut up to 8 1/2in. rounds, motorised 400/3/50 cycles.

NORLE & LUND 22in. Hydraulic Cold Metal Sawing Machine, cut up to 7 1/2in. rounds, motorised 400/3/50 cycles.

MASSEY 3 Cwt. and ALLDAYS & ONIONS 1 Cwt. Pneumatic Power Hammers, motorised 400/3/50 cycles.

ADAMSON 30 Ton Overhead Electric Travelling Crane, 42ft. 3in. span, motorised 400/3/50 cycles.

CLYDE 5 Ton and **SMITH** 2 Ton Overhead Electric Travelling Cranes, 34ft. 0in. span, motorised 400/3/50 cycles.

JOHN CASHMORE LTD., GREAT BRIDGE, STAFFS. Tel.: Tipton 2181/7 (Also at NEWPORT, MON.)

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

MACHINE TOOLS SELECTIONS FROM LARGE STOCKS

KEARNS OC Horizontal Borer.
FRORIEP 48in. Vertical Borer, side head.
FENSCOTT 36in. Vertical Borer, side head.
BROWN & SHARPE No. 2 Vertical Miller.
CINCINNATI No. 2 Vertical Miller, dial type.
ARCHDALE 12in., 18in., 24in. and 30in. Vertical
Milers.
CINCINNATI 08 Auto Cycle Millers
KENT OWEN 1-14 Miller.
ARCHDALE 28in. Horizontal Miller.
RICHMOND 03 Universal Miller, 38in. by 9in.
EDGWICK No. 2 Simplicill, 37in. by 12in.

CLEVELAND 24in. Automation.
HERBERT No. 5 Auto. 18in. by 34in.
CONOMATIC 1in. 4-spindle Automatic.

ASQUITH 5ft. Radial Drill.
KITCHEN & WADE 4ft. 6in. Radial Drill.
ARCHDALE "O" Multi Drill.
POLLARD 12X Multi Drill.
HERBERT Type V Drill.
FOLLARD 4-spindle Sensitive Drill.
JONES & SHIPMAN 4in. Tapping Machines.
HULLER No. 3 Radial Tapper.

ORMEROD 26in. Slotter
BETTS 12in. Slotter.

OSTER 6in. Screwing Machine.

SNOW NC14 Face Grinder, 12ft. stroke.
HEALD 72 Sizenatic Duplex Internal Grinder.
CHURCHILL HRR Automatic Internal Grinder.
CHURCHILL 8in. by 16in. Semi-Universal
Grinder.
CHURCHILL 10in. by 24in. Universal Grinder.
CHURCHILL 12in. by 30in. Universal Grinder.
BROWN & SHARPE No. 2 Surface Grinder.
SNOW 24in. by 8in. Surface Grinder.
SNOW T-20 and T-14 Table Surface Grinders.
GARDNER 50in. Face Grinder.
New OLIVETTI 134in. Swing by 48in. Cylindrical
Grinders.
CHURCHILL 18in. by 6in. Plain Grinder.
MULTIMAT 74in. Capacity Centreless Grinder.
LANDIS 12in. by 32in. Crankshaft Grinder.
NEWALL 10in. by 48in. Model L.A. Hydraulic
Cylindrical Grinders.
VAN NORMAN 16in. Raceway Grinders.

New MITCHELL 164in. Lathe, 17ft. 6in. be-
tween centres.
New MITCHELL 144in. Lathe, 9ft. 9in. between
centres.
COLCHESTER Mascot 84in. Gap Bed Lathes.
HENDEY 14in. by 30in. Lathes.
WILLSON 74in. by 6ft. Gap Bed Lathes.
WARD No. 7 Capstan Lathe.
WARD 2A Capstans.
BARDONS & OLIVER No. 5 Capstan.
HERBERT 5H Capstan.
LIBBY 4A Capstan, bar feed, 24in.
HERBERT 2B Capstan, bar feed, 14in.
WARD No. 7 Combination Turret Lathe.
HEYLIGENSTADT 48in. Surfacing and Boring
Lathe.
CHURCHILL REDMAN 24in. Surfacing and
Boring Lathe.

ALEXANDER Broaching Machine, 40in. stroke.
SYKES V10 Gear Generators, 0in.-14in. capacity.
CHURCHILL Cleveland 6in. Rigid Hobber.
NOBLE & LUND 4in. 60in. Sawing Machines.
CLIFTON & WADDELL 13in. Sawing Machine.

Inspect under ideal conditions at
THE F.J.E. MACHINE CENTRE,
ISLINGTON PARK STREET.

Nr. HIGHBURY CORNER, LONDON. N.1.

F. J. EDWARDS LTD.,
359-361, EUSTON RD., LONDON, N.W.1
Telephone EUston 4681-3771.

And at Lansdowns House, 41, Water St.
Birmingham, 3. Telephone: Central 7606-8.

GLASS 94in. x 10ft. 6in. S.S. & S.C.
Gap Bed Lathe. All-gear self-contained
motor drive 220/380 volts, 3 phase, 50.
Admits 6ft. 6in. b.c., 2 1/2in. H.S. Swing
in gap 30in. dia. Q.C.G.B. for English
and Metric threads.

CHURCHILL REDMAN 7in. x 6ft. 6in.
S.S. & S.C. Gap Bed Lathe. All-gear
head clutch operated, with 400 volts,
3 phase, 50 cycles motor. Admits 3ft. 6in.
b.c., 1 1/2in. H.S. Swing in gap 26in. dia.
Semi-quick change gearbox and change
wheels for English and Metric threads.

HENDEY 6in. x 5ft. S.S. & S.C. Toolroom
Lathe. All-gear head, motorised
415/3/50, with "inching" control.
Admits 27in. b.c., 1in. H.S. Norton
Q.C.G.B.

Robey

4/6, Minerva Road, Park Royal,
LONDON, N.W.10.
Telephone: ELgar 4841-4842.

BLISS Double Action Power Press, punch stroke
16in., motor driven 400/3/50.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

Jones & Shipman No. 310
motorised Universal Tool and Cutter
Grinding Machine. Cap. 8in. x 16in. 2 h.p.
400/3/50 motor—LEE & HUNT LTD., Crocus
Street, Nottingham. Tel.: 84246

"B.I.C." No. 131 Longitudinal
Seam Welding Machine for sale.
Specially suited for work which may be fed into
the machine throat, side or straight seams on
cylinders or drums. All electrical equipment
suitable for 400 volts, 50 cycles. Maximum
power required 12 kW. Two thicknesses of
20 s.w.g. Number of heating speeds 8. Depth
of throat 24in.—Photo and details from F. J.
EDWARDS, LIMITED, 359, Euston Road,
London, N.W.1, or 41, Water Street, Birming-
ham, 3.

Weatherley Oil Gear Vertical
Branch, Mot., studs, etc. Type V.S.
12 x 30, room required, reasonable offer
accepted.—C. L. THOMAS, LTD., 18, Park
Avenue, Solihull 1281.

Jones & Lamson 24in. Swing
A.G.H. Turret Lathe. £255.
Herbert No. 3 Automatic. £100.
Parkinson Vertical Pillar Drill for billets. £65.
Lane A.G.H. 54in. Hollow Spindle Parting-off
Lathe. £295.
Pratt & Whitney Production Miller, H.D.
£250.
E.M.B. Airdraulic Riveter Press, 374in.
throat. £135.
Ruskin R2 20 ton Power Press, 400/3/50.
£235.
Federal 10 ton Ditto. £110.
J. & S. 6-spindle (in-line) Pillar Drill, 400/3/50.
£55.
S.P.P. CO., Walmer Road, Pakefield,
Lowestoft. (Tel.: Pakefield 110.)

Universal Miller with Profiling
Attachment. Post war. £400.—A.
McNAMARA & CO., New Line, Bacup, Lancs.
Phone: Bacup 946.

Pederson Plain Miller, All
gears, power feeds three ways. Mot.,
studs, etc., 40in. x 11in. Good condition.—
C. L. THOMAS, LTD., 18, Park Avenue,
Solihull 1281.

WIDDOWSONS

NEW BROADBENT 5ft. Vertical Boring and
Turning Mill, swing 70in. diameter. Ex-stock.

JUNGENTHAL KE1200 4ft. Swing Single
Column Turret Type Vertical Boring and
Turning Mill, with side head, 20 h.p. motor,
speeds 5-6 to 180 r.p.m.

SWIFT 4ft. Radial Drilling Machine. No. 4
Morse Taper Spindle, speeds 42 to 1,500 r.p.m.

JONES & SHIPMAN 20in. High Speed
Pillar Drilling Machine. No. 3 Morse Taper
Spindle.

FELLOWS No. 61 Spur Gear Shaping Machine,
capacity 35in. dia. external, 24in. dia. internal.

ADAMS U.S.A. No. 5 Horizontal Gear Hobbing
and Thread Milling capacity, 10in. dia., 49in.
long.

ONES & SHIPMAN 138. 10in. x 27in.,
Universal Grinding Machine, good equipment.

CHURCHILL OSB 60in. x 8in. Hydraulic
Horizontal Spindle Surface Grinding Machine,
magnetic chuck.

CHURCHILL OSB 40in. x 8in. Hydraulic
Horizontal Spindle Surface Grinding Machine.

CHURCHILL NB 18in. x 6in. Hydraulic
Horizontal Spindle Surface Grinding Machine.

SWIFT 154in. Centres Heavy Duty All Geared
Gap Bed S.S. & S.C. Lathe, admit 10ft.
between centres.

SWIFT 13in. Centres High Speed All Geared
Gap Bed S.S. & S.C. Lathe, admit 6ft. between
centres, speeds 8-800 r.p.m.

HOLBROOK Model "C" 16 8in. Centres
High Speed Tool Room Lathe, admit 36in.
between centres, speeds 26 to 1,200 r.p.m.

WARD No. 7 Combination Turret Lathe,
swing 16in. dia. over bed covers, excellent
equipment including bar feed gear.

MINGANTI Type 20-40P Hydraulic
Pre-Selector Bar Feed and Chucking Capstan
Lathe, fully equipped.

WARD, HAGGAS & SMITH 36in. Swing
Heavy Duty Boring and Surfacing Lathe.
Modern Machine.

CINCINNATI No. 3 OM Dial Type Horizontal
Milling Machine, table 624in. x 154in.,
backlash eliminator. As New.

ARCHDALE 28in. Plain Manufacturing Milling
Machine, table 49in. x 13in.

MILWAUKEE 4K Heavy Duty Vertical
Milling Machine, table 82in. x 18in., speeds
13-1,300 r.p.m.

MILWAUKEE 4H Heavy Duty Vertical Milling
Machine, table 74in. x 15in.

CINCINNATI No. 2 Dial Type High Speed
Vertical Milling Machine, table 524in. x
124in., power down feed head, speeds 20 to
1,500 r.p.m.

OSTER Model 326 6in. capacity Six-chaser
Pipe Screwing and Cutting-off Machine.
Unused.

CLIFTON & BAIRD No. 2 Hydraulic Heavy
Duty Cold Circular Sawing Machine, capacity
84in.

HERBERT

WIDDOWSON

& SONS LTD.
CANAL STREET, NOTTINGHAM

'PHONE 51891.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



PIDGEN BROS. LIMITED

HELMET ROW, OLD STREET, LONDON, E.C.1.

Telephone: CLerkenwell 6481

ALL MACHINES MOTORISED FOR 3 PHASE SUPPLY UNLESS OTHERWISE STATED

AUTOMATICS

CONOMATIC 4 Spindle.

CAPSTANS

HERBERT No. 4. Barfeed.
WARD No. 8 Combination. Serial R.
WARD 2A and 3A. Serial M.
GISHOLT No. 4 Simplified. 2in. cap.
DRUMMOND Model K, 1 1/2in. Bar feed.
HILLE R.H.15 1/2in. Bar feed.
ACCURATOOL 1in. Bar feed.
WARNER & SWASEY No. 2, 1in. Bar feed.
HERBERT No. 7 Combination Turret.
ACME SW Universal Turret, 2in. Bar feed.
LIBBY 4A, 2in. Bar feed.
MURAD 1in. Bar feed.
HAHN & KOLB RH25. 1in. bar. Unused.
SOUTHWARK No. 2. 1 1/2in. Bar feed.

DRILLS

DENBIGH 1in. type P7.
ARCHDALE 2 1/2in. Production.
HERBERT Type B Bench.
ARCHDALE 5ft. Radial. 3in. cap.
JONES & SHIPMAN 2-sp., 15in., No. 2 M.T.
JONES & SHIPMAN 15in. Speed Drill-Max.
CORONA 12AX. 1/2in. cap.
BOLEY Cluster Type.
15in. HERBERT Type C, No. 3 M.T.

ENGRAVERS

T.M.A. Cutter Grinder.
ALEXANDER No. 1, 3 Dimensional.
T.M.A. Type G 3 1/2 G.2.
LIENHARD Type 3R and 2.
T.T.H. Multi-Etcher.

FILING AND SAWING MACHINES

EDGWICK Filer.
RAPIDOR No. 1 Hacksaw.
WICKSTEED Cold Saw No. 1, 6in.

FOLDERS

BESCO 3ft. x 18 g. No. 5 Angle Bender.
KEETONA 4ft. x 14 g. Cramp.

GEAR CUTTERS

SYKES HV14 Hobber.
MAXICUT 7in. x 2in. x 6 D.P.
RAPIDAN No. 1 1/2, 2 1/2in. dia. gears.
FELLOWS "Hourglass."

GRINDERS (Tool)

ROWLAND 12 x 2 Single Wheel.
UNION 14in. and 10in. As new.

GRINDERS (Cylindrical)

TRUVOX 2 1/2 x 18.
FRANCIS 6 x 7.
PRECIMAX MPB 10 x 48.
MYFORD MG12. New.
PRECIMAX MPH Plain. 10 x 24.
PRECIMAX U.P.J. Universal. 12 x 48.
NORTON 18 Hy. Type C.
NORTON 10 x 36. Type C.

GRINDERS (Miscellaneous)

ALBA Tool and Cutter.
LE BLOND No. 2. T. & C.
JONES & SHIPMAN 310. T. & C.
J. & S. 12in. x 24in. 305 T. & C.
JONES & SHIPMAN Carbide.
HERBERT HUNT No. 4 Drill.

GRINDERS (Surface)

SNOW Table, 20in.
CHURCHILL OSB 40in. x 18in.
WRIGHT 8in. Table.
ROBOT 18 x 6.
SNOW P24. 24in. x 8in. Hyd.
ABWOOD 18 x 6 Vertical.

GRINDERS (Internal)

SMART & BROWN.
SAACKE Model VII, 1/2in.

GUILLOTINE

KEETONA 4ft. x 14 g. Power.

HONERS

KITCHEN & WADE Hydraulic.
SUNNEN Type LB.
BARNES No. 2 Horiz.

KEYSEATER

CARTER & WRIGHT No. 2, 24in. x 1 1/2in.

LATHES

RIVETT 608 S.S. & S.C.
SMART & BROWN Type L. Sec. Op.
COUTHURST Surfacing and Boring.
EDWARDS 12in. Spinning.
WILLSON 7 1/2in. x 3ft. S.S. & S.C.
BRADFORD 8in. S.S. & S.C.
RYDERMATIC No. 12 Multi Tool.
CARDIFF 7in. x 60in.
DENHAM 5 1/2in. S.S. & S.C.
LE BLOND 1 1/2in. x 16in. Prod.
SOAG-OXFORD 6 1/2in. x 24in. S.S. & S.C.
SOUTHBEND 9in. (Workshop), 14in.
LE BLOND Regal 10in. swing.

ROBEY SMITH No. 2 12in. Bevel Gear Planing Machine, with all equipment. Modern tool. Motor-driven 400/3/50.

PARKES (MACHINE TOOLS) LTD.

WITTON ROAD, BIRMINGHAM, 6.

Tel.: EAST 1742

Westminster Type C Single

Ended Sealing Machine for sale. Motorised machine for cleaning the edge of sheet metal prior to resistance welding. Sheets of any length can be passed through the machine. Sealing speed approximately 40/45ft. per minute. Size of table 3 1/2in. wide x 34in. long. Photo, etc., from F. J. EDWARDS LIMITED, 359-361, Euston Road, London, N.W.1, or 41, Water Street, Birmingham, 3.

1—(Type E1QA), 2 kVA Delapena.

Induction Heater, together with automatic control panel.

1—(Type E0) Ditto.

3—(Type W12A) 6 kVA Delapena Induction Heaters together with automatic control panel.

1—(Type E14) 10 kVA Delapena Induction Heater without voltage regulator.

BOX 2771, MACHINERY, Clifton House, Euston Road, N.W.1.

Compressors and Motors For

Sale. Two only. 1,440 r.p.m. Brush Induction Motors complete with starters, etc. Two only Reavell Two Stage HCSA6 Type H.P. Compressors, delivery 37 cu. ft. per min. at 720 r.p.m. Fifteen only Air Storage Bottles, 4ft. x 8in. dia. Reasonable price accepted for quick sale.—APPLY: FENDRY (PLASTICS), LTD., Bridge Works, Brentfield Road, N.W.10.

MILLERS (Horizontal)

BURNERS Bench Table 14 1/2 x 4.
CENTEC 2A.
US Multi Mills.
U.S. (Whitney Type) Production.
KEMPSMITH No. 1G.
BROWN & SHARPE No. 12 and 000 Prod.
CINCINNATI 08 and 1-18 Prod.
BROWN & SHARPE No. 2 Univ. Light.
SUNDSTRAND No. 00 Rigidmill.
BURKE. Table 16 x 3 1/2.
ARCHDALE 28in. Mfr.
CINCINNATI 3-24 Hyd.

MILLERS (Vertical)

RICHMOND VHM. Table 26 x 8.
ARCHDALE 30in. Table 48 x 12 1/2.
HERBERT ISS. Table 50 x 10 1/2.

POLISHING HEADS

CANNING 5 h.p.
PRESSES (Power)

BLISS No. 8.
BESCO TWO Bench, 4 ton.
O. & S. 30 tons Straightening.
BESCO EB4, 40 tons. New.
TAYLOR & CHALLENGER 10 tons.
RHODES No. 19. 10 tons.
SCHULER VZZ. 15 tons d/s gripper feed.

RIVETERS

HIGH SPEED Hammer 4A. 1/2in.
ROTORIVET No. 5 Hammer.
TURNER 1in. RS2A Spinning.

SCREWING MACHINES

OSTER 1in.-6in. Pipes No. 326.
ATLAS No. 2, 3in.-6in. (Unused)

SHAPERS

ANCO 6in. Precision.
24in. ROCKFORD Hyd.

TAPPERS

HERKE 1/2 Bench.
HERBERT No. 2 Flash.
SUPERIOR 1in.
JONES No. 26. 2 B.A.-1in.
THIEL Nos. 3 and 4.
J. & S. Electrotap, 1in.

THREAD MILLERS

FACKS Plain, cap. 3in. x 1in.
LEES BRADNER Mod. 40. 6 1/2in. H.M.
HANSON WHITNEY. 8in. x 40in.

No. 2 Kearns Standard Motor-
ised Hor. Boring and Facing Machine.
Will face up to 30in. dia. 24 spindle speeds.
Main table 48in. x 30in. Top table 36in. x 26in. Balanced head. Covered ways. Verner fitted. Facing head to outer steady 5ft. A.C. motor.—LEE & HUNT, LTD., Crocus Street, Nottingham. Tel.: 84246.

WARD No. 7 Combination Turret Lathe.
A.C. motor drive. Covered bed. With automatic ball chuck, bar feed, front and back toolpost.

HERBERT No. 9S Combination Turret Lathe.
A.C. motor drive, 4 1/2in. H.S. Very well equipped with chucks, tool-holders, etc.

NOBLE & LUND 11/16 "Fluifeed"
Cold Saw. Capacity 5in. diameter. A.C. motor drive.

4/6, Minerva Road, Park Royal,
LONDON, N.W.10.

Telephone: ELGAR 4841-4842.

Asquith Model OD1, 4ft. 6in.
Radial Arm Drill No. 5 M.T. 2-motor type, 4500.—A. McNAMARA & CO., New Line, Bacup, Lancs. Phone: Bacup 946.

When answering advertisements kindly mention MACHINERY.

J. W. LITHERLAND (MACHINE TOOLS) LTD.,
98, Brunswick Road, London, W.5.
Perivale 1831.

CONOMATICS

Being available Jan. 1st, 4 only, 4 spindle 2in. cap. Bar Automatics. Complete Bar Feed, motor 400/3/50. Equipped. Machines still working, and may be inspected under power. 1939-40 machines, reconditioned 1951.

Asquith H.K.1 Horizontal Duplex

Keyseater, serial 81433, table w/s 32in. x 7in., maximum keyway cut with autocrank at one setting 1in. x 6in. through 3in., six table speeds, auto feed to depth at each end of table stroke, spindle speeds 400 to 1,200 r.p.m., self-contained motor-driven machine 400/3/50, in good condition, £150.—E. SMITH (MACHINE TOOLS), LTD., 76, St. Lukes Road, Birmingham, 3. Tel.: CALthorpe 3761.

Manlove Alliott Mot. Oil Separ-
ator, 30in. bowl, foot brake, good condition, 400/3/50.—J. L. THOMAS, LTD., 18, Park Avenue, Solihull 1281.

Pollard 4 Spindle Driller. Ind.
Mot. No. 2 M.T. Heads mounted radially at 90 deg. Auto feeds.—WILCOX & CO., Bar Street, Birmingham, 19. Northern 1234/5

RING BELLS for machine tools

LEEDS 63-7398

CHURCHILL 24in. by 36in. Cylindrical Grinder. Dia. of work admitted 24in. by 36in. length. Hydraulic table feeds. Grinding wheel size 20in. dia. by 2in. face. M.D. 400/3/50.

HERBERT 33 Plain Miller. Table 38 $\frac{1}{2}$ in. by 10 $\frac{1}{2}$ in. Speeds 37 to 400 r.p.m. M.D. 400/3/50.

LECRA 18 ND Inclinable Press. Cap. 10 tons. Stroke 1 $\frac{1}{2}$ in. With strip feed. M.D. 400/3/50.

KANE & ROACH Model No. 1A Section Straightening Machine. Estimated cap. 1 $\frac{1}{2}$ in. dia. rounds in M.S. M.D. 400/3/50.

CLIFTON & BAIRD 24in. Automatic Cold Saw. Admits 24in. blades to cut 8in. rounds. Hydraulic clamping. Automatic hydraulic infeed for continuous cutting. M.D. 400/3/50.

OLIVER Quickwork Rotary Shear. Throat 30in. Cap. 12's gauge. M.D. 400/3/50.

OHIO 32in. Heavy Duty Drednought Crank Shaper. V-belt drive from 10 h.p. motor 440/3/50.

KENDALL & GENT Model 6-3 Screwing Machine. Cap. $\frac{1}{2}$ in. to 3in. bolts and 1in. to 6in. tubes. Tangential die head. M.D. 400/3/50.

RHODES No. 20 Ungear'd Inclinable Power Press. Built 1955. Cap. 18 tons. Stroke $\frac{1}{2}$ in. to 3 $\frac{1}{2}$ in. M.D. 400/3/50. Planing Machine, 10ft. by 3ft. by 3ft. Table 10ft. by 2ft. Rack driven. M.D. 400/3/50.

EDWARDS Nibbling Machine. Pedestal mounted. Throat 1 $\frac{1}{2}$ in. Estimated cap. $\frac{1}{2}$ in. in M.S. M.D. 400/3/50.

MILWAUKEE 2H Vertical Miller. Table 50in. by 10in. Long traverse 28in. Rapid power three ways. 16 speeds 35 to 1,400 r.p.m. M.D. 400/3/50.

HERBERT 155 Vertical Miller. Table 41in. by 10 $\frac{1}{2}$ in. Long traverse 30in. Eight speeds 51 to 700 r.p.m. M.D. 400/3/50.

ASQUITH Model LDP and HDP two-spindle profile Millers. Table 18in. by 15in. Speeds 250 to 3,000 r.p.m. M.D. 400/3/50.

FRITZ WERNER Model 2202 Plain Horizontal Miller. Table 63in. by 14 $\frac{1}{2}$ in. Quick power all ways. Speeds 19 to 960 r.p.m. M.D. 415/3/50.

DARLING & SELLARS 6A Combination Turret Lathe with plain bed. Speeds 750 r.p.m. Spindle bore 2 $\frac{1}{2}$ in. M.D. 400/3/50.

HERBERT No. 4 Chucking Capstan. Speeds to 1,000 r.p.m. Built 1946. Reconditioned. M.D. 400/3/50.

JONES & SHIPMAN Duplex Horizontal Keyway Cutting Machine. (Slot Hydro-mill.) Table 53in. by 10 $\frac{1}{2}$ in. with variable hydraulic traverses. Keyways cut up to 12in. long and 1in. wide. M.D. 220-440/3/50.

HURTH Type LF Keyseater. Table 40 $\frac{1}{2}$ in. by 10 $\frac{1}{2}$ in. Max. stroke of cutter head 6 $\frac{1}{2}$ in. Five speeds 250 to 1,000 r.p.m. M.D. 400/3/50.

JONES & SHIPMAN Fig. 310 Tool and Cutter Grinder. Cap. 8in. by 16in. with elevating and swivelling wheelhead, internal spindle, universal cutter head, chuck, etc. M.D. 400/3/50.

PRECIMAX M.P.L. 636 Hydraulic Plain Grinder. Max. wheel size 20in. dia. by 4in. face. Plunge feed to wheelhead. M.D. 400/3/50.

TAYLOR No. 2 Cutting-off Machine. Rotary tool type. For bars up to 4 $\frac{1}{2}$ in. dia. and tubes up to 6in. dia. max. M.D. 400/3/50.

KENDALL & GENT No. 3 Horizontal Broaching Machine. Screw operated. 20-ton pull. Max. stroke 50in. M.D. 400/3/50.

PETERMANN P.4 Single Spindle Automatic. Capacity $\frac{1}{2}$ in. with bar feed equipment. Electrics 220-380/3/50.

H. BELL (Machine Tools) LTD., Walter Street, LEEDS 4.

TAYLOR & CHALLEN 808 200-ton Power Press. 26in. between columns, area of bed 36in. x 26in., 3in. stroke.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

Archdale 28in. Horizontal Miller with vertical Attachment. 400/3/50.—**HICKS MACHINERY, LTD.**, 26, Addison Place, London, W.11. Tel.: PARK 2333.



Offer at Attractive Prices
**HIGH CLASS
HORIZONTAL BORERS
FROM STOCK**

KEARNS No. 5 Patent type, 5in. spindle covered bed, main table 48in. x 84in. Verniers.

KEARNS No. 4 Patent type, 4in. spindle, verniers, main table 42in. x 66in., distance 7 $\frac{1}{2}$ in.

KEARNS No. 3 Patent type, 3 $\frac{1}{2}$ in. spindle, covered bed, table 32in. x 60in., verniers, screwcutting.

RICHARDS HB.2 28in. spindle; fully reconditioned.

PEARNS RICHARDS No. 4 standard type, facing head only, table 60in. x 36in.; older machine but in good condition.

It's Cheaper to Buy Now

We specialise in rebuilding the heavier types of machine tools and would welcome your enquiries.

SOAG MACHINE TOOLS LTD.,
JUXON STREET, LAMBETH, LONDON, S.E.11.

'Phone: REliance 7201.

'Grams: Sotoolsag, London, S.E.11.

Richards No. 2 Horizontal Boring and Facing Machine. 400/3/50. £400.—**A. McNAMARA & CO.**, New Line, Bacup, Lancs. 'Phone: Bacup 946.

Robot 6in. x 18in. Horizontal Spindle Surface Grinder, auto traverse, self-contained machine, 400/3/50, complete with dust extractor and magnetic chuck, excellent condition. £250.—**E. SMITH (MACHINE TOOLS) LTD.**, 76, St. Luke's Road, Birmingham 5. Tel.: Calthorpe 3761.

Ravensburg Surfacing and Boring Lathe with Electronic-Hydraulic copying, model K.45. Maximum swing 57in., 12 speeds, 8.4 to 380. Copying traverse in one stroke cross 19 $\frac{1}{2}$ in., copying traverse in one stroke longitudinal 13 $\frac{1}{2}$ in. Used 20 months only.—**FTT LTD.**, Harpenden.

Kearns No. 2A Horizontal Borer. 30in. Quartering Table. 18in. Springfield Boring, Surfacing Lathe, approx. 1940 machines. Seen working.—10, Whitehall Lane, Slade Green, Kent.

Ward 3A B.F. B/c. No. 7 Spindle. 5 years old. Ward 2C B.F. B/c. No. 3 spindle, 1957. Lodge & Shipley Lathe. 30in. x 14in. swing. A.G.H. Motorised all 3 phase, space needed quickly. Offers.—Redhill 3478.

No. 3U "Adcock & Shipley" motorised all-gear'd Universal Milling Machine. Table 50in. by 12in., has long travel of 30in. Spindle speeds 20-1,400 r.p.m. Auto feed $\frac{1}{2}$ in.-50in. per min. all movements. Rapid traverse by separate motor. Good equipment. Post war machine.—**LEE & HUNT LTD.**, Crocus Street, Nottingham. Tel.: 84246.

Friction Screw Presses, 75 Ton and 100 ton for sale.—**ALAN-MARKOVITS LTD.**, Emblem House, Sussex Road, Hove. Tel. Hove 30003.

B.S.A. Automatics, $\frac{1}{2}$ in. Cap. long stroke, 2 available, one third size Good condition. £450 the pair.—**C. L. THOMAS LTD.**, 18, Park Avenue, Solihull 1281.

Ward 2A, 1 $\frac{1}{2}$ in. Bar Capstan Lathe. 400/3/50. Also Chucking Machine with raised centres. S.P.D.—**HICKS MACHINERY, LTD.**, 26, Addison Place, London, W.11. Tel.: PARK 2333.

POWER PRESSES FOR SALE

HORDEN, MASON & EDWARDS LM100 Gear'd, Open Front Power Press. 100 ton pressure, adj. stroke 1in.-6in., bed area 40in. x 33in., throat 13in., air balanced slide. 400/3/50.

RHODES Type 64-26 Double Sided Gear'd Power Press, 150 ton pressure, 18in. stroke, bed area 25in. x 37in., hole through bed 16in. x 13in., air operated friction clutch. 400/3/50.

TAYLOR & CHALLEN Type 1449 Double Sided Gear'd Power Press, 150 ton pressure, 10in. stroke, bed area 32in. x 28in. 400/3/50.

TAYLOR & CHALLEN Size 4 $\frac{1}{2}$ Toggle Drawing Press, Punch stroke 15in. Largest draw 7 $\frac{1}{2}$ in., largest blank admitted 18in. dia, bed area 24in. x 26in. 400/3/50.

RHODES No. 41 Double sided Gear'd Power Press, 250 ton pressure, 2in. stroke, bed area 32in. x 36in., hole through bed 14 $\frac{1}{2}$ in. dia., friction plate air operated clutch. 400/3/50.

RHODES No. 2 Double sided Gear'd Power Press, 75 ton pressure, 2in. stroke, bed area 26in. x 20in., hole through bed 14 $\frac{1}{2}$ in. x 14 $\frac{1}{2}$ in. 400/3/50. Roll feed attachment available for this machine.

TAYLOR & CHALLEN Size 31 Drawing Press, Punch stroke 10in., deepest draw 5in., bed area 22in. x 19 $\frac{1}{2}$ in., largest blank admitted 14in. dia. 400/3/50.

RHODES 218 Gear'd Inclinable Power Press, 60 ton pressure. 34in. stroke, bed area 30in. x 22in., Centre to back 9in. Tie rods, fully guarded. 400/3/50.

TAYLOR & CHALLEN Type S18 Double Sided Gear'd Power Press. 200 ton pressure, 8in. stroke, bed area 36in. x 26in., Hole through bed 18in. dia. 400/3/50.

SWEENEY & BLOCKSIDE No. 12 Open front Gear'd Power Press. 50 ton pressure, adj. stroke 2in.-5in., bed area 36in. x 22in. Hole through bed 12in. dia. 400/3/40. Fitted mechanical hand device.

HORDEN, MASON & EDWARDS Type RTP No. 2 115 ton pressure, bed area 32in. x 23in., hole through bed 19in. x 8in., max. depth of draw 10in. 400/3/50.

All modern machines, in excellent condition. Also in stock, full range of presses 10-60 tons.

STANCROFT LTD.

LANCASTER STREET, BIRMINGHAM, 4.

ASTon Cross 2235.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE contd.)

- BETTER TRY 600 FIRST !

for NEW AND USED PRESSES & SHEET METAL MACHINERY

New **BENNIE** 10ft. x 4in. Combined Plate Bending and Straightening Rolls, top roller 12in. dia., bottom rollers 10in. dia., outer or straightening roller 11in. dia.

New **BENTLEY** 250 ton capacity type G/15 Billet Shearing Machine, max. capacity 3 1/2 in. sq. M.S., air-operated clutch, automatic lubrication.

New **PEARSON** 8ft. x 4in. Electro Hydraulic Guillotine Shearing Machine of steel plate welded construction, 12in. gap in end frames.

New **STECO** 6ft. x 4in. Pyramid type Plate Bending Rolls, dia. of top roll 8 1/2 in., bottom rolls 7 1/2 in.

Used **BENNIE** All Steel Frame Section Cropping Machine, capacity 6in. x 6in. x 4in. angles at 90 deg. or 4in. x 4in. x 4in. at 45 deg., 1 1/2 in. round bars, 1 1/2 in. square bars.

New **HOLLMAN** Oil Hydraulic Bending and Straightening Press, capacity 315 tons, bed area 63in. x 25 1/2 in. Ram stroke 19 1/2 in.

Used **CRAIG & DONALD** 7 1/2/26 Straight Side Single Crank Geared Press, with 8in. stroke. Distance between columns 26in. Bed area 26in. x 38in.

Used **TAYLOR & CHALLEN** 40 tons capacity Open Front Rigid Power Press with 3in. stroke. Complete with Roll Feed Equipment and 2 speed motor drive.

Used **TAYLOR & CHALLEN** type 370 20 tons capacity Open Front Rigid Power Press with 2in. fixed stroke. Complete with Roll Feed Equipment, arranged for flat belt drive.

New **WEYBRIDGE** MS. 48 Medium type Rotary Gang Slitting Shears, max. capacity 6 cuts in 48in. x 4in. M.S.

New **BARNES** 6ft. x 4in. Upstroking Hydraulic Bending Press. Max. stroke 8in. 6in. gap in frames. 73in. between columns. 78in. overall bed.

New **RASKIN** R7 120 tons capacity Open Front Rigid Geared Power Press with adjustable stroke 2in. to 4 1/2 in. Bed area 35 1/2 in. x 24 1/2 in. Depth of throat 12 1/2 in.

ALL ARRANGED FOR MOTOR DRIVE
400-440/3/50.

**GEORGE COHEN
SONS & COMPANY LIMITED**
Sunbeam Road, London, N.W.10

Tel: Elgar 7222/7

Stanningley, Nr. Leeds.

Tel: Pudsey 224/1

MIDLAND

HERBERT O Capstan. Bar feed and tooling.

WARD O.E. Capstan. Bar feed and tooling.

WARD 7 Capstan. Bar feed and tooling.

HOLBROOK 9in. Lathe. Taper turning, etc.

PROGRES 20in. by 9ft. b.c. Gap Bed Lathe.

BROWN & SHARPE No. 2 Universal Grinder.

BIERNATZKI F.W. 2A Horiz. Miller. Table 55in. by 14in.

HERBERT 21 Combination Turret Lathe.

WEINGARTEN 4ft. 6in. by 4in. Swing Beam Folder.

CRAIG & DONALD 10ft. by 4in. Swing Beam Folder.

BUTLER 12ft. by 5ft. by 5ft. Planer. Three toolboxes.

KOLB 4ft. Radial Drill. Box Table.

ASQUITH 4ft. 6in. Radial Drill. Box Table.

G.S.P. 6ft. Radial Drill. Box Table.

CINCINNATI 1/18 Production Miller.

KEARNS No. 3 Horizontal Borer.

DALE 10in. by 5ft. 6in. S.S. & S.C. Lathe. Well equipped.

CHURCHILL REDMAN Double Ended Centring Machine. 6ft. between heads.

CHURCHILL REDMAN 12in. Facing and Boring Lathe. 40in. in gap. Taper turning.

ORMEROD 22in. Heavy Duty Shaper.

THE MIDLAND MACHINE TOOL CO

BRADLEY, BILSTON, STAFFS. Bilston 42471/7



One Newall No. 1
Jig Borer to the following brief
specification.

TABLE: 36in. by 24in.
SPINDLE NOSE TO TABLE: 32in.
QUILL MOVEMENT: 9in.

Fully rebuilt and guaranteed.
Supplied with complete electrical equip-
ment including control cabinet and motors
suitable for 400 volts 50 cycles 3 phase.

THE
NEWALL
USED MACHINE DIVISION
OUNDLE ROAD
ORTON LONGUEVILLE,
PETERBOROUGH
Telephone: 6116

TAYLOR & CHALLEN B.3 Inclination
Power Press, 40 tons pressure, 2in. stroke,
with roll feed and tie rods.

TAYLOR & CHALLEN No. 1220 In-
clination Power Press, 20 tons pressure,
3in. stroke. With automatic guards.

TAYLOR & CHALLEN No. 1220 In-
clination Power Press, 20 tons pressure,
blanking stroke 4in.

TAYLOR & CHALLEN B.1 1/4 Non-
inclination Power Press, 10 tons pressure,
blanking stroke 4in.



4/6, Minerva Road, Park Royal,
LONDON, N.W.10.

Telephone: ELGAR 4841-4842.

30in. Archdale Vertical Column

Drilling Machine with quick-acting
compound table. Flange-mounted motor, 5 h.p.
400-440/3/50. Speeds 60-1,500 r.p.m. Spindle
bored No. 5 M.T. Post-war machine.—LEE &
HUNT, LTD., Crocus Street, Nottingham.
Tel.: 84246.

Sciaky Type RAMC 2/40 Circum-
ferential or End Seam Pneumatic Welding
Machine for sale. Specially suitable for welding
the ends of cylinders or drums and for straight
runs. Pneumatic electrode pressure. Bottom
electrode wheel driven in either direction with
variable speed chain drive. Nominal rating
40 K.v.a. Capacity two thicknesses of 18 s.w.g.
Welding speed from 2 to 9ft. per minute. Depth
of throat 14 1/2 in.—Photo, etc., from F. J.
EDWARDS, LIMITED, 359-361, Euston Road,
London, N.W.1. or 41, Water Street, Birming-
ham, 3.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



NEW MACHINE TOOLS FROM STOCK

GRANOR OF HALIFAX 11in. Gap Bed Lathe, by 8ft. 0in. b.c. Hole in spindle 3 1/2in. dia. 400-440/3/50

MITCHELL OF KEIGHLEY 8 1/2in. Gap Bed Lathe by 5ft. 3in. b.c. 400-440/3/50.

MITCHELL OF KEIGHLEY 10 1/2in. Gap Bed Lathe by 5ft. 5in. b.c. 400-440/3/50.

MITCHELL OF KEIGHLEY 12 1/2in. Gap Bed Lathe by 6ft. 9in. b.c. 400-440/3/50.

EXCEL No. 3/12 Hydraulic Horizontal Spindle Surface Grinding Machine. Capacity 24in. by 8in. Coolant equipment Motorised 400-440/3/50.

VICTORIA V2 Vertical Milling Machine. Spindle speeds 32-1,050 r.p.m. Table 45in. by 11in. Table traverse 29 1/2in. 400-440/3/50.

VICTORIA U2 Universal Milling Machine. Spindle speeds 30-1,010 r.p.m. Table 45in. by 11in. Longitudinal traverse 30in. 400-440/3/50.

USED MACHINE TOOLS

STIRK Double Housing "Won-Worm" Single Spiral Drive, Planing Machine, capacity 8ft. 0in. x 50in. x 4 1/2in. 4 Toolboxes. Modern machine. Split Drive for 400/3/50. Almost new condition.

NORTON Horizontal Spindle Hydraulic Surface Grinding Machine, with hydraulic cross feed head. Capacity 48in. by 10in. Complete with D.C. magnetic chuck and generator. Coolant pump and fittings. 400-440/3/50.

HERBERT No. 4 Capstan Lathe, with draw-lack collet, and power feed to turret slide. 400-440/3/50

NEWALL Type L 10in. by 24in. Plain Grinding Machine. 400-440/3/50.

LE BLOND A.G.H. S. & S. Lathe, 15in. d.a. swing. 400-440/3/50.

HULLER No. 5 Vertical Tapping Machine. 400-440/3/50.

POLLARD 21A Single Spindle Vertical Production Drilling Machine.

ARCHDALE 18in. High Speed Vertical Milling Machine. Table size 38in. by 10in. Spindle speeds 79-2,000 r.p.m. 400-440/3/50.

DEAN, SMITH & GRACE 12in. Gap Bed Lathe by 3ft. 6in. b.c. 400-440/3/50.

BROWN & SHARPE No. 2 Light Plain Milling Machine, with dividing head, and universal vertical head. 400-440/3/50.

ARCHDALE 20in. Horizontal Plain Milling Machine, longitudinal feed 20in. 400-440/3/50.

WE UNDERTAKE RERUILDING OF ALL TYPES OF MACHINE TOOLS

**CENTAUR TOOL WORKS,
EYRE STREET, SPRING HILL
BIRMINGHAM, 18.**

Tel. EDGlaston (8) : Grams : 1118 & 1119 Capstan, Birmingham.



QUICKWORK No. 321 Motorised Rotary Shearing Machine with circle cutting attachment. Arranged motor drive for 400-440/3/50. Capacity 14 s.w.g. mild steel. Cuts circles from 6in. to 60in. diameter. Weight approximately 18 cwt.

BRADLEY & CRAVEN Power Geared Open Ended Guillotine Shearing Machine. Undercrank type. Capacity 84in. x 1in. Gap in open ends 4 1/2in. Fitted with automatic sheet hold-down and adjustable gauges.

BARHOPE Power Operated Double Geared Open Ended Guillotine Shearing Machine. Overcrank type. Arranged motor drive for 400/3/50. Capacity mild steel 4ft. x 1in. Weight approximately 50 cwt.

BESCO High Duty Double Geared Guillotine Shearing Machine. Overcrank type. Model R. Capacity 120in. x 1in. mild steel. Treadle operated clutch. Arranged motor drive for 400-440/3/50. Depth of gap 6in. Weight approximately 110 cwt.

Power Operated Geared Guillotine Shearing Machine. Undercrank type. Fitted with adjustable front and side gauges. Length of blades 40 1/2in. Maximum capacity approx. 18 s.w.g.

RECENT Power Operated Open End Guillotine Shearing Machine. Undercrank type. Arranged motor drive for 400/3/50. Complete with one spare pair of blades. Capacity 40 1/2in. x 16 s.w.g. Depth of gap 2in. Fitted with automatic sheet hold-down and front, back and side gauges.

BESCO 40in. Open End Treadle Guillotine. Capacity 18 s.w.g. mild steel. Complete with front, back and side gauges.

Photographs of the above are available. Very favourable Hire Purchase terms can be obtained.

MACHINE TOOLS, NEW AND USED,
Of Every Description. Attractive Prices.

F. J. EDWARDS LTD.
359-361, EUSTON RD., LONDON, N.W.1

Telephone: EUSTON 4681-3771.

And at Lansdowne House 41, Water St. Birmingham, 3. Telephone: Central 7606-8

Taylor Double Ended Milling machine, index table incorporated, in 1. Nearly new condition. Richmond hor. 26in. x 3in. Mot. all-g geared, power feeds.—C. L. THOMAS, LTD., 18, Park Avenue, Solihull 1281.

Myfords at Old Prices. No increases while stocks last so why not order now? Our policy saves you money.—PRODUCTION PROMOTION, 94, Camden Road, N.W.1.

Asquith 50in. H.D. Vertical Pillar Drilling, Boring and Tapping Machine. 12 speeds. 3 1/2in. cap. in steel. Modern Machine in first class condition, guaranteed. £585.—BOX Z769, MACHINERY, Clifton House, Euston Road, N.W.1.

New Wire Straightening Machine for sale. Motorised 400-440/3/50. All steel fabricated body on four wheels, for portable use. Capacity 4mm. to 12mm. with 5 hardened steel guide bushes for 4, 6, 8, 10 and 12 mm. wires. Straightening speed 80ft. per min.—Photo, etc., from F. J. EDWARDS, LTD., 359, Euston Road, London, N.W.1.

TATE

AUTOMATICS

Four **MANURHIN** Type GD.35 Second operation Hopper Feed Automatics (unused and in original crates).
ACME GRIDLEY 4 Spindle Auto, 4in. £125

HORIZONTAL BORING

DICKINSON 3in. Travelling Spindle Horizontal Borer No. 5 M.T. 45in. by 28in. main table, 10 h.p. motor or 400-440 volts 3 phase 50 cycles A.C. supply £595

LATHES

ACCURATOOL 4in. Capstan.
WARD, HAGGAS & SMITH 60in. Surfacing and Boring Lathe. (Good condition.)
LANG 10in. by 3ft. 6in. S.S. & S.C., 10 h.p.
HARRISON 7in. S.S. & S.C. £225
MITCHELL 6 1/2in. S.S. & S.C. (1952).
SIMMONS No. 2 1 1/2 Capstan with bar feed.
SMALLPEACE Lathe, multi-tool production.
WILLSON 7 1/2in.

GRINDING MACHINES

JONES SHIPMAN Fig. 1204 E.IUR 8in. by 22in. Universal (nearly new).
JONES SHIPMAN Fig. 138 10in. by 27in. Universal (1948).
MYFORD MGR 5in. by 9in. Internal-External.
Two **LUMSDEN** 70 LEOD Vert. cal. Surface, 48in. by 12in., with chuck, etc. From £850

MILLING MACHINES

CINCINNATI 4/36 Hydromatic.
VAN NORMAN No. 2 Horizontal and Vertical Milling Machine, 44in. x 10in.
VICTORIA U-3 Universal 50in. by 12in. with power feeds and rapid traverses and Vertical Head (very good condition).
COCHRANE & BLY No. 14 Universal Vertical Miller Shaper.
VICTORIA UO Mill (new).
CINCINNATI 4/36 Hydromatic Serial 4009/1 Excellent condition.
ARCHDALE 24in. Production, with Auto-cycle (1946).
CINCINNATI 30in. by 8in. Plain.
WADKIN LXA 36in. by 12in. Vertical.
PALLAS Model HO Plain, 30in. by 8in.
PALLAS Model HOO Plain, 22in. x 7 1/2in.
Two **SENIOR** Model M1 Plain Mills (new).
SMITH & COVENTRY 72in. by 15in. Heavy Duty Vertical (very low price).
EDGWICK 40in. by 10in. Horizontal.
VICTORIA U2R Universal Mill with vertical head.

DRILLING MACHINE

CORONA Model IAX Sensitive Box Column Drilling Machine, No. 1 M.T.

SAWING

E.H.J. Model 17 Bandsaw.
2 MELBO 6in. x 6in. hacksaws.

SHEET METAL

BROOKES 8ft. by 4in. Bending and Folding Machine.
BESCO Type F Size No. 8 4ft. Slip Bending Rolls.
HANDY 1in. Bar Cropping Machine. £10
HANDY 1in. Bar Bending Machine. £10
BESCO Type SH 42in. Hand Lever Shear. £75

**TATE MACHINE TOOL
CO. LTD.,**

6, NORTH END PARADE
OPPOSITE OLYMPIA,
LONDON, W.14.

Fulham 6563/4/5.

When answering advertisements kindly mention MACHINERY.

RING BELLS for machine tools

LEEDS 63-7398

HORDERN MASON & EDWARDS L70 geared
inclinable Power Press, 3in. stroke. Motor-
driven 400/3/50.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.

Crossley Power Automatic Wire
Straightening and Cutting-off machine for
sale. Spinner type straightener. Capacity up
to 1/4 in. diameter. To cut up to 3ft. 6in.,
5ft. 3in. and 7ft. 6in. in length or any length
within these sizes.—**F. J. EDWARDS LIMITED**,
359, Euston Road, London, N.W.1, or 41, Water
Street, Birmingham, 3.

AUCTION

By Order of the Minister of Supply



Messrs.
**FULLER HORSEY
Sons & Cassell**

have been instructed to offer for SALE BY
AUCTION in Lots at the ROYAL ARSENAL,
WOOLWICH, LONDON, S.E.18, on
MONDAY, 15th DECEMBER, 1958,
and following days, at 10.30 a.m. precisely each
day

ENGINEERS' MACHINE TOOLS MOTOR VEHICLES INDUSTRIAL EQUIPMENT & SURPLUS STORES

Including 2 Massey 3 and 5 cwt. PNEUMATIC
HAMMERS; S.S. & S.C. LATHES by Monarch,
Swift, Le Blond, Hendey, Craven, Niles, Dean,
Smith & Grace and Holbrook & Lang; CAP-
STAN and TURRET LATHES by Ward,
Herbert, Gleibert and Timbrell & Wright;
PLAIN, UNIVERSAL and SURFACE
GRINDERS by Lumsden, Herbert, Thompson
Brown & Sharpe and Churchill; RADIAL and
Drilling Machines, Cincinnati HORIZONTAL
PLANING MACHINE, 8ft. x 3ft. x 3ft.;
VERTICAL and HORIZONTAL MILLING
MACHINES by Archdale, Edgwick, Mann and
Herbert; METAL BANDSAWING MACHINES;
Drilling, Slotting, Hacksawing and Woodwork-
ing Machines; approximately 450 VEHICLES
including PACIFIC TRACTOR; 2 SCAMMELL
30 TON TRACTORS; HEAVY DUTY TRAIL-
ERS: 200 Bedford 3-ton Trucks, 22 Morris F.A.
T's fitted Winch, DENNIS 6 TON DIESEL
TRUCKS; DIAMOND "T" Breakdown
Vehicles; White Halftrack, Jeep, Light
Utilities and Trailers 70 B.S.A. Motor Cycles;
Fork Lift and Industrial Trucks; Diesel and
Petrol Electric Generating and Charging Sets;
Mobile Compressor Plants, Workshop Cranes,
large quantity of Engineers' Hand Tools and Tool
Kits; 600 TONS PONTON SPARES; Radio
and Electrical Stores and Equipment, 12,000
REELS RECORDING TAPE; 3,000 PAIRS
PRISMATIC BINOCULARS; Compasses; Tele-
scopes; Microscopes; Surveyors' Levels; Theo-
dolites; 20,000 KIT BAGS; large quantity of
DENIM and KHAKI DRILL CLOTHING;
10,000 ARMY GREATCOATS, and numerous
other effects.

Catalogue is, each, admitting two persons on
view days (Tuesday, Wednesday, Thursday and
Friday preceding sale) and one on Sale Days,
may be had, when ready, from the AUCTION-
EER'S OFFICES, Dept. X, 10 Lloyd's Avenue,
London, E.C.3.

Brown & Sharpe No. 13 Univer-
sal and Tool and Cutter Grinder, serial
3712, 8in. swing by 24in. between centres, power
and hand traverses, equipment includes—
universal motorised workhead, universal cutter-
head, ball bearing type internal grinding attach-
ment, centres, faceplate, electric coolant equip-
ment, etc., self contained machine 400/3/50,
good condition.—**E. SMITH (MACHINE
TOOLS), LTD.**, 76, St. Lukes Road, Birming-
ham, 5. Tel.: CALthorpe 3761.

Reed Prentice No. 5 Vertical
Mill, knee-less type, 60in. x 16in. table,
ex-toolroom. £900.—**A. McNAMARA & CO.**,
New Line, Bacup, Lancs. Phone: Bacup 946.

ARTICULATED VEHICLES FOR SALE

Leyland Beaver Tractor and
20-ton Low-loader Machinery Trailer,
17ft. well. K.O. Back Axle.—BOX 2651,
MACHINERY, Clifton House, Euston Road,
N.W.1.

MISCELLANEOUS FOR SALE

Universal Engineers, Complete
jobbing workshop—comprising 6in. x 34
B.G.S.S.C. Lathe, Hand shaping Machine,
sensitive pillar drill, grinder, welding and
blacksmith's equipment, usual hand tools,
benches, etc., 4 h.p. and 1 h.p. 230v. A.C.
motors, the whole housed in portable wooden
building approx. 15ft. x 11ft. Offers up to
£150 considered.—Apply **BULFORD LODGE**,
Heathside, Camberley.

By Order of the Liquidator, **PERCY PHILLIPS**,
Esq., F.A.C.C.A., F.C.I.S., re: VENTAIR
LIMITED and PARKS ENGINEERING
COMPANY LIMITED.

**HANWORTH LANE,
CHERTSEY, SURREY.**

HENRY BUTCHER & CO.
are instructed to offer for SALE BY AUCTION
in LOTS at THE WORKS on
MONDAY, 8th DECEMBER, 1958,
at ELEVEN A.M. the

SHEET METAL WORKING PLANT, STORES & EQUIPMENT

including
"KENDRICK" 6ft. BRAKE PRESS
"EDWARDS" 8ft. x 14in. POWER
BENDING ROLLS
"KIRCHIES" 8ft. POWER FOLDER
RADIAL and PILLAR DRILLING
MACHINES
POWER NIBBLERS: 4ft. FOLDERS
S.S. & S.C. LATHES
PORTABLE ARC WELDING SETS
POWER HACKSAWS: HAND FOLDERS
Double End Grinders: Polishing Spindles
Hand Shearing Machines
HEAVY DUTY BENDING ROLLS
Screw Fly Presses: Circle Cutters:
Tube Benders
BICYCLE PLANT: ELECTRIC MOTORS
ENGINEERS' SMALL TOOLS and
STORES

OFFICE FURNITURE and EQUIPMENT
"BEDFORD" 3-TON OPEN TRUCK
Catalogues (when ready), price 6d. each,
may be obtained of:
Messrs. **PERCY PHILLIPS & CO.**, Account-
ants and Auditors, 76, New Cavendish Street,
London, W.1, and of
Messrs. **HENRY BUTCHER & CO.**, 73,
Chancery Lane, London, W.C.2. Telephone:
HOLborn 8411 (eight lines).

SITUATIONS VACANT

If you do not wish your reply to any Box No.
advertisement in this section to be forwarded to
certain firms, please advise us. Your reply will
then be destroyed, but you will not be notified as
this would disclose the identity of the advertiser.

**THE POLYTECHNIC, 309 REGENT STREET,
W.1.
CIVIL AND MECHANICAL ENGINEERING
DEPT.**

Applications are Invited for the
post of CHIEF LABORATORY TECH-
NICIAN. Experience in the installation, use,
maintenance and repair of engines and hydraulic
machinery is desirable. This post could be
suitable for an ex-Service engineer.

Salary, £607 10s. by £30 to £727 10s. per
annum. Proficiency increments are also possible
beyond the scale.

Apply by letter, giving details of age, experi-
ence, etc., to the SECRETARY.

Estimator for Job Costing

Young man of 25/30 years required, pre-
ferably with experience of automatic screw
machine layouts.—**DAVIS & TIMMINS, LTD.**,
Billet Road, Walthamstow, E.17. LARKSWOOD
2313.

Works Manager Required by

well-established company within 50 miles
of London, for expanding works with approx-
imately 150 employees, engaged on the production
of Cutting Tools and Machine Tool components.

Applicants must be trained engineers with
previous experience of Works Management,
Work Study and the batch production of
Threading Tools.

Superannuation Scheme. Assistance with
housing if required.

Replies, stating age, experience and salary
required, to BOX Z734, MACHINERY, Clifton
House, Euston Road, N.W.1.

Setter Improver Wanted for

Swiss type automatics. N.W.10 area.—
BOX Z756, MACHINERY, Clifton House, Euston
Road, N.W.1.

Junior Engineer for Non-Ferrous

Component Production Estimating, must
make quick and accurate assessments of weight
and machining requirements from Drawings.
Experience of up to date Machining method as
applied to both Mass and Jobbing production
essential.—Full particulars to PERSONNEL
OFFICER, THE ANTI ATTRITION METAL
CO., LTD., Woodlands Park Works, Maidenhead,
Berks.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (SITUATIONS VACANT, contd.)

SANDVIK SWEDISH STEELS

LIMITED invite applications for the position of Foreman, in charge of the special tool making section. This is an important part of our rapidly expanding business, and only applications from trained men can be considered. The following conditions require to be fulfilled:—

AGE 35-40. Must have drive and initiative. Technical training up to National Certificate standard or equivalent. Practical experience on tool making, involving milling and grinding machine practice, preferably with special tool manufacture. Also have a working knowledge of Planning and Estimating Office procedure, and be able to operate a piece-work system of payment.

Position will be staff and pensionable. Ideal working conditions in modern well-equipped factory.

Apply in writing, stating full particulars, to:—Ref. P1/L, SANDVIK SWEDISH STEELS, LTD., Manor Lane, HALESOWEN, Birmingham.

Highly Paid, Secure and Interest-

ing posts are always available for technically trained men. Find out how you can put some letters after your name by preparing at home on "No Pass—No Fee" terms for A.M.I.Mech.E., A.M.I.Prod.E., A.M.S.E., City and Guilds, etc., etc. Full details of exams and hundreds of courses in all branches of Engineering, Draughtsmanship, Management and Automation Techniques, the benefits of our Employment Dept., and unique record of 95 per cent. successes are given in "Engineering Opportunities"—a valuable 148-page Guide which will reveal many chances you are now missing.—Write for your copy today (stating subject of interest)—FREE and without obligation, B.I.E.T., (Dept. 34a), 29, Wright's Lane, London, W.8

WORKS SUPERINTENDENT

Required for factory in the West of Scotland, at present engaged in light Mechanical and Structural Engineering.

Candidates preferably between the ages of 35 and 40 years, should be conversant with modern Management techniques and control systems. The successful candidate must be a sound production engineer with a good technical background and knowledge of modern developments in the manufacturing field. He must be able to delegate responsibility to his subordinates.

Preference may be given to candidates with previous experience which includes light electrical production techniques, and who are members of the Institution of Production Engineers or a similar professional body.

Contributory Pension and Free Life Assurance schemes in operation. This position gives scope for further advancement with an expanding organisation. Reply, giving full particulars of previous experience in chronological order, together with details of technical training, to **BOX Z744, MACHINERY, Clifton House, Euston Road, N.W.1.**

Draughtsman Required, Experi-

enced in the design of press tools for the mass production of precision pressings. Must have good knowledge of follow-on tools. Experience on Multi-slide machine an advantage. High salary is offered to Draughtsman with this experience.—**BOX Z748, MACHINERY, Clifton House, Euston Road, N.W.1.**

PRODUCTION ENGINEER

A VACANCY EXISTS FOR A FIRST-CLASS PRODUCTION ENGINEER ON THE ENGINEERING STAFF OF A LARGE AIRCRAFT COMPANY ENGAGED IN MANY ASPECTS OF PRECISION ENGINEERING INCLUDING THE MANUFACTURE OF GUIDED WEAPONS AND ELECTRONIC EQUIPMENT

The candidate to fill this position should be one with sound engineering knowledge, coupled with initiative and imagination and be capable of liaising with design teams to ensure the product design is maintained to maximum production standards and requirements.

The applicant should be conversant with modern light engineering methods, and production engineering as applied to economical production quantities of small precision mechanisms. Preference will be given to applicant with previous experience on the manufacture of GYRO ASSEMBLIES and SERVO MECHANISMS. THIS IS AN EXECUTIVE POSITION AND ASSISTANCE WITH HOUSING AND REMOVAL EXPENSES WILL BE MET BY THE COMPANY.

Write, giving full details of career, technical qualifications and salary required, etc., to

BOX Z.780, MACHINERY, Clifton House, Euston Road, N.W.1.

Machinery's SMALL advertisements bring BIG results

USE THIS FORM WHEN SENDING YOUR SMALL ADS. • FOR RATES SEE COMMENCEMENT OF CLASSIFIED AD. SECTION

"MACHINERY," Clifton House, Euston Road, London, N.W.1. 'Phone: EUSon 8441

You are authorised to insert the above for.....insertions. We enclose remittance according to the rates given on page 165

NAME

ADDRESS

3.12.58

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (SITUATIONS VACANT, contd.)

**GENERAL FOREMAN
MACHINE SHOP AND
TOOLROOM**

A well-known Engineering Company in the West of Scotland are, at present, undergoing internal re-organisation to improve their facilities and equipment prior to expansion.

There is a vacancy for a General Foreman to manage the Machine Shop and Toolroom, and applications are invited from suitable candidates not over 40 years of age, who must possess initiative and who are seeking a position with prospects for promotion.

Preference will be given to those with proved organising ability, a sound technical training and the capability of retraining and instructing adult operators. Contributory Pension and Free Life Assurance Schemes in operation.

Reply, giving full particulars of previous experience in chronological order, together with details of technical training to **BOX Z763, MACHINERY, Clifton House, Euston Road, N.W.1.**

REPRESENTATIVES**MACHINE TOOL
REPRESENTATIVE**

for the West Midlands and South West England required by **WADKIN LTD., Leicester** to specialise in the sale of their range of high speed machine tools. Applicants must be experienced machine tool sales engineers with a proved sales record. Basic machine shop training important. This is a permanent pensionable post offering good prospects.

Apply in writing
to Managing Director,

WADKIN LIMITED

**Green Lane Works,
LEICESTER**

Freelance Agents Required for the sale of well-introduced machine tools and workshop equipment in all areas except Birmingham and Yorkshire. Liberal commission and mileage allowance. Workshop experience required, car owner preferred.—**BOX Z445, MACHINERY, Clifton House, Euston Road, N.W.1.**

Free Lance Representative.

Small Company, S.W. London area, with surplus capacity available Vertical and Horizontal Mills—Shaper, etc., wishes to contact live wire representative to obtain capacity for same on commission basis.—**BOX Z655, MACHINERY, Clifton House, Euston Road, N.W.1.**

**COMPANY SELLING HIGH QUALITY
HEAVY DUTY MECHANICAL PRESSES**

Invites applications for the post of an

**EXPERIENCED SENIOR
SALES REPRESENTATIVE**

Full engineering training essential. Must be fully competent to discuss engineering details and applications of presses. Necessary be well introduced with major press users, including contacts highest level. Write, in confidence, giving full details, qualifications and experience to:

**BOX No. Z772, MACHINERY
Clifton House, Euston Rd., N.W.1.**

Yorkshire and Staffordshire

Livewire Agents required immediately by Progressive Company in the North East. Manufacturers of Precision Gauges, Jigs and Fixtures, Special Purpose Machines. Youthful and energetic approach is essential.—Applications in strict confidence to **BOX Z758, MACHINERY, Clifton House, Euston Road, N.W.1.**

Representatives Required by manufacturers of Machine Tools, Jigs, press tools, plastic moulds and special machines. London and home counties, areas North and South of Thames. Generous commission. Give details of experience, age, etc. Freelance considered if handling non-conflicting product.—**BOX Z782, MACHINERY, Clifton House, Euston Road, N.W.1.**

**SITUATIONS
WANTED**

Chief Inspector Seeks Appointment in London area. A.I.D., A.R.B., I.E.M.E. Approved.—**BOX Z709, MACHINERY, Clifton House, Euston Road, N.W.1.**

Showroom and Warehouse Manager, fifteen years control English and Foreign Machine Tools and accessories. Sales promotion, technical German, seeks position with prospects.—**BOX Z752, MACHINERY, Clifton House, Euston Road, N.W.1.**

Young Englishman, Well Educated, 18½, trained in large German machine tool factory, all shops and service, wishes to take a position with English company leading to sales executive position. Has very fluent technical German, and can demonstrate and service.—**BOX Z778, MACHINERY, Clifton House, Euston Road, N.W.1.**

Design Consultant, 48, Special Purpose Machinery and similar, seeks regular (full or part time) employment. Specialising in designing, Manufacturing and Demonstrating of whole job.—**BOX Z776, MACHINERY, Clifton House, Euston Road, N.W.1.**

Production and Mechanical

Engineer experienced in design special purpose machines modification or redesign of machine tools, automotive design and production gas turbines, heavy engineering etc.—**BOX Z722, MACHINERY Clifton House, Euston Road, N.W.1.**

Chief Engineer/Works Manager,

A.M.I.P.E., age 48, experienced in electrical mechanical and pneumatic engineering. Introduction of new lines covering all aspects of development and manufacturing methods, etc. Extensive knowledge of automatics, special purpose machinery. Experience of production methods in U.S.A.—**BOX Z781, MACHINERY, Clifton House, Euston Road, N.W.1.**

Machine Tool Engineer (50)

desires position of top level responsibility, preferably Sales function. Nation wide connection Continental and British machine tools. Past positions commanding £3,200 to £3,600 per year. Principals only, please.—**BOX Z729, MACHINERY, Clifton House, Euston Road, N.W.1.**

REPRESENTATIVE**Technical Representative/Sales.**

Yorkshire, M.I.Mech.E. Offers representation of highest integrity. Knowledge oil hydraulics.—**BOX Z757, MACHINERY, Clifton House, Euston Road, N.W.1.**

RECEIVED**TOO LATE FOR
CLASSIFICATION****PLANT WANTED****Universal Modern Grinding**

machine. Capacity approximately 10in. x 36in. Must be in first class condition.—Write **BOX Z773, MACHINERY, Clifton House, Euston Road, N.W.1.**

5-tool Bechler Automatics with

attachments. Please state type and serial numbers.—**BOX Z774, MACHINERY, Clifton House, Euston Road, N.W.1.**

Wanted: 8½in. Centre x 8ft. Gap

Bed—all geared head. Must be in first class condition and guaranteed.—**BOX Z783, MACHINERY, Clifton House, Euston Road, N.W.1.**

Wanted, Wheel Press, 400/600

tons capacity to admit 8ft. 0in. between tie-bars and 8ft. 12in. between ram and resistance head. Condition not important. Any suitable Press considered.—**BOX Z785, MACHINERY, Clifton House, Euston Road, N.W.1.**

Hydraulic Accumulator Wanted

—medium size—pressure approx. 2,000 lb. per square inch, with or without pump. Full particulars and price.—**BOX Z754, MACHINERY, Clifton House, Euston Road, N.W.1.**

CONTRACT WORK**Heat Treatment in All its**

Branches, A.I.D., A.R.B. and I.E.M.E. approved.—**HARMANS HEAT TREATMENTS LTD., 72, Brewery Road, London, N.7, North 4452.**


Capacity for Precision Work

available. Centre lathe turning, milling, grinding, and fitting.—**BLAGDON ENGINEERING CO., Blandon, Seaton Burn, Northumberland, near Newcastle-on-Tyne. Telephone: Stannington 243.**

When answering advertisements kindly mention MACHINERY.

INDEX TO ADVERTISERS—(continued from page 193)

	PAGE		PAGE		PAGE
P ase Manufacturing Co. Ltd., The	148	Martonair Ltd.	22	Selcon Machine Tool Co. Ltd., The	88
P erris, J. E. Ltd.	162	Maur Industries Ltd.	162	Seton Creaghe Engineering Ltd.	166, 167 & 170
P escod Ltd.	63	Maurall Engineering Co.	166	S hand, J. H. Ltd.	108
P irch Brown Tools Ltd.	58 & 59	Middleton Tool & Engineering Co. Ltd.	173	S heet Metal Engineering Co. Ltd.	150
P isher-Deane Eng'g. Co. Ltd.	142	Midland Machine Tool Co., The	178 & 188	S heffield Twist Drill & Steel Co. Ltd., The	8
P letcher Miller Ltd.	72	Midland Saw & Tool Co. Ltd., The	125	S helsmerline & Mulley Ltd.	170
P orrett, W. & Co. Ltd.	170	Millen, Edwin	178 & 180	S houlder Engineering Co. Ltd.	174
P uller, Horsey, Sons & Cassell	190	M ills, George (Engineers) Ltd.	126	S ilcoms	46
P U. London Ltd.	158	M ills, John & Co. (Llandilose) Ltd.	126	S immonds Aerossories Ltd.	42
		M itcham Jig & Press Tool Co. Ltd.	173	S impson, P. & Co.	179
G A. Precision Products Ltd.	172	M itchells Emery Wheel Co. Ltd.	97	S intered Products Ltd.	130
G ale, A. E. Ltd.	176	M odern Machine Tools Ltd.	37	S lack, Sellars & Co. Ltd.	128
G rantham, Paul & Co. Ltd.	78	M oore & Ellis (London) 1946 Ltd.	166	S limshy, Walter & Co. Ltd.	176
G ray, R. O.	184, 185, 187 & 188	M ortimer Engineering Co.	43, 142 & 160	S M.E.C. Ltd.	150
G R.M. Heat Treatments Ltd.	168	M oser Cams & Tools Ltd.	194	S mith & Netherwood Ltd.	166
G unn, D. A. (Eng'g) Ltd.	169	M otor Gear & Engineering Co. Ltd., The	161	S oag Machine Tools Ltd.	23 & 186
G uyson Industrial Equipment Ltd.	156	M P.J. Gauge & Tool Co. Ltd.	138	S ociete Genevoise Ltd.	6
		M ulhead Engineering Co. Ltd., The	73	S ommerfield, H. G. Ltd.	136
H allifax Rack & Screw Cutting Co. Ltd.	156	N aish Bros. & Co. Ltd.	173	S outhern Engineering & Machinery Co.	177
H anda, Eng'g.	172	N ell, James & Co. (Sheffield) Ltd.	90	S outhern Instruments Ltd.	104
H arper, John & Co. Ltd.	28	N ettlefold & Moser Ltd.	70	S outhwell, W. R. (Designs) Ltd.	166
H arrison, T. S. & Sons Ltd.	62	N ewall, Alexander S. Machine Tool Co. Ltd.	79	S parklets Ltd.	110
H atch, Geo. Ltd.	132	N ewall Group Sales Ltd.	52	S pectra Chemicals Ltd.	157
H ayes Engineers (Leeds) Ltd.	2	N ewall Used Machine Division	188	S peed Tools Ltd.	138
H enley Foundries Ltd.	156	N ewman Industries Ltd.	117, 155 & 181	S pinning & Sheet Metal (Guildford) Ltd.	152
H erbert, Alfred Ltd.	45 & 49	N orton, T. & Co. Ltd.	126	S taines Machine Tool Co.	182
H erbert, Edward G. Ltd.	114	N orton, W. E. (Machine Tools) Ltd.	177	S tancroft Ltd.	186
H ey Engineering Co. Ltd.	134			S tanley Machine Tool Co. Ltd., The	107
H igh Precision Equip. Ltd.	18			S tein Atkinson Vickers Hydraulics Ltd.	106
H igh Speed Service Tool Co. Ltd.	170 & 173			S tephens, R. & Son Ltd.	163
H indle Auto Products Ltd.	Inside Front Cover			S tevens & Bullivant Ltd.	136
H olland & Caesar Ltd.	171			S traight & Vines Ltd.	182
H untley & Sparks Ltd.	169			S tuart-Turner, S. M. & Co. (Surrey) Ltd.	171
				S urplice & Tozer Engineering Co. Ltd.	172
I de, C. F. Engineering Ltd.	162	P arkes (Machine Tools) Ltd.	179, 180, 182, 183, 184, 185, 186, 187 & 190	S ussex Rubber Co. Ltd.	158
I deal Hardening Co. Ltd.	168	P arkinson, J. & Son (Shipley) Ltd.	20	S ykes, W. E. Ltd.	38
I lllich, F. M. (Gears) Ltd.	166	P arneto Co. Ltd.	3		
I ncandescent Heat Co. Ltd., The	12	P el, Henry & Co. Ltd.	84		
		P hillips Electrical Ltd.	89		
J B. Machine Tool Co. Ltd.	177	P idgen Bros. Ltd.	123 & 184		
J esson, William & Sons Ltd.	139	P ipehawk & Engineering Ltd.	167		
J ohansson, C. E. Ltd.	68	P ollard, E. & Co. Ltd.	153		
J ones, A. A. & Shipman Ltd.	151	P owell, C. B. Ltd.	166		
J ones, E. H. (Machine Tools) Ltd.	177 & 187	P ower Petroleum Co. Ltd., The	83		
		P recision Heating Ltd.	167		
K ayser, Ellison & Co. Ltd.	94	P recision Products (Romford) Ltd.	165		
K entworth Manfgs. Co. Ltd., The	118	P reconomy Co. Ltd.	174		
K E.N.T. Machinery & Engineering Co.	178 & 182	P remier Screw & Repetition Co. Ltd.	152		
K ieserling, Th. & Albrecht	5	P resswork Products Ltd.	172		
K irk, Harry Eng'g. Ltd.	187	P rice, J. T. & Co. (Brass & Aluminium Foundries) Ltd.	7		
K itchen & Wade Ltd.	34	P rinde, Robert & Sons	7		
K laxon Ltd.	118	P urfection Engineering Co. (Coleshill) Ltd.	81		
K lockner Moeller England Ltd.	140				
K ubach, F. W. Ltd.	160				
L auden (Engineers) Ltd.	165	Q ualcut Tools Ltd.	141		
L andis Machine-Maiden Ltd.	32	R abstrick, J. E. Ltd.	177		
L ang Pneumatic Ltd.	131	R ansome & Marles Bearing Co. Ltd.	103		
L attimer, E. R. Ltd.	170	R atcliffe Tool Co. Ltd.	148		
L awrence, A. & Co. (Machine Tools) Ltd.	177	R ayner, Peter Ltd.	160		
L ayton, M. C. Ltd.	178	R eamin Engineering Works Ltd., The	170		
L enchs (Birmingham) Ltd.	174	R edcar Engineering Co. Ltd.	175		
L evy, B. & Co. (Patterns) Ltd.	168	R earch Engineers Ltd.	168		
L ewis Spring Co. Ltd.	193	R evolving Centres Ltd.	150		
L incoln Electric Co. Ltd.	9	R hodes, Joseph & Sons Ltd.	96		
L ip Industry	130	R ichards, George & Co. Ltd.	50		
L itherland, J. W. (Machine Tools) Ltd.	185	R .H. Tool & Equipment Co. Ltd., The	140		
L loyd, Richard Ltd.	14	R ockwell Machine Tool Co. Ltd.	25, 26 & 164		
L ubrication Equipment Ltd.	175	R odgers Bros. Ltd.	166		
L umsden Machine Co. Ltd.	143	R osser & Russell Ltd.	170		
		R otax Ltd.	4		
M acdonald Equipment Co. Ltd.	174	R oth, L.	180		
M achdow Publishing Co. Ltd., The	92, 110 & 158	R otheroe & Mitchell Ltd.	159		
M aher, J. W. & Son Ltd.	160	R owland, F. E. & Co. Ltd.	61		
M arbaix, Gaston E. Ltd.	29	R yder, Thomas & Son Ltd.	13		
M arbaix Industries Ltd.	24	R ye, Claude Bearings	175 & 177		
M arley, W. H. & Co. Ltd.	154	S ale, H. B. & Co. Ltd.	Inside Back Cover		
M arsden & Shiers Ltd.	172	S anders Bros. & Newbold Ltd.	109		
M arsden, W. G. Engineering Ltd.	172	S crew Machine Products Ltd.	94		
M artin Bros. (Machinery) Ltd.	179	S culford-Fockeley Vautier & Cie.	165		



CAMS, FORM TOOLS, CAM BLANKS

We design and manufacture complete tooling for all turret type and swiss-type automatic screw machines. Cam blanks supplied ex-stock. Cams machined to customers drawings


MOSER CAMS & TOOLS LTD., 465 HORNSEY ROAD, LONDON, N.19
TELEPHONE ARCHWAY 1766 and 7917



When answering advertisements kindly mention MACHINERY.

NUMBERING MACHINES

FOR ALL METALS



STAMPINGS

ALL KINDS
CARRYING INSCRIPTIONS
INCLUDING NAME PLATES
LABELS AND CHECKS



DIES FOR EMBOSSED AND FORMING METALS



NAMING PUNCHES

FOR METALS WOOD AND
PLASTIC
HOT OR
COLD
USE



H. B. SALE LIMITED
PROGRESS WORKS, SUMNER LANE, BIRMINGHAM
TEL. 011 241-1111

Grip


*The symbol of
supreme quality in*
JIG BUSHES

Britain's widest range covering over
5,000 sizes in nine types for
Standard, Glass Fibre, Plastic
and Plate Jigs.



TALBOT TOOL CO. LTD.
"GRIP" WORKS, ROEDALE RD.,
BRIGHTON, SUSSEX
Phone: Brighton 55822

CATALOGUE SENT ON REQUEST Sales Division



5M Maximum swing 7½". Swing over cross slides 6½". Independent motors for spindle drive and rapid motion to turret and cross slides. Wide range of speeds with three automatic changes. Suitable for small batch work.

95 Maximum swing 12½". Swing over cross slides 10½". Wide range of speeds and feeds. Three automatic speed changes. Headstock adjustable 4½" longitudinally. FIVE face turret; adjustable 2" along the bed.

FULLY AUTOMATIC apart from chucking. Air chucking is available in the range of additional equipment



	5M		95	
	ins	mm	ins	mm
Maximum swing	7½	197	12½	317.5
Maximum swing over cross slides	6½	168	10½	273
Cross slides stroke	2½	70	4	101.6
Cutting travel of turret	4½	111	5½	146
Number and range of spindle speeds	21 FORWARD 14 REVERSE 58 to 1458 r.p.m.		30 40 to 834 r.p.m. or 60 to 1220 r.p.m.	
Horse power of main motor	4½		10	

**BSA TOOLS LTD
BIRMINGHAM 33
ENGLAND.**

Cables: MADRICUT · BIRMINGHAM.

SOLE AGENTS GT. BRITAIN · BURTON GRIFFITHS & CO., LTD., · KITTS GREEN · BIRMINGHAM · STECHFORD 3071